

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE
NEW DELHI-110 001.


No. F.6/DFS/MS/GH/2013/827

Dated: 27/02/13

FIRE SAFETY CERTIFICATE

Certified that the Guest House **Kyron** located at 15A/45, W.E.A, Karol Bagh, New Delhi-110005 comprised of Basement, stilt floor, ground floor plus three upper floors, using basement as Two Hall/Storage, stilt floor as a parking, ground floor having five guest rooms and store, first, second and third floor each having six guest rooms respectively (Total Twenty Three guest rooms), A pantry for staff in a tin shed on terrace was issued NOC by this department vide letter No.F.6/DFS/MS/GH/2010/2806 dated 27.09.2010 in the name of Dream Land. Now the owner changing the name of the guest house from Dream Land to Kyron Guest House. The guest house building was re inspected by the officers concerned of this department on 13.02.2013 in the presence of Sh. Ajay Kumar Gupta and found that the owner have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the building/ premises is fit for occupancy class residential w.e.f. the date of issue of this certificate for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule-38 of the Delhi Fire Service Rules, 2010 printed overleaf.

Issued on.....27/02/13..... at New Delhi.


CHIEF FIRE OFFICER
DELHI FIRE SERVICE

Copy to:-

1. The Addl. Commissioner of Police (Lic.)
1st floor, P.S., Defence Colony, New Delhi.
(Re. No.735/Addl. C.P./Lic.(H), Dated 04.01.2013)
2. Sh. Manoj Kumar Tomar
Guest House Kyron,
15A/45, WEA, Karol Bagh, New Delhi-110005.

OK 

Following fire safety directives must be adhered to –

1. All the fire safety arrangements provided therein shall be maintained in good working condition at all times.
2. Any loss of life or property due to non- functional fire safety measures shall be at the risk & responsibility of the management.
3. The trained staff should be available round the clock.
4. Any deviation w.r.t. construction shall be verified by the concerned building sanctioning agency.
5. The basement shall be used strictly as per the provisions of the Building Bye Laws, 1983.
6. The certificate may not be treated in any case for regularization of unauthorized construction, if any.
7. The owner/occupier shall submit a declaration every year in form 'K' Provided in the first schedule of Delhi Fire Service Rules 2010, form is available on www.dfs.delhigovt.nic.in

M/S Basement, Stilt Floor, Ground Floor plus three Upper Floors.

INSPECTION REPORT

1. Name & address of the building : G.H Kyron, 15A/45, WEA, Karol Bagh, N.D.O.S.
2. Type of Occupancy : Residential (Guest House)
3. Type of Case : New Case/Renewal
4. Details of Previous NOC : Letter No. FG/DFS/MS/GH/2010/2806 Date 27.09.2010
5. Fire Safety directives letter No : N/A
6. Date of inspection : 13.02.2013
7. Name of Inspecting Officer : D.O H.L. Aneja & A.D.O P.S. Sahija
8. Name and designation of officers : Sh. Ajay Kumar Gupta
9. Year of Construction : Before 2010
10. Applicant's letter No. : 735/Addl.C.P./LIC.(H) dated 04.01.2013

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	NBC/BBL Requirement	Provided at site	Remarks
1.	Access to building			MR/NMR
	• Road width	Accessible	06 mtr	MR
	• Gate width	-	150 cms	MR
	• Width of internal road	-	-	-
2.	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases			
	• Upper Floors	One	One	MR
	• Basements	- do -	- do -	MR
	b. Width of staircases			
	• Upper Floor	-	125 cms	MR, Being a Old Case
	• Basements	-	130 cms	- do -
	c. Protection of exits			
	• Fire check door	N/A	-	-
	• pressurization	N/A	-	-
	d. No. of continuous staircases to terrace			
		-	One	-
	e. Width of Corridor			
		-	130 cms, 122 cms	-
	f. Door Size			
		-	86 cms x 202 cms	-
3.	Compartmentation			
	• Fire check door	N/A	-	-
	• Sealing of electrical shafts	-	Sealed	-
	• Fire Rating of shaft door	N/A	-	-
	• Water Curtain	N/A	-	-
	• Fire Dampers	N/A	-	-
4.	Smoke Management System			
	• Basements	30 a/c per hour	Exhaust fans are Provided	MR
	• Upper floors		Natural Ventilation	MR

N/6

		12 a/c per hour	-	-
5.	Fire Extinguishers			
	• Total numbers	12 Nos	Provided	MR
	• Types	CO ₂ , WCO ₂ , ABC	- do -	MR
	• IS marking	ISI marked	ISI Marked	MR
6.	First-Aid Hose Reels			
	• Total numbers on each floor	One	Provided	MR
	• Length of hose reel hose	30 m	- do -	MR
	• Nozzle diameter	5 mm	- do -	MR
7.	Automatic fire detection and alarming system			
	• Type of detectors	N/A	-	-
	• Location of Main Panel	N/A	-	-
	• Location of Repeater Panel	N/A	-	-
	• Alternate source of power	-	D.G. Set of 82.5 KVA	-
	• Hooters' Location	-	-	-
8.	MOEFA			
		Required	Provided	MR
9.	Public Address System			
		- do -	- do -	MR
10.	Automatic Sprinkler System			
	• Basement	Required	Provided	MR
	• Upper Floor	N/A	-	-
	• Sprinkler above false ceiling	N/A	-	-
11.	Internal Hydrants			
	• Size of riser/down-comer	N/A	-	-
	• Number of hydrants per floor	N/A	-	-
	• Hose Box	N/A	-	-
12.	Yard Hydrants			
	• Total number of hydrants	N/A	-	-
	• Hose Box	N/A	-	-
13.	Pumping Arrangements			
	• Ground Level			
	➤ Discharge of main Pump	N/A	-	-
	➤ Head of Main pump	N/A	-	-
	➤ Number of main pumps	N/A	-	-
	➤ Jockey Pump out put	N/A	-	-
	➤ Jockey pump head	N/A	-	-
	➤ Standby Pump out put	N/A	-	-
	➤ Standby Pump Head	N/A	-	-
	➤ Auto Starting/Manual stopping	N/A	-	-

N/7-

ISA/45, WEA, Karol Bagh,
New Delhi - 110005.

	<ul style="list-style-type: none"> ➤ Pump House Access • Terrace level ➤ Discharge of pump ➤ Head of the pump ➤ Power Supply ➤ Auto Starting of pump 	N/A	-	-
		450 LPM Each	540 LPM, 456 LPM	MR (02 Pump)
		30M Each	24 M, 30 M	MR (Being old Case)
		Required	Provided	MR
		-	-	-
14.	Captive Water Storage for fire fighting			
	<ul style="list-style-type: none"> • Underground tank capacity ➤ Draw-off connection ➤ Fire service inlet ➤ Access to tank • Overhead Tank capacity 	N/A	-	-
		N/A	-	-
		-	Provided	MR
		N/A	-	-
		10000 Ltr	10000 Ltr	MR
15.	Exit Signage.	Required	Provided	MR
16.	Provision of Lifts.			
	<ul style="list-style-type: none"> • Pressurization of Lift Shaft • Pressurization of Lift lobby • Communication In lift Car • Fireman's Grounding Switch • Lift Signage 	N/A	-	-
		N/A	-	-
		-	Provided	MR
		Required	- do -	MR
		- do -	- do -	MR
17.	Standby power supply	Required	Provided	MR
18.	Refuge Area.			
	<ul style="list-style-type: none"> ➤ Total Area ➤ Location 	N/A	-	-
		N/A	-	-
19.	Fire Control Room			
	<ul style="list-style-type: none"> • Detector System Panel • Flow Switch Panel • PA System Panel • Batter backup • Building Floor Plans 	N/A	-	-
		N/A	-	-
		N/A	-	-
		Required	Provided	MR
		N/A	-	-
20.	Special Fire Protection System for Protection of special Risks, if any:	N/A	-	-

N/8.

The fire protection systems provided in the building were test checked and found functional at the time of inspection.

Keeping in view the above substantial compliance of the minimum standards on fire prevention and Fire Safety measures required under the rules it is recommended to grant Fire Safety Certificate under rule 35 of Delhi Fire Service Rules 2010/ ~~issue shortcomings as noted at serial numbers.....~~

Note:- The previous NOC issued in the name of Dream Land vide letter No- F.6/DFS/MS/GH/2010/2806 dated 27.09.2010, Now the Owner Changing the name of the Guest House from Dream Land to Kyron Guest House. The Guest House having total 23 Rooms only.

[Handwritten Signature]

Signature of Inspecting Officer

Name H.L. Aneja

Designation Divisional Officer

[Handwritten Signature]

Signature of Inspecting Officer

Name P.S. Dahiya

Designation Asstt. Divisional Officer.