

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: NEW DELHI- 110 001

No. F6/DFS/MS/AH/2015/52/17

Dated: 06/01/15

FIRE SAFETY CERTIFICATE

Certified that the M/S The Krishna Green Farm House No.H-1, Pushpanjali, Dawarka Link Road, New Delhi-37, comprised of ground floor and open farm house owned/occupied by Sh. Ashok Kumar Dusad was granted NOC by this department vide letter No. F6/DFS/MS/H/09/794, dated 20-03-2009. The premises was re-inspected by the officer concerned of this department on 29-12-2014 in the presence of Sh. Ashok Kumar Dusad and found that the said farm house premises have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the premises is fit for occupancy class Assembly (Farm House) with effect from 06/01/2015 for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 06/01/15 at New Delhi by.



(Dr.G.C.Misra)

Chief Fire Officer

T.No.011-23414333



Copy to:-

- 1.Executive Engineer, Building Department, Najafgarh Zone, South Delhi
Municipal Corporation, Main Zonal Building, Room No.121-122, 1st floor,
Dhansa Stand, Najafgarh, New Delhi-43.
3. Sh. Ashok Kumar Dusad,
M/S The Krishna Green Farm House No.H-1, Pushpanjali, Dawarka Link Road, New Delhi-37.

Conditions for the validity of fire safety certificate are overleaf:-

INSPECTION REPORT

1	Name & address of the building	M/s The Krishna Green Farm House No.H-1, Pushpanjali, Dawarka Link Road, New Delhi.		
2	Type of Occupancy	Assembly building "D" Farm House.		
3	Type of case	Renewal		
4	Details of previous NOC	No.F6/DFS/MS/H/09/794, dated 20.03.2009.		
5	Fire safety directives letter No	Nil		
6	Date of inspection	29.12.2014.		
7	Name of the inspecting Officers	ADO Vedpal		
8	Name and designation of officers from the building side	Mr. Ashok Kumar Dusad (Properitor)		
9	Year of construction	2002		
10	Applicant's letter No.	No.EE(B)NGZ/14/D-1035	15.12.2014.	Ground floor only and open farm house.
S. NO.	Minimum Standards on fire prevention and fire safety U/R 33	Old NOC Requirement	Provided at site	Remarks MR / NMR
1	Access to building			
	1) Road width	Required	25 Mtr	MR
	2) Gate width	5 Mtr	Provided	MR
	3) Width of internal road	N/A	N/A	N/A
2	Number, width Type & arrangement of exits			
	a. Number of staircases			
	1. Upper floors	N.A.	N.A.	N.A.
	2. basements	N.A.	N.A.	N.A.
	b. Width of staircase			
	1. Upper floors	N.A.	N.A.	N.A.
	2. basements	N.A.	N.A.	N.A.
	c. Protection of exits			
	1. Fire check door	N/A	N/A	N/A
	2. Pressurization	N/A	N/A	N/A
	d. No. of continuous staircase to terrace	Required	One Provided	MR
	e. Width of corridor	N/A	N/A	N/A
	f. Door size	N/A	N/A	N/A
3	Compartmentation.			
	1. Fire check door	N/A	N/A	N/A
	2. Sealing of electrical shafts	N/A	N/A	N/A
	3. Fire Rating of shaft door	N/A	N/A	N/A
	4. water curtain	N/A	N/A	N/A
	5. Fire dampers	N/A	N/A	N/A
4	Smoke Management system.			
	basement	30 a/c per hour	12	N/A
	upper floors	a/c per hour		N/A
5	Fire Extinguishers			
	total numbers	08Nos. ABC,CO2 ISI	12 Nos. Provided	MR
	Types		ABC and CO2	MR
	ISI marking		ISI Mark	MR
6	First-Aid Hose Reels.			
	total numbers on all around	04nos.	07nos.	MR
	Length of Hose reel hose	30 Mtr	30mtr.	MR
	Nozzle Diameter	5mm	5mm	MR
	Automatic fire alarm and detection system			
	Type of detection	N/A	N/A	N/A
	Alarm system	N/A	N/A	N/A


7	Automatic fire detection and alarming system			
	Type of detectors	N/A	N/A	N/A
	location of Main Panel	N/A	N/A	N/A
	location of Repeater panel	N/A	N/A	N/A
	Alternate source of power	N/A	N/A	N/A
	hooter's location	N/A	N/A	N/A
8	MOEFA	Required	Provided	MR
9	Public Address System.	Required	Provided	MR
10	Automatic Sprinkler System.			
	basement	N/A	N/A	N/A
	upper floors	N/A	N/A	N/A
	sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	Size of riser/down-corner	N/A	N/A	N/A
	Number of Hydrants per floor	N/A	N/A	N/A
	hose Box	N/A	N/A	N/A
12	Yard Hydrants.			
	total number of hydrants	Required	07nos.	MR
	house box	Required	07nos.	MR
13	Pumping arrangements			
	1. Ground level			
	a. Discharge of main Pump	900lpm	900lpm	MR
	b. Head of main pump	40m	40m	MR
	c. Number of main pumps	01no.	01no.	MR
	d. jockey pump out put	N/A	180lpm	N/A
	e. jockey pump head	N/A	40m	N/A
	f. Standby Pump output	N/A	N/A	N/A
	g. Stanby Pump head	N/A	N/A	N/A
	h. Auto Starting/Manual stopping	Required	Provided	MR
	pump house access	Required	Provided	MR
	2. Terrace level			
	a. Discharge of pump	N/A	N/A	N/A
	b. head of the pump	N/A	N/A	N/A
	c. Power supply	N/A	N/A	N/A
	d. Auto starting of pump	N/A	N/A	N/A
14	Captive water storage for fire fighting			
	1. Underground tank capacity	50000Liters	50000Liters	MR
	a. Draw-off connection	N/A	N/A	N/A
	b. fire service inlet	N/A	N/A	N/A
	c. Access to tank	Required	Provided	MR
	Over head tank Capacity	10,000 Ltr	Provided	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of lifts.	No Lift Provided		
	a. Pressurization of lift shaft	N/A	N/A	N/A
	b. pressurization of lift lobby	N/A	N/A	N/A
	c. communication in lift car	N/A	N/A	N/A
	d. Fireman's grounding switch	N/A	N/A	N/A
	e. Lift signage	N/A	N/A	N/A
17	Standby power supply	Required	Provided	MR
18	Refuge Area.	Not Required		
	total area			
	location			

The Kirshana Green Farm House No -A-I Puspajali Dawarka link Road,

19	Fire control room		
	a. detector system Panel	N/A	
	b. Flow switch Panel	N/A	N/A
	c. PA system Panel	Required	N/A
	d. Batter backup	Required	Provided
20	e. Building floor plans	Required	MR
	Special Fire Protection systems for protection of special risks, if any:		
		N/A	MR
		N/A	N/A

The fire protection systems provided in the building were checked and found functional at the time of inspection.

In view of the deemed compliance of the minimum standards on fire prevention and fire safety required under the rules the NOC issued vide letter No.F.6/DFS/MS/H/09/794, dated 20.03.2009 renewal under rule 35 of the Delhi Fire Service Rule 2010 is recommended.
Accordingly DFA is put up for your approval and signature please.

 30/12/14

Signature of the Inspecting Officer

Name Vedpal

Design: ADO (SJ)

D.O. (South)

