

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE
NEW DELHI-110 001.**

E-mail:- cfohq.dlfire@nic.in

Fax:- 011-23412593


No. F.6/DFS/MS/GH/2015/ 52 /193

Dated: 10/02/15

FIRE SAFETY CERTIFICATE

Certified that the **Hotel Metro Continental** located at 15A/5, WEA, Karol Bagh, New Delhi-110005 is comprised of Basement, Ground Floor plus four upper floors, using basement as hall & office, ground floor as reception & shops, first, second & third floor each having 10 guest rooms respectively, fourth floor having 06 guest rooms (Total 36 guest rooms) and the terrace floor sealed by the owner was issued NOC by this department vide letter No.F.6/DFS/MS/GH/2012/761 dated 02.03.2012 owned/ occupied by Sh. Rishi Preet Singh. The guest house building was re- inspected by the officers concerned of this department on 31.01.2015 in the presence of Sh. Mahesh Kumar (Manager) and found that the owner have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the building/ premises is fit for occupancy class residential w.e.f. the date of issue of this certificate for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule-38 of the Delhi Fire Service Rules, 2010 printed overleaf.

Issued on.....10/02/15.....at New Delhi.



(DR. G.C. MISRA)
CHIEF FIRE OFFICER
DELHI FIRE SERVICE

Ph:- 011-23414333

Copy to:-

1. The Joint Commissioner of Police (Lic.)
1st floor, P.S., Defence Colony, New Delhi.
(Re. No.942/Joint C.P./Lic.(H), Dated 09.01.2015)
2. Sh. Rishi Preet Singh (Owner)
Hotel Metro Continental, 15A/5, WEA,
Karol Bagh, New Delhi – 110005.

Following fire safety directives must be adhered to:-

1. All the fire safety arrangements provided therein shall be maintained in good working condition at all times.
2. Any loss of life or property due to non-functional fire safety measures shall be at the risk and responsibility of the management.
3. The trained staff should be available round the clock.
4. Any deviation w.r.t. construction shall be verified by the concerned building sanctioning agency.
5. The certificate may not be treated in any case for regularization of unauthorized construction, if any.
6. The basement shall be used strictly as per the provisions of the building bye laws.
7. The owner/ occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rules 2010, form is available on www.dfs.delhigovt.nic.in
8. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry.

Basement, Ground Floor plus Four upper floors

N/27

INSPECTION REPORT

1. Name & address of the building : Hotel Metro Continental, ISA/S, WEA, Kaxal Bagh, N.D-05.
2. Type of Occupancy : Residential (Guest House)
3. Type of Case : New Case/Renewal
4. Details of Previous NOC : Letter No. F.6/DFS/MS/GH/2012/761 Date 02.03.2012
5. Fire Safety directives letter No : —
6. Date of inspection : 31.01.2015
7. Name of Inspecting Officer : D.O S.K. Tomar & A.D.O P.S. Dahiya
8. Name and designation of officers
From the building side : Sh. Mahesh Kumar (Manager)
9. Year of Construction : Before 1994
10. Applicant's letter No. : 942/Joint C.P/Lic. (H) dated 09.01.2015

| S. No. | Minimum Standards on fire prevention and fire safety U/R 33 | NBC/BBL Requirement | Provided at site | Remarks MR/NMR |
|--------|---|---|---|---|
| 1. | Access to building | | | |
| | <ul style="list-style-type: none"> • Road width • Gate width • Width of internal road / <u>Side Road</u> | <ul style="list-style-type: none"> Accessible - - | <ul style="list-style-type: none"> 09 mtr 125 cms 05 mtr Approx | <ul style="list-style-type: none"> MR MR MR |
| 2. | Number, Width, Type & Arrangement of Exits | | | |
| | a. Number of staircases | | | |
| | <ul style="list-style-type: none"> • Upper Floors • Basements | <ul style="list-style-type: none"> One - do - | <ul style="list-style-type: none"> One - do - | <ul style="list-style-type: none"> MR MR |
| | b. Width of staircases | | | |
| | <ul style="list-style-type: none"> • Upper Floor • Basements | <ul style="list-style-type: none"> 125 cms 125 cms | <ul style="list-style-type: none"> 134 cms 145 cms | <ul style="list-style-type: none"> MR MR |
| | c. Protection of exits | | | |
| | <ul style="list-style-type: none"> • Fire check door • pressurization | <ul style="list-style-type: none"> - - | <ul style="list-style-type: none"> - - | <ul style="list-style-type: none"> - - |
| | d. No. of continuous staircases to terrace | | | |
| | e. Width of Corridor | | | |
| | f. Door Size | | | |
| | | | <ul style="list-style-type: none"> One 131 cms, 150 cms 86 cms x 200 cms | <ul style="list-style-type: none"> - - - |
| 3. | Compartmentation | | | |
| | <ul style="list-style-type: none"> • Fire check door • Sealing of electrical shafts • Fire Rating of shaft door • Water Curtain • Fire Dampers | <ul style="list-style-type: none"> - - - - - | <ul style="list-style-type: none"> - Sealed - - - | <ul style="list-style-type: none"> - - - - - |
| 4. | Smoke Management System | | | |
| | <ul style="list-style-type: none"> • Basements • Upper floors | <ul style="list-style-type: none"> 30 a/c per hour | <ul style="list-style-type: none"> Exhaust Fans are Provided Natural Ventilation | <ul style="list-style-type: none"> MR MR |

| | | | | |
|-----|---|------------------------------------|--------------------|----|
| | | 12 a/c per hour | - | - |
| | Fire Extinguishers | | | |
| | • Total numbers | Two at each floor | Provided | MR |
| | • Types | CO ₂ , WCO ₂ | - do - | MR |
| | • IS marking | ISI marked | ISI Marked | MR |
| | First-Aid Hose Reels | | | |
| | • Total numbers on each floor | One | Provided | MR |
| | • Length of hose reel hose | 30 m | - do - | MR |
| | • Nozzle diameter | 5 mm | - do - | MR |
| | Automatic fire detection and alarming system | | | |
| | • Type of detectors | - | - | - |
| | • Location of Main Panel | - | - | - |
| | • Location of Repeater Panel | - | - | - |
| | • Alternate source of power | - | D.G. Set of 62 kVA | - |
| | • Hooters' Location | - | - | - |
| 8. | MOEFA | Required | Provided | MR |
| 9. | Public Address System | - do - | - do - | MR |
| 10. | Automatic Sprinkler System | | | |
| | • Basement | Required | Provided | MR |
| | • Upper Floor | - | - | - |
| | • Sprinkler above false ceiling | - | - | - |
| 11. | Internal Hydrants | | | |
| | • Size of riser/down-comer | - | - | - |
| | • Number of hydrants per floor | - | - | - |
| | • Hose Box | - | - | - |
| 12. | Yard Hydrants | | | |
| | • Total number of hydrants | - | - | - |
| | • Hose Box | - | - | - |
| 13. | Pumping Arrangements | | | |
| | • Ground Level | | | |
| | ➤ Discharge of main Pump | - | - | - |
| | ➤ Head of Main pump | - | - | - |
| | ➤ Number of main pumps | - | - | - |
| | ➤ Jockey Pump out put | - | - | - |
| | ➤ Jockey pump head | - | - | - |
| | ➤ Standby Pump out put | - | - | - |
| | ➤ Standby Pump Head | - | - | - |
| | ➤ Auto Starting/Manual stopping | - | - | - |

M/29.

ISA/S, WEA, Karol Bagh,
New Delhi - 110005.

| | | | | |
|-----|---|----------|----------|--------------|
| | <ul style="list-style-type: none"> ➤ Pump House Access • Terrace level ➤ Discharge of pump ➤ Head of the pump ➤ Power Supply ➤ Auto Starting of pump | - | - | - |
| | | - | 450 LPM | MR, Old Case |
| | | - | 30 M | MR, Old Case |
| | | Required | Provided | MR |
| | | - | - | - |
| 14. | Captive Water Storage for fire fighting | | | |
| | <ul style="list-style-type: none"> • Underground tank capacity ➤ Draw-off connection ➤ Fire service inlet ➤ Access to tank • Overhead Tank capacity | - | - | - |
| | | - | Provided | MR |
| | | - | 5000 Ltr | MR, Old Case |
| | | Required | Provided | MR |
| 15. | Exit Signage. | | | |
| 16. | Provision of Lifts. | | | |
| | <ul style="list-style-type: none"> • Pressurization of Lift Shaft • Pressurization of Lift lobby • Communication In lift Car • Fireman's Grounding Switch • Lift Signage | - | - | - |
| | | - | Provided | MR |
| | | Required | -do- | MR |
| | | -do- | -do- | MR |
| | | Required | Provided | MR |
| 17. | Standby power supply | | | |
| 18. | Refuge Area. | | | |
| | <ul style="list-style-type: none"> ➤ Total Area ➤ Location | - | - | - |
| | | - | - | - |
| 19. | Fire Control Room | | | |
| | <ul style="list-style-type: none"> • Detector System Panel • Flow Switch Panel • PA System Panel • Batter backup • Building Floor Plans | - | - | - |
| | | - | Provided | - |
| | | - | - | - |
| 20. | Special Fire Protection System for Protection of special Risks, if any: | - | - | - |

The fire protection systems provided in the building were tested, checked and found functional at the time of inspection.

In view of the deemed compliance of the minimum standards of fire prevention and fire safety measures as required under the rules the NOC issued vide letter no.

F.6/DFS/MS/GH/2012/761 dated 02.03.2012 renewal under rule 35 of the Delhi Fire Service rules 2010 is recommended.

Note:- The top floor of the Guest house is sealed by the owner as per affidavit submitted vide dated 08.12.2004 which is placed in the file.

S.K. Tomar
3/2/15

Signature of Inspecting Officer

Name S.K. Tomar

Designation Divisional Officer

P.S. Dahiya
2/2/15

Signature of Inspecting Officer

Name P.S. Dahiya

Designation Asstt. Divisional Officer