

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEAD QUARTERS: DELHI FIRE SERVICE: NEW DELHI - 110001

No F 6 / DFS / MS / 2016 / *School/w2/1105*

Dated: *1/7/2016*

FIRE SAFETY CERTIFICATE

Certified that the Ryan International School located at plot no. G-2 (Adjacent building), Sec-11, Rohini, Delhi-110085 comprised of ground and one upper floors owned/occupied by the Ryan International School have complied with the fire prevention and safety requirements in accordance with requirements of circular issued by Director of Education letter no 3298-3398 dated 01.03.2011 and verified by the officer concerned of Fire Service on 22.06.2016 in the presence of Smt. Mamta Nanda (Principal) and that the building/premises is fit for occupancy Group B Educational with effect from *...1/7/16* for a period of three years, subject to compliance of the conditions mentioned below:

**Conditions for the validity of Fire Safety Certificate:**

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director of Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on [WWW.dfs.Delhigovt.nic.in](http://WWW.dfs.Delhigovt.nic.in)

Issued on *...1/7/16* at New Delhi

*[Signature]*  
*1/7/16*

(Atul Garg)

Chief Fire Officer  
Ph:-011-23414250

Copy to :-

1. The Director, Education, Government of N.C.T of Delhi. Old Sectt. Delhi - 54.
2. The Principal, Ryan International School located at plot no.G-2 (Adjacent building), Sec-11, Rohini, Delhi-110085..

**SPECTION REPORT**

1. Name & address of the building : Ryan International School, G-2 ( Adjacent bldg). Sec- 11, Rohini, Delhi- ( G +01 Floors)
  2. Type of Occupancy : Educational
  3. Type of Case : New Case
  4. Details of previous NOC : Nil
  5. Fire Safety directives letter No : Director of Education Letter dated 01.03.2011.
  6. Date of inspection : 22/06/2016
  7. Name of the Inspecting Officers : Rajesh Kumar, ADO (RN)
  8. Name and designation of officers from the building side : Smt. Mamta Nanda/ Principal
  9. Year of Construction : 2005
  10. Applicant's letter No. : Nil dated 26.05.2016
- Plot Area-799.89 Sqm    Covered area ---532.34 sqm ,    No of student—250 nos,    Total class room --10nos

	Minimum Standards on fire prevention and fire safety U/R 33	Dir of Education Circular dated 01.03.2011	Provided at site	Remarks MR/NMR
1	<b>Access to building</b>			
	• Road width	6m	9m (approx)	MR
	• Gate width	4.5m	4.5m	MR
	• Width of internal road	NA	NA	NA
2	<b>Number, Width, Type &amp; Arrangement of Exits</b>			
	<b>a. Number of staircases</b>			
	• Upper Floors	01	01	MR
	• Basements	NA	NA	NA
	<b>b. Width of staircases</b>			
	• Upper Floors	1.50 m	1.50m	MR
	• Basements	NA	NA	NA
	<b>c. Protection of exits</b>			
	• Fire check door	NA	NA	NA
	• Pressurization	NA	01no	NA
	d. No. of continuous staircases to terrace	NA	NA	NA
	e. Width of Corridor	1.0m	1.0m	MR
	f. Door Size			
	3	<b>Compartmentation.</b>		
• Fire check door		NA	NA	NA
• Sealing of electrical shafts		NA	NA	NA

*AM*

	<ul style="list-style-type: none"> <li>• Fire Rating of shaft door</li> <li>• Water Curtain</li> <li>• Fire Dampers</li> </ul>	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
4	<b>Smoke Management System.</b>			
	<ul style="list-style-type: none"> <li>• Basements</li> </ul>	30 a/c per hour	No basement	NA
	<ul style="list-style-type: none"> <li>• Upper floors</li> </ul>	12 a/c per hour	Natural Ventilated	MR
5	<b>Fire Extinguishers</b>			
	<ul style="list-style-type: none"> <li>• Total numbers</li> </ul>	04 nos	09 nos	MR
	<ul style="list-style-type: none"> <li>• Types</li> </ul>	ABC/Co2	ABC--09	MR
	<ul style="list-style-type: none"> <li>• ISI marking</li> </ul>	Yes	Yes	MR
6	<b>First-Aid Hose Reels.</b>			
	<ul style="list-style-type: none"> <li>• Total numbers on each floor</li> </ul>	NA	Provided- 01	NA
	<ul style="list-style-type: none"> <li>• Length of hose reel hose</li> </ul>	NA	Provided 30m	NA
	<ul style="list-style-type: none"> <li>• Nozzle diameter</li> </ul>	NA	Provided 5mm	NA
7	<b>Automatic fire detection and alarming system</b>			
	<ul style="list-style-type: none"> <li>• Type of detectors</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Location of Main Panel</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Location of Repeater Panel</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Alternate source of power</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Hooters' Location</li> </ul>	NA	NA	NA
8	<b>MOEFA</b>	NA	NA	NA
9	<b>Public Address System.</b>	NA	NA	NA
10	<b>Automatic Sprinkler System.</b>			
	<ul style="list-style-type: none"> <li>• Basement</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Upper Floor</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Sprinkler above false ceiling</li> </ul>	NA	NA	NA
11	<b>Internal Hydrants</b>			
	<ul style="list-style-type: none"> <li>• Size of riser/down-comer</li> </ul>	NA	01 DC system	NA
	<ul style="list-style-type: none"> <li>• Number of hydrants per floor</li> </ul>	NA	01	NA
	<ul style="list-style-type: none"> <li>• Hose Box</li> </ul>	NA	01	NA
12	<b>Yard Hydrants.</b>			
	<ul style="list-style-type: none"> <li>• Total number of hydrants</li> </ul>	NA	NA	NA
	<ul style="list-style-type: none"> <li>• Hose Box</li> </ul>	NA	NA	NA
13	<b>Pumping Arrangements.</b>			
	<ul style="list-style-type: none"> <li>• Ground Level</li> </ul>			

M/12

	<ul style="list-style-type: none"> <li>➤ Discharge of main Pump</li> <li>➤ Head of Main pump</li> <li>➤ Number of main pumps</li> <li>➤ Jockey Pump out put</li> <li>➤ Jockey pump head</li> <li>➤ Standby Pump out put</li> <li>➤ Standby Pump Head</li> <li>➤ Auto Starting/ Manual stopping</li> <li>➤ Pump House Access</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
	• Terrace level			
	➤ Discharge of pump	NA	450 lpm	NA
	➤ Head of the pump	NA	Provided	NA
	➤ Power Supply	NA	Provided	NA
	➤ Auto Starting of pump	NA	Provided	NA
14	<b>Captive Water Storage for fire fighting.</b>			
	• Underground tank capacity	NA	NA	NA
	➤ Draw-off connection	NA	NA	NA
	➤ Fire service inlet	NA	NA	NA
	➤ Access to tank	NA	NA	NA
	• Overhead Tank capacity	NA	5,000ltrs	NA
15	<b>Exit Signage.</b>	Required	Provided	MR
16	<b>Provision of Lifts.</b>			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication In lift Car	N/A	N/A	N/A
	• Fireman's Grounding Switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17	<b>Standby power supply</b>	N/A	N/A	N/A
18	<b>Refuge Area.</b>			
	➤ Total Area	N/A	N/A	N/A
	➤ Location	N/A	N/A	N/A
19	<b>Fire Control Room</b>			
	• Detector System Panel	N/A	N/A	N/A
	• Flow Switch Panel	N/A	N/A	N/A
	• PA System Panel	N/A	N/A	N/A
	• Batter backup	N/A	N/A	N/A

M

N/13

	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection Systems for Protection of special Risks, if any:	N/A	N/A	N/A

The fire protection systems provided in the building were tested/ checked randomly and found in good working condition, at the time of inspection. The management has complied all the shortcomings issued and communicated by this department vide letter of even no. 425 dated 07.02.2012 & 956 dated 13.04.2016.

Keeping in view the satisfactory compliance of the minimum standard on fire prevention and fire safety requirements as stipulated under the circular issued by Director of Education dated 01.03.2016, it is recommended to issue Fire Safety Certificate.

N/2316

Signature of the Inspecting Officer  
Name: - Rajesh Kumar  
Designation: - ADO/RN

DO/INWD

Styngl  
26.6.16

Dy CEO (WR)

CPG work - Alty  
FT Pb

29/6/16