

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS: DELHI FIRE SERVICE: NEW DELHI - 110001

No F 6 / DFS / MS / 2018 / *w2/1197*

Dated: *23/5/2018*

FIRE SAFETY CERTIFICATE

Certified that the **M/s Hari Consolidated Pvt. Ltd.** located at Plot no **A64/3.** , **G.T K. Road, Industrial Area, Delhi-110033** comprised of **basement, ground, Mezz. & one upper floors** owned/occupied by **M/s Hari Consolidated Pvt. Ltd.** have complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and verified by the officer concerned of Fire Service on 14.05.2018 in presence of **Sh. Raman Kumar Saluja, Owner** of the premise is fit for occupancy class G-2 Industrial occupancy for **basement, ground, Mezz. & one upper floors** with effect from.....*23/5/18*..... for a period of three years, in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Conditions for the validity of Fire Safety Certificate:

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director of Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on WWW.dfs.Delhigovt.nic.in

Issued on*23/5/18*..... at New Delhi

(Atul Garg)

Chief Fire Officer

Ph:-011-23414250

Copy to :-

1. The Authorized Signatory, M/s Hari Consolidated Pvt. Ltd., Plot no A64/3. , G.T K. Road, Industrial Area., Delhi-110033

N/13

INSPECTION REPORT

- 1 Name & address of the building : Hari Consolidated Pvt. Ltd., Plot no A64/3. , G.T K. Road, Industrial Area. Delhi-110033.
- 2 Type of Occupancy : Industrial Building (Basement, Ground , Mazz. & first floor)
- 3 Type of Case : New Case
- 4 Details of previous NOC : Nil
- 5 Fire Safety directives letter No :
- 6 Date of inspection : 14/05/2018
- 7 Name of the Inspecting Officers : ADO (RN)
- 8 Name and designation of officers
from the building side : Sh. Raman Kumar Saluja / Owner
- 9. Year of Construction : prior to 1983
- 10. Applicant's letter No. : Nil Dated- 20.03.2018

Plot Area-

S.no.	Minimum Standards on fire prevention and fire safety U/R 33	D M C (Drainage) Bye Laws 1959	Provided at site	Remarks MR/MNR
1	Access to building			
	• Road width	6m	6m	MR
	• Gate width	Accessible	Directly Accessible	MR
	• Width of internal road	NA	NA	NA
2	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases			
	• Upper Floors	02	02	MR
	• Basements	02	02	MR
	b. Width of staircases			
	• Upper Floors	4'6" (1.37 m) each	1.37m each	MR
	• Basements	4'6" (1.37 m) each	1.37m each	MR
	c. Protection of exits			
	• Fire check door	Required	Provided	MR
	• Pressurization	NA	NA	NA
	d. No. of continuous staircases to terrace	01	01	MR
e. Width of Corridor	NA	NA	NA	
f. Door Size	1.0m	1.0m	MR	
3	Compartmentation.			

2/14

	<ul style="list-style-type: none"> • Fire check door • Sealing of electrical shafts • Fire Rating of shaft door • Water Curtain • Fire Dampers 	Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
		NA	NA	NA
		NA	NA	NA
4	Smoke Management System.			
	<ul style="list-style-type: none"> • Basements • Upper floors 	30 a/c per hour	Axial Fan	MR
		12 a/c per hour	Natural Ventilated	MR
5	Fire Extinguishers			
	<ul style="list-style-type: none"> • Total numbers • Types • ISI marking 	14nos	14nos	MR
		ABC/CO2	ABC	MR
		ISI Marked	Yes	MR
6	First-Aid Hose Reels.			
	<ul style="list-style-type: none"> • Total numbers on each floor • Length of hose reel hose • Nozzle diameter 	Required	Provided	MR
		30m	Provided	MR
		5mm	Provided	MR
7	Automatic fire detection and alarming system.			
	<ul style="list-style-type: none"> • Type of detectors • Location of Main Panel • Location of Repeater Panel • Alternate source of power • Hooters' Location 	Required	Provided	MR
		Ground Floor	Provided	MR
		Each Floor	Provided	MR
		Required	Provided	MR
		Each Floor	Provided	MR
8	MOEFA	Required	Provided	MR
9	Public Address System.	NA	NA	NA
10	Automatic Sprinkler System.			
	<ul style="list-style-type: none"> • Basement • Upper Floor • Sprinkler above false ceiling 	Required	Provided	MR
		Required	Provided	MR
		NA	NA	NA
11	Internal Hydrants			
	<ul style="list-style-type: none"> • Size of riser/down-comer • Number of hydrants per floor • Hose Box 	Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
12	Yard Hydrants			
	<ul style="list-style-type: none"> • Total number of hydrants • Hose Box 	NA	NA	NA
		NA	NA	NA

M/15

13	Pumping Arrangements.			
	<ul style="list-style-type: none"> • Ground Level <ul style="list-style-type: none"> ➤ Discharge of main Pump ➤ Head of Main pump ➤ Number of main pumps ➤ Jockey Pump out put ➤ Jockey pump head ➤ Standby Pump out put ➤ Standby Pump Head ➤ Auto Starting/ Manual stopping ➤ Pump House Access 			
		1620 lpm	1620 lpm	MR
		60m	60m	MR
		01	Provided	MR
		180lpm	180lpm	MR
		60m	60m	MR
		1620 lpm	1620 lpm	MR
		60m	60m	MR
		Required	Provided	MR
	<ul style="list-style-type: none"> • Terrace level <ul style="list-style-type: none"> ➤ Discharge of pump ➤ Head of the pump ➤ Power Supply ➤ Auto Starting of pump 	900 lpm	900 lpm	MR
		40mtr	40mtr	MR
		Required	Provided	MR
Required		Provided	MR	
14	Captive Water Storage for fire fighting.			
	<ul style="list-style-type: none"> • Underground tank capacity ➤ Draw-off connection ➤ Fire service inlet ➤ Access to tank • Overhead Tank capacity 	25,000 ltr	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
		15,000 ltr	15,000 ltrs	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.			
	<ul style="list-style-type: none"> • Pressurization of Lift Shaft • Pressurization of Lift lobby • Communication In lift Car • Fireman's Grounding Switch • Lift Signage 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
17	Standby power supply	Required	Provided	MR
18	Refuge Area.			
	<ul style="list-style-type: none"> ➤ Total Area ➤ Location 	N/A	N/A	N/A
		N/A	N/A	N/A
19	Fire Control Room			

N/116

	<ul style="list-style-type: none"> • Detector System Panel • Flow Switch Panel • PA System Panel • Batter backup • Building Floor Plans 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
20	Special Fire Protection Systems for Protection of special Risks, if any:	N/A	N/A	N/A

The fire protection systems provided in the building were test checked and found functional at the time of inspection. The Party has complied all the shortcomings issued and communicated by this department vide letter of even no. 1128 dated 21.03.2018.

Keeping in view the substantial compliance of the minimum standard on the fire prevention fire safety required under the rules, FSC issued under rule 35 of the Delhi Fire Service Rules 2010 is recommended.

11/15/18

Signature of the Inspecting Officer
 Name :- Rajesh Kumar
 Designation:- ADO/RN

~~Deputy CFB/W2~~
~~CFB West~~
 16/5/18
 FT D/C

ADO/RN As approved, f.t. letter is put up for your signature @1.

~~CFB/W2~~
 23/05/18

11/23/18

pu