

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE NEW DELHI-110001**


No. F6/DFS/MS/2021/School/WZ /131

Dated: 17/2/21

**FIRE SAFETY CERTIFICATE**

Certified that the **School of Excellence, Sector-17, Rohini, Delhi-110086**, comprised of **Ground + Three upper floors** owned/occupied by **School of Excellence**, has already been issued FSC by this department vide letter No. **F.6/DFS/MS/2017/School/WZ/1072 dated 21.07.2017**. The premises was re-inspected by the officer concerned of this department on **02.02.2021** in the presence of **Sh. Rakesh Kumar (HOS)** and observed that all the fire prevention and fire safety arrangements as provided in the premise found in good working condition. The premises have therefore deemed complied with the requirements under Rule 33 of the Delhi Fire Service Rules, 2010 and that the premises fit for occupancy under Educational "Group B" with effect from 17/2/21 for a period of three years in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subjected to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010.

Issued on ...17/2/21... at New Delhi by

  
(Dhrampal Bhardwaj)  
Dy. Chief Fire Officer  
Tel:-01123412050

Copy to :-

1. The Principal, School of Excellence, Sector-17, Rohini, Delhi-110086.
2. The Director of Education, Old Secretariat, Delhi

**Conditions for validity of Fire Safety Certificate;**

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form "K" is available on

[http://www.delhi.gov.in/wps/wcm/connect/doiit\\_fire/FIRE/Home/Fire+Safety+Acts+and+Rules/](http://www.delhi.gov.in/wps/wcm/connect/doiit_fire/FIRE/Home/Fire+Safety+Acts+and+Rules/)  
[http://www.delhi.gov.in/wps/wcm/connect/doiit\\_fire/FIRE/Home/Forms](http://www.delhi.gov.in/wps/wcm/connect/doiit_fire/FIRE/Home/Forms)

**INSPECTION REPORT**


1. Name & address of the building : School of Excellence, Sector-17, Rohini, Delhi-110086.
2. Type of Occupancy : Educational
3. Type of Case : Renewal **(Ground + 03 upper floors)**
4. Details of Previous NOC : F.6/DFS/MS/2017/School/WZ/1072 dated 21.07.2017
5. Fire Safety directives letter No : NBC Part-IV
6. Date of inspection : 02.02.2021
7. Name of Inspecting Officer : A.K.Sharma (ADO Rohini)
8. Name and designation of officers  
From the building side : Sh. Rakesh Kumar (HOS)
9. Year of Construction : 2017
10. Applicant's letter No. : Online mail dated 17.11.2020

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	NBC Requirement	Provided at site	Remarks MR/NMR
1.	<b>Access to building</b>			
	• Road width	Accessible	Provided	MR
	• Gate width	Accessible	Provided	MR
	• Width of internal road	NA	NA	NA
2.	<b>Number, Width, Type &amp; Arrangement of Exits</b>			
	a. Number of staircases			
	• Upper Floors	Required	03	MR
	• Basements	NA	NA	NA
	b. Width of staircases			
	• Upper Floor	1.5m	2.0m	MR
	• Basements	NA	NA	NA
	c. Protection of exits	NA	NA	NA
	Fire check door	NA	NA	NA
	• Pressurization	NA	NA	NA
	d. No. of continuous staircases to terrace	01	02	MR
	e. Width of Corridor	Required	Provided	MR
	f. Door Size	1m	1.10m	MR
3.	<b>Compartmentation</b>			
	• Fire check door	NA	NA	NA
	• Sealing of electrical shafts	NA	NA	NA
	• Fire Rating of shaft door	NA	NA	NA
	• Water Curtain	NA	NA	NA
	• Fire Dampers	NA	NA	NA
4.	<b>Smoke Management System</b>			
	• Basements	30 a/c per hour	NA	NA
	• Upper floors	12 a/c per hour	Natural ventilated	MR
5.	<b>Fire Extinguishers</b>			
	• Total numbers	50 nos	60 nos	MR
	• Types	ABC/Co2	ABC-30/CO2-30	MR
	• IS marking	ISI marked	Provided	MR
6.	<b>First-Aid Hose Reels</b>			
	• Total numbers on each floor	02	03	MR
	• Length of hose reel hose	30m	30m	MR
	• Nozzle diameter	5mm	5mm	MR
7.	<b>Automatic fire detection and alarming system</b>			
	• Type of detectors	NA	NA	NA
	• Location of Main Panel	NA	NA	NA
	• Location of Repeater Panel	NA	NA	NA
	• Alternate source of power	NA	NA	NA
	• Hooters' Location	NA	NA	NA


8.	<b>MOEFA</b>	NA	NA	NA
9.	<b>Public Address System</b>	NA	NA	NA
10.	<b>Automatic Sprinkler System</b>			
	<ul style="list-style-type: none"> <li>• Basement</li> <li>• Ground &amp; Upper Floors</li> <li>• Sprinkler above false ceiling</li> </ul>	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
11.	<b>Internal Hydrants</b>			
	<ul style="list-style-type: none"> <li>• Size of riser/down-comer</li> <li>• Number of hydrants per floor</li> <li>• Hose Box</li> </ul>	NA	100mm	NA
		NA	03	NA
		NA	03	NA
12.	<b>Yard Hydrants</b>			
	<ul style="list-style-type: none"> <li>• Total number of hydrants</li> <li>• Hose Box</li> </ul>	NA	06	NA
		NA	NA	NA
13.	<b>Pumping Arrangements</b>			
	<ul style="list-style-type: none"> <li>• Ground Level <ul style="list-style-type: none"> <li>➤ Discharge of main Pump</li> <li>➤ Head of Main pump</li> <li>➤ Number of main pumps</li> <li>➤ Jockey Pump out put</li> <li>➤ Jockey pump head</li> <li>➤ Standby Pump out put</li> <li>➤ Standby Pump Head</li> <li>➤ Auto Starting/Manual Stopping</li> <li>➤ Pump House Access</li> </ul> </li> <li>• Terrace level <ul style="list-style-type: none"> <li>➤ Discharge of pump</li> <li>➤ Head of the pump</li> <li>➤ Power Supply</li> <li>➤ Auto Starting of pump</li> </ul> </li> </ul>	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		450lpm	450lpm x 2	MR
		40m	40m	MR
		Required	Provided	MR
		Required	Provided	MR
14.	<b>Captive Water Storage for fire fighting</b>			
	<ul style="list-style-type: none"> <li>• Underground tank capacity <ul style="list-style-type: none"> <li>➤ Draw-off connection</li> <li>➤ Fire service inlet</li> <li>➤ Access to tank</li> </ul> </li> <li>• Overhead Tank capacity</li> </ul>	NA	100,000 ltr	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		10,000 ltr	10,000 ltr	MR
15.	<b>Exit Signage.</b>	Required	Provided	MR
16.	<b>Provision of Lifts.</b>			
	<ul style="list-style-type: none"> <li>• Pressurization of Lift Shaft</li> <li>• Pressurization of Lift lobby</li> <li>• Communication In lift Car</li> <li>• Fireman's Grounding Switch</li> <li>• Lift Signage</li> </ul>	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
17.	<b>Standby power supply</b>	NA	NA	NA
18.	<b>Refuge Area.</b>			
	<ul style="list-style-type: none"> <li>➤ Total Area</li> <li>➤ Location</li> </ul>	NA	NA	NA
		NA	NA	NA
19.	<b>Fire Control Room</b>			
	<ul style="list-style-type: none"> <li>• Detector System Panel</li> <li>• Flow Switch Panel</li> <li>• PA System Panel</li> <li>• Battery backup</li> <li>• Building Floor Plans</li> </ul>	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
20.	<b>Special Fire Protection System for Protection of special Risks, if any:</b>	NA	NA	NA

The fire protection systems provided in the building were test checked and found functional at the time of inspection.


In view of the deemed compliance of the minimum standards of the fire prevention and fire safety measures as required under the rules the NOC issued vide letter no. F.6/DFS/MS/2017/School/WZ/1072 dated 21.07.2017 is recommended for renewal under rule 37 of the Delhi Fire Service rules 2010.

  
Signature of the Inspecting Officer  
Name Ajay Kumar Sharma  
Designation ADO(Rohini)


DO(NW)

  
04/02/2021

By ~~ADG~~ (WZ) clarify the name of school  
by CR-


  
05/02/2021

~~DO(NW)~~


  
10/02/2021  
ADG (R)

C-10 may kindly be processed for request  
of school name change.


Put up again for kind perusal and  
approval please.

  
11/02/2021

~~DO(NW)~~ The name of the school  
has been changed by Govt. and  
in this regard a letter was issued which  
is placed at C-10. Re-submitted by

  
12/02/2021

By ~~ADG~~ (WZ)

  
18/02/2021

FT letter is put up for