

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS: DELHI FIRE SERVICE: NEW DELHI-110001**


No. F.6/DFS/MS/SZ/2021/ 135

Dated: 19/02/2021

FIRE SAFETY CERTIFICATE

Certified that Punjab & Sind Bank located at Building No.- 21, Rajendra Place, New Delhi- 110008, comprised of basement, ground plus eight upper floors, was inspected by the officer concerned of this department on 02.02.2021 in the presence of Captain Gurjeet Singh, CSO of the building and found that the said building have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the premises is fit for occupancy class Business with effect from ~~19/02/2021~~ for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules 2010.

Issued ~~19/02/2021~~ at New Delhi by.


(Atul Garg)
Director
Delhi Fire Service

Copy to:-

1. Captain Gurjeet Singh (Chief Security Officer), Punjab & Sind Bank, Building No.-21, Rajendra Palace, New Delhi-110008.

Following Fire Safety Directives Must Be Adhered To:-

1. Providing of fire safety measures does not give any guarantee that there will be No fire. These equipments/installations can minimize the losses if maintained in good working condition and handled efficiently in case of fire.
2. The approach to the building all around shall not used for parking and kept free for the movement of fire appliances all the time.
3. Any deviation w.r.t. construction etc. shall be verified by the concerned building sanctioning authority.
4. Any loss of life or property due to non-functional of fire safety measures shall be at the risk & responsibility of the management.
5. All the fire safety arrangements provided therein shall be maintained in good working condition at all times.
6. All occupants/security personal shall be trained to operate the fire safety equipments during emergency.
7. The NOC is subject to condition that approach road around the building should be cleared of parking of DDA/DMRC.
8. The alternate exit/staircase shall be directly accessible from the ground floor & it should be completed within three months of time.

2. Type of Occupancy : Business
 3. Type of Case : Renewal
 4. Details of previous NOC : F.6/DFS/MS/2017/SZ/652 dated 05.05.2017
 5. Fire Safety directives letter No : F.6/DFS/MS/82/1369 dated 16.09.1982
 6. Date of inspection : 28.12.2020
 7. Name of the Inspecting Officers : D.B. Mukharjee, Div. Officer (SW) & P.V Rathee, ADO (SRD)
 8. Name and designation of officers from the building side : Caption Gurjeet Singh (Chief Security Officer)
 9. Year of Construction : Before 1982
 10. Applicant's letter No. : HOSD/Fire Safety Certificate dated 18.09.2020

The said building is comprised of basement, ground plus eight upper floors

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	Requirement as per NOC dt. 05.05.2017	Provided at site	Remarks MR/NMR
1	Access to building			
	• Road width	Accessible	06 mts	MR
	• Gate width	NA	NA	NA
	• Width of internal road	06 mts	Approachable from one side	MR(Being old case)
2	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases	-	-	-
	• Upper Floors	NA	02 Nos.	NA
	• Basements	NA	01 No.	NA
	b. Width of staircases	-	-	-
	• Upper Floors	NA	1.25 & .90 mts	NA
	• Basements	NA	1.25 mts	NA
	c. Protection of exits	-	-	-
	• Fire check door	Required	Provided	MR
	• Pressurization	NA	NA	NA
	e. No. of continuous staircases to terrace	NA	01	NA
	g. Width of Corridor	NA	NA	NA
	h. Door Size	NA	NA	NA
3	Compartmentation			
	• Fire check door	Required	Provided	MR
	• Sealing of electrical shafts	Required	Provided	MR
	• Fire Rating of shaft door	N/A	N/A	N/A
	• Water Curtain	N/A	N/A	N/A
	• Fire Dampers	N/A	N/A	N/A
4	Smoke Management System.			
	• Basements	Required	Provided	MR
	• Upper floors	Required	Natural Vantilation	MR
5	Fire Extinguishers			
	• Total numbers	30	Provided	MR
	• Types	ABC & CO ₂ type	Provided	MR
	• IS marking	ISI marked	Provided	MR
6	First-Aid Hose Reels.			
	• Total numbers on each floor	01 No.	Provided	MR
	• Length of hose reel hose	30 m	Provided	MR
	• Nozzle diameter	5 mm	Provided	MR


	<ul style="list-style-type: none"> Location of Main Panel Location of Repeater Panel Alternate source of power Hooters' Location 	N/A	Ground Floor	N/A
		N/A	N/A	N/A
		Required	Provided	MR
		N/A	At exits	N/A
8	MOEFA	Required	Provided	MR
9	Public Address System.	Required	Provided	MR
10	Automatic Sprinkler System.			
	<ul style="list-style-type: none"> Basement 	Required	Provided	MR
	<ul style="list-style-type: none"> Upper Floor 	Required	Provided	MR
	<ul style="list-style-type: none"> Sprinkler above false ceiling 	Required	Provided	MR
11	Internal Hydrants			
	<ul style="list-style-type: none"> Size of riser/down-comer 	100 mm	Provided	MR
	<ul style="list-style-type: none"> Number of hydrants per floor 	01 No.	Provided	MR
	<ul style="list-style-type: none"> Hose Box 	01 No	Provided	MR
12	Yard Hydrants.			
	<ul style="list-style-type: none"> Total number of hydrants 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Hose Box 	N/A	N/A	N/A
13	Pumping Arrangements.			
	<ul style="list-style-type: none"> Ground Level 	---	---	---
	<ul style="list-style-type: none"> ➤ Discharge of main Pump 	2250 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Head of Main pump 	50 m	Provided	MR
	<ul style="list-style-type: none"> ➤ Number of main pumps 	01	Provided	MR
	<ul style="list-style-type: none"> ➤ Jockey Pump out put 	240 LPM (02 nos.)	Provided	MR
	<ul style="list-style-type: none"> ➤ Jockey pump head 	50 m	Provided	MR
	<ul style="list-style-type: none"> ➤ Standby Pump out put 	2250 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Standby Pump Head 	50 m	Provided	MR
	<ul style="list-style-type: none"> ➤ Auto Starting/ Manual stopping 	Required	Provided	MR
	<ul style="list-style-type: none"> ➤ Pump House Access 	N/A	N/A	N/A
	* Terrace level	-----	-----	-----
	<ul style="list-style-type: none"> ➤ Discharge of terrace pump 	450 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Head of the terrace pump 	40 mts	Provided	MR
	<ul style="list-style-type: none"> ➤ Power Supply 	Required	Provided	MR
	<ul style="list-style-type: none"> ➤ Auto Starting of pump 	Required	Provided	MR
14	Captive Water Storage for fire fighting.			
	<ul style="list-style-type: none"> Underground tank capacity 	100000 lts	Provided	MR
	<ul style="list-style-type: none"> ➤ Draw-off connection 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Fire service inlet 	N/A	Provided	N/A
	<ul style="list-style-type: none"> ➤ Access to tank 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Overhead Tank capacity 	50000 lts	Provided	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.			
	<ul style="list-style-type: none"> Pressurization of Lift Shaft 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Pressurization of Lift lobby 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Communication In lift Car 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Fireman's Grounding Switch 	Required	Provided	MR
	<ul style="list-style-type: none"> Lift Signage 	Required	Provided	MR
17	Standby power supply	Required	Provided	MR
18	Refuge Area.			
	<ul style="list-style-type: none"> ➤ Total Area 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Location 	N/A	N/A	N/A
19	Fire Control Room			
	<ul style="list-style-type: none"> Detector System Panel 	Required	Provided	MR
	<ul style="list-style-type: none"> Flow Switch Panel 	Required	Provided	N/A
	<ul style="list-style-type: none"> PA System Panel 	Required	Provided	N/A
	<ul style="list-style-type: none"> Batter backup 	Required	Provided	N/A
	<ul style="list-style-type: none"> Building Floor Plans 	N/A	Provided	N/A

20	Special Fire Protection Systems for Protection of special Risks, if any:	N/A	N/A	N/A
----	--	-----	-----	-----


The fire protection systems provided in the building were checked and found functional at the time of inspection.

In view of the deemed compliance of the minimum standards of fire prevention and fire safety measures as required under the Rules the Fire Safety Certificate issued vide letter number F.6/DFS/MS/2017/SZ/652 dated 05.05.2017 renewal under rule 37 of the Delhi Fire Service Rules 2010 is recommended.


DFA is put up for approval & signature please




 D.B. Mukharjee
 Divisional Officer (SZ)




 P.V. Rathee
 Asstt. Div. Officer (SRD)

By CFO/SZ

 8/2


C.F.O.



 9/2




 10/9/2021 FTPS



 SW

F.T. letter bl.



 12/02/2021

ADD (Sr. Rd.)

