

C-52

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE
NEW DELHI- 110 001

No.F.6/DFS/MS/School/2021/NDZ/ 234

Dated: 18/03/2021

FIRE SAFETY CERTIFICATE

Certified that the M/s Mother's Global School, C-Block, Preet Vihar, Vikas Marg, Delhi – 110092, comprised of Three blocks, whereas Two blocks having Basement, Ground plus Two upper floors and One block is Ground plus Two upper floors only. Owned / occupied by Mother's Global School was issued FSC vide letter no. F6/DFS/MS/2009/329 dated: 04/02/2009. The school building was re-inspected by the officer concerned of this department on 10/03/21 in presence of Principal of the school and found that the school building Two blocks having Basement, Ground plus Two upper floors and One block is Ground plus Two upper floors only, is fit for occupancy class 'B 'Educational Building' for with effect from 18/03/2021 for a period of three years, in accordance with the rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010, subject to conditions printed overleaf.

Issued on.....18/03/2021.....at New Delhi by


18/3/21

(Dr. S.K. Tomar)
Dy.Chief Fire Officer

o/c

Copy to:-

1. The Vice Principal
Mother's Global School,
C-Block, Preet Vihar, Vikas Marg,
Delhi- 110092.
2. The Joint Director of Education
(Land & Estate)
Directorate of Education, Lucknow Road, Delhi -54

- Conditions -

- 1 All the means of escape shall be kept free of all type of obstruction all the time.
- 2 All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
3. All the fire fighting equipments shall be maintained in good working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
4. The clarification with regards electrical installation, ventilation, structure stability set back areas, occupancy and constructional deviation in building etc .may be got verified from the authorities concerned.
5. This Fire Safety certificate can not be treated in any case for regularizations of unauthorized construction if any.
6. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on www.dfs.delhigovt.nic.in
7. "The owner /occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form'J'[sub rule(1) of rule 37] along with a copy of this certificate, six months prior to its expiry"

N/A

1. Name & address of the building : Mother's Global School, C-Block, Preet Vihar, Vikas Marg, Delhi - 110092.
2. Building is comprised of : (Two Blocks = B+G+2) & (One Block = G+2)
3. Type of Occupancy : Educational
4. Type of Case : Renewal
5. Details of Previous FSC letter : F6/DFS/MS/School/2018/NDZ/1373 Dated 13.06.20
6. Fire Safety direction letter No : NBC Part-IV
7. Date of Inspection : 16/03/2021
8. Name of the Inspecting officers : DO. Francis Brown,
9. Name and designation of Officer from the building side : (Principal)
10. Year of Construction : 1995
11. Applicant's letter No : Online Dated - 01/03/2021

NO.	Minimum Standards on fire prevention and fire safety U/R33	Requirement as per BBL/NBC	Provided at Site	Remarks MR/NM
1	Access to building			
	<ul style="list-style-type: none"> • Road width • Gate width • Width of internal road 	05 Mtrs	20 Mtrs	MR
		N/A	N/A	N/A
		N/A	N/A	N/A
2	Number, Width, Type and Arrangement of Exits			
	a. Number of Staircases			
	<ul style="list-style-type: none"> • Upper Floor 	02 no.	02 Nos. (each block)	MR
	<ul style="list-style-type: none"> • Basement 	02	02	MR
	b. Width of Staircases			
	<ul style="list-style-type: none"> • Upper Floor 	1.5 m	(Two Blocks = 1.5 & 1.10 each)	MR
	<ul style="list-style-type: none"> • Basement 		(One Block = 1.35 x 2)	
	c. Protection of exits			
	<ul style="list-style-type: none"> • Fire check door • Pressurization 	1.5	1.5 m & 1.0 m	MR
		N/A	N/A	N/A
	d. No. of continuous staircases to terrace	N/A	N/A	N/A
	e. Width of Corridor	01 no	01 each block	MR
	f. Door Size			
		1.5 m	1.5 m	MR
		1.0 m	1.0 m	MR
3	Compartmentation.			
	<ul style="list-style-type: none"> • Fire check door • Sealing of electrical shafts • Fire rating of shaft door • Water curtain • Fire Dampers 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
4	Smoke Management System.			
	<ul style="list-style-type: none"> • Basement • Upper floor 	N/A	Ventilated	MR
		N/A	N/A	N/A
5.	Fire Extinguishers			
	<ul style="list-style-type: none"> • Total numbers 	25 nos.	26 nos.	MR
	<ul style="list-style-type: none"> • types 	ABC & Co2	ABC & Co2	MR
	<ul style="list-style-type: none"> • ISI marking 	ISI marked	ISI marked	MR

f

6	First-aid-Hose Reels.			
	Total numbers of each floor	01 no.	01 no. each block	MR
	• Length of hose reel hose	30 m	30 m	MR
	• Nozzle diameter	5 mm	05 mm	MR
7	Automatic fire detection and alarming system.			
	• Type of detectors	N/A	N/A	N/A
	• Location of main panel	N/A	N/A	N/A
	• Location of repeater panel	N/A	N/A	N/A
	• Alternate source of power	Required	Provided	MR
	• Hooter's location	Required	Gr .Floor	MR
8	MOEFA	Required	Provided	MR
9	Public address System.	Required	Provided	MR
10	Automatic Sprinkler System.			
	• Basement	Required	Provided	MR
	• upper floor	N/A	N/A	N/A
	• sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	• size of riser/down-comer	Required	100 mm each Block	MR
	• Number of hydrants per floor	01 nos.	01 nos.	MR
	• Hose Box	01 nos.	01 nos.	MR
12	Yard Hydrants.			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13	Pumping Arrangements.			
	• Ground Level	N/A	N/A	N/A
	➤ Discharge of main Pump	N/A	N/A	N/A
	➤ Head of Main Pump	N/A	N/A	N/A
	➤ Number of main pumps	N/A	N/A	N/A
	➤ Jockey pump out put	N/A	N/A	N/A
	➤ Jockey pump head	N/A	N/A	N/A
	➤ Standby pump out put	N/A	N/A	N/A
	➤ Standby pump Head	N/A	N/A	N/A
	➤ Auto Starting /Manual stopping	N/A	N/A	N/A
	➤ Pump House Access	N/A	N/A	N/A
	• Terrace Level			
	➤ Discharge of pump	450 LPM	450 LPM each block	MR
	➤ Head of the Pump	40 M	40 M	MR
	➤ Power supply	Required	Provided	MR
	➤ Auto Starting of pump	Required	Provided	MR
14	Captive Water Storage for Fire Fighting			
	• Underground tank capacity	N/A	50,000 Liters	MR
	➤ Draw-off connection	N/A	N/A	N/A
	➤ Fire service inlet	N/A	N/A	N/A
	➤ Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	10000 Liters each block	10000 Liters each block	MR
15	Exit Signage.	Required	Provided	MR

16	Provision of Lifts.			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication in lift car	N/A	N/A	N/A
	• Firemen's grounding switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17	Standby power supply	Required	Provided	MR
18	Refuge Area.			
	• Total area	N/A	N/A	N/A
	• Location	N/A	N/A	N/A
19	Fire Control Room			
	• Detector system panel	N/A	N/A	N/A
	• Flow switch panel	N/A	N/A	N/A
	• PA system panel	N/A	N/A	N/A
	• Battery backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection systems for protection of special Risks, if any:	N/A	N/A	N/A

The Fire protection systems provided in the building were Tested / Checked and found functional, at the time of inspection.

Keeping in view, of the deemed compliance, of the minimum standards on Fire prevention and Fire safety measures as required under the rules.

[Handwritten Signature]
16/3/21

Signature of the Inspecting Officer
Name: F. Brown
Designation: DO (East)

DCFO (NDZ)

P.H. P.I.

[Handwritten Signature]
18/3/21

DOCEP

Ft. Lella is prepared and put up for special plan

Dy. CSD NDZ

[Handwritten Signature]
18/3/21

[Handwritten Signature]
18/3

M.S. Cell