

C-16

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS: DELHI FIRE SERVICE, CONNAUGHT PLACE

NEW DELHI

No. F6/DFS/MS/School/WZ/2021/ 1028

Dated: 17/12/2021

FIRE SAFETY CERTIFICATE

Certified that the **V.S.P.K International School Juniors (Kailash Memorial Charitable Society)**, Located at Plot no 12, FC-57, Road no 44, PitamPura, Delhi comprised of Basement + Stilt + Ground + 02 Upper Floors owned and occupied by **Kailash Memorial Charitable Society** was issued Fire Safety Certificate vide Letter No. F6/DFS/MS/School/2018/WZ/178 dated 29.01.2018. The premises was re-inspected by the officer concerned of this department on 03.12.2021 in the presence of Sh. Sandeep Kumar (Caretaker) and found that the building/premises have deemed complied with the fire prevention and fire safety requirements in accordance with NBC Part-IV and that the premises/building is fit for occupancy class "Educational Building" Group B with effect from 17/12/2021 for a period of three years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40, subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on17/12/2021... at New Delhi by.

(Dharampal Bhardwaj)
Dy. Chief Fire Officer
(West Zone)

Copy to:

1. The Principal, V.S.P.K International School Juniors (Kailash Memorial Charitable Society) Located at Plot no 12, FC-57, Road no 44, PitamPura, Delhi.
2. The Director, Directorate of Education, GNCT NCT of Delhi, Old Secretariat Delhi - 110054.

Following fire safety directives must be adhered to:-

1. All the fire safety arrangements provided therein shall be maintained in good working condition at all times.
2. Any loss of life or property due to non-functional fire safety measures shall be at the risk and responsibility of the management.
3. The trained staff should be available round the clock.
4. Any deviations w.r.t. construction shall be verified by the concerned building sanctioning agency.
5. The certificate may not be treated in any case for the regularization of the unauthorized construction, if any.
6. The owner/ occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this certificate, six months prior to its expiry.
7. Basement shall be used strictly as per building bye laws.
8. The owner/occupier shall submit a declaration every year in the form 'K' provided in the first schedule of Delhi Fire Service Rules 2010, form is available on www.dfs.delhigovt.nic.in.
9. The Basement shall be used as per BBL.

INSPECTION REPORT

1. Name & address of the building : **V.S.P.K. International School Juniors (Kailash Memorial Charitable Society)**. Located at **Plot no 12, FC-57, Road no 44, Pitampura, Delhi**
2. Type of Occupancy : Educational (Basement +Stilt + Ground + 02 Upper Floor)
3. Type of Case : Renewal
4. Details of previous NOC : F6/DFS/MS/School/2018/WZ/178 dated 29.01.2018
5. Fire Safety directives Letter No : Cr.No.3298-3398 dated 01-03-2011
6. Date of inspection : 03.12.2021
7. Name of the Inspecting Officer : S.P. Bhardwaj, ADO (WP)
8. Name and designation of Officer from the building side : Sh. Sandeep Kumar(Caretaker)
9. Year of Construction : 2013-14
10. Applicant's letter No. : email dated 15.12.2021

S No	Minimum standards on fire prevention and fire safety U/R 33	Cr.No.3298-3398 dated 1-3-11/NBC/letter dated 29.01.2018	Provided at site	Remarks MR/NMR
1.	Access of building			
	<ul style="list-style-type: none"> • Road width • Gate width • Width of internal road 	<ul style="list-style-type: none"> Accessible Accessible NA 	<ul style="list-style-type: none"> 12 m Provided 380cm NA 	<ul style="list-style-type: none"> MR MR(Old Case) NA
2.	Number, width, Type & Arrangements of exits			
	a. Number of staircases			
	<ul style="list-style-type: none"> • Upper floors • Basements 	<ul style="list-style-type: none"> 01 02 	<ul style="list-style-type: none"> 02 02 	<ul style="list-style-type: none"> MR MR
	b. Width of staircases			
	<ul style="list-style-type: none"> • Upper floors • Basements 	<ul style="list-style-type: none"> 1.5 m 1.5 m 	<ul style="list-style-type: none"> 1x145 cm & 1x150 cm 1x150 cm & 1x135 cm 	<ul style="list-style-type: none"> MR MR
	c. Protection of exits			
	<ul style="list-style-type: none"> • Fire check door • Pressurization 	<ul style="list-style-type: none"> NA NA 	<ul style="list-style-type: none"> NA NA 	<ul style="list-style-type: none"> NA NA
	d. No of continuous staircase to terrace	01	Provided	MR
	e. Width Of Corridor	1.5 m	Provided	MR
	f. Door Size	1m	111cm	MR
3.	Compartmentation			
	<ul style="list-style-type: none"> • Fire check door • Sealing of electrical shafts • Fire Rating of shaft door • Water Curtain • Fire Dampers 	<ul style="list-style-type: none"> Required NA NA NA NA 	<ul style="list-style-type: none"> Provided in basement NA NA NA NA 	<ul style="list-style-type: none"> MR NA NA NA NA
4.	Smoke managements System			
	<ul style="list-style-type: none"> • Basements • Upper floors 	<ul style="list-style-type: none"> Required NA 	<ul style="list-style-type: none"> Provided NA 	<ul style="list-style-type: none"> MR NA
5.	Fire Extinguishers			
	<ul style="list-style-type: none"> • Total numbers • Types • IS marking 	<ul style="list-style-type: none"> 12 nos. ABC & CO₂ ISI marked 	<ul style="list-style-type: none"> Provided Provided Provided 	<ul style="list-style-type: none"> MR MR MR

6.	First - Aid Hose Reels			
	• Total numbers on each floor	02	Provided	MR
	• Length of hose reel hose	30m	Provided	MR
	• Nozzle diameter	5mm	Provided	MR
7.	Automatic fire detection and alarming system			
	• Type of detectors	NA	NA	NA
	• Location of Main Panel	NA	NA	NA
	• Location of Repeater Panel	NA	NA	NA
	• Alternate source of power	NA	NA	NA
	• Hooters' Location	NA	NA	NA
8.	MOEFA	NA	NA	NA
9.	Public Address System	NA	NA	NA
10.	Automatic Sprinkler System			
	• Basements	Required	Provided	MR
	• Upper Floor	NA	NA	NA
	• Sprinkler above false ceiling	NA	NA	NA
11.	Internal Hydrants:			
	• Size of riser/down-comer	NA	NA	NA
	• Number of hydrants per floor	NA	NA	NA
	• Hose Box	NA	NA	NA
12.	Yard Hydrants			
	• Total number of hydrants	NA	NA	NA
	• Hose Box	NA	NA	NA
13.	Pumping Arrangements:			
	• Ground Level			
	• Discharge of main pump	NA	NA	NA
	➤ Head of main pump	NA	NA	NA
	➤ Number of main pumps	NA	NA	NA
	➤ Jockey pump out put	NA	NA	NA
	➤ Jockey pump head	NA	NA	NA
	➤ Standby Pump out put	NA	NA	NA
	➤ Standby Pump Head	NA	NA	NA
	➤ Auto Starting/Manual stopping	NA	NA	NA
	➤ Pump House Access	NA	NA	NA
	• Terrace level			
	➤ Discharge of pump	900 lpm	Provided	MR
	➤ Head of the pump	50 M	Provided	MR
	➤ Power supply	Required	Provided	MR
	➤ Auto starting of pump	Required	Provided	MR
14.	Captive water Storage for fire fighting:			
	• Under ground tank capacity	NA	NA	NA
	➤ Draw off connection	NA	NA	NA
	➤ Fire service inlet	NA	NA	NA
	➤ Access to tank	NA	NA	NA
	• Overhead Tank capacity	15,000Ltr	Provided	MR
15.	Exit Signage	Required	Provided	MR
16.	Provision of Lifts	(Lift will Run from G toUF)		
	➤ Pressurization of Lift Shaft	NA	NA	NA
	➤ Pressurization of lift lobby	NA	NA	NA
	➤ Communication in lift Car	Required	Provided	MR

MR

N-12

	➤ Fireman's Grounding Switch	Required	Provided	MR
	➤ Lift Signage	Required	Provided	MR
17.	Standby power supply	NA	NA	NA
18.	Refuge Area			
	➤ Total area	NA	NA	NA
	➤ Location	NA	NA	NA
19.	Fire control room			
	➤ Detector system panel	NA	NA	NA
	➤ Flow Switch Panel			
	➤ PA System Panel	NA	NA	NA
	➤ Battery backup	NA	NA	NA
	➤ Building Floor Plans	NA	NA	NA
		NA	NA	NA
20.	Special Fire Protection Systems for Protection of special Risks, if any;	NA	NA	NA

The Fire protection systems provided in the building were checked and found functional at the time of inspection.

In view of the deemed compliance of the minimum standards of fire prevention and fire safety requirements as per Cr.No.3298-3398 dated 01.03.2011, renewal of Fire Safety Certificate issued vide letter no. F6/DFS/MS/School/2018/WZ/178 dated 29.01.2018 is recommended.

S.P. Bhardwaj
AOO (WP)
13/12/21

D.O. (WEST) 287
DATED 13/12/2021

~~Do/ment~~

13/12/2021

~~D/O (W2)~~

15/12/2021

~~AOO/W/P~~

FR is put up for signch for

~~Defol WZ~~
17/12/2021

15/12/21

MS/ceer