



DELHI JAL BOARD: GOVT. OF NCT OF DELHI
OFFICE OF THE MEMBER (WATER SUPPLY)
106, VARUNALAYA PH-II: KAROL BAGH, DELHI-05
Phone No. 011-23528578, mail: memberwsdjb@gmail.com



*“STOP CORONA; WEAR MASK, FOLLOW PHYSICAL
DISTANCING, MAINTAIN HAND HYGIENE”*

No. F-3/DJB/Mem.(WS)/2021/ 622

Dated: 30.03.2021

INSTRUCTIONAL ORDER

Due to rapid pace of development, several agencies (e.g. DMRC, PWD, NCRTC, NHAI etc) are working for their development projects, requiring the replacement of existing water infrastructure coming in their alignment. In recent past, during execution, there were leakages and stability issues in the shifted rising mains feeding various UGRs. Generally such replacement works are executed by these agencies through their concessionaire or approved contractors after due approval of their scheme by DJB.

Due to non clarity in dealing the permission of such cases, in supersession of earlier orders, the following procedure shall be adopted hereafter:-

1. The outside agency i.e. DMRC, PWD etc. shall submit all requests pertaining to water side with drawings and proposed alignment of replacement (3 sets of drawing indicating the present and proposed alignment) to CE(W)Projects-I who will act as nodal officer in all such cases.

2. The agency shall arrange joint inspection of site with CE(W)Projects-I, CE(WW) and CE(Maintenance) or their nominated representatives to show their execution plan and the required shifting of water infrastructure. A joint inspection report should be prepared ensuring suitable alignment and stability of water mains / shifting of tappings agreed by the custodian of the line. Sluice valve / Air valve should be affixed at possible locations in the replacement of water mains.

3. CE(W)Projects-I shall put up the approval file to Member(WS) alongwith the joint inspection report and execution drawings with modifications, if any. On approval from Member(WS), the approved drawings shall be handed over to CE(WW) and CE(Maintenance) for further necessary action.

4. All such works shall be inspected by CE(W)Projects-I, CE(WW) and CE(Maintenance) or their nominated representative atleast once in a month to ensure full compliance of the conditions / alignment of approved scheme. Any deviation shall be reported to Member (WS).

5. For shutdown during the execution, the agency shall put up the request to CE(W)Projects-I with details of interconnection and affidavit of preparation for completion of work in the minimum possible time. The referring shutdown shall also be vetted by CE(WW) / CE(Maintenance).

All guidelines as per order dated 16.03.2021 issued from the office of CEO, DJB shall be followed by the agency (annexed). Henceforth, all major planned shutdown on rising mains, main line etc shall be approved by CEO, DJB after fulfilling all directions of the order.

6. The agency shall inform about the completion of work. A final joint inspection shall be carried out to ensure no deviation from the approved plan. The final joint inspection report shall also be send to CE(WW) and CE(Maintenance) and the work stands hand over to the concerned CEs for further maintenance.

It is again reiterated that hence forth all schemes of replacement and shifting of water infrastructure shall be approved by Member(WS) irrespective of their nature and size of scheme.

Encl: As above.

Shalabh Kumar
30/3/2021
(SHALABH KUMAR)
MEMBER (WS)

All CEs/All SEs

Copy for kind information to:

1. CEO
2. Member(A)/Member(F)/Member(Dr)
3. C.V.O.
4. EDP Cell - to upload on DJB website

Shalabh Kumar
30/3/2021
MEMBER (WS)

*For n.e to upload on website
of DJB.*



Prog-1 | *Ms Basile*

1/4/21
Md. Usama
BE (EDP)