

C-36

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS: DELHI FIRE SERVICE: NEW DELHI-110001


No. F6/DFS/MS/School/WZ/2022/ 133


Dated: 08/02/2022

FIRE SAFETY CERTIFICATE

Certified that **Nathu Ram convent Sr. Sec. School (ID- 16172018)** located at **Shiv Ram Park, Phase-II, Nilothi More, Nangloi, New Delhi- 110041**, comprised of ground and first floor only, was granted Fire Safety Certificate by this department vide letter No. F.6/DFS/MS/School/2017/WZ/469 dated 29.03.2017. The school building was re-inspected by the officer concerned of this department on 27.01.2022, in the presence of Sh. Ravinder Lakra (Principal) and found that the school building have deemed complied with the fire prevention and fire safety requirements in accordance with Directorate of Education Circular No. 262-362 dt. 17.01.2005 and that the building/premises is fit for occupancy class "Educational" with effect from 08/02/2022 for a period of three years, subject to compliance of the conditions, printed overleaf.

Issued on 08/02/2022 at New Delhi by.


(Dharampal Bhardwaj)
Dy. Chief Fire Officer
(West Zone)


08/02/22

Copy to: -

1. The Principal,
Nathu Ram convent Sr. Sec. School,
Shiv Ram Park, Phase-II, Nilothi More, Nangloi,
New Delhi- 110041.
2. The Directorate of Education,
GNCT of Delhi, Old Secretariat, Delhi- 110054.

Conditions for the Validity of Fire Safety Certificate

1. All the fire safety arrangements provided therein shall be maintained in good working conditions at all times.
2. Any loss of life or property due to non-functional of fire safety measures shall be at the risk & responsibility of the management.
3. The trained firefighting staffs should be available round the clock.
4. Any deviation w.r.t. construction etc. shall be verified by the concerned building sanctioning authority.
5. This fire safety certificate may not be treated in any case for regularization of unauthorized construction, if any.
6. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on www.dfs.delhigovt.nic.in
7. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form "J" [sub rule (1) of rule 37] along with a copy of this certificate, six months prior to its expiry. The form is available on www.dfs.delhigovt.nic.in.
8. All the means of escapes /exits shall not be locked/blocked at any time for safe evacuation of the occupants in case of emergency.

INSPECTION REPORT

1. Name & address of the building : Nathu Ram Sr. Sec. School, located at Shiv Ram Park, Phase-II, Nilothi More, Nangloi, New Delhi- 110041.
2. Type of Occupancy : Educational
3. Type of Case : Renewal
4. Details of previous NOC : F6/DFS/MS/School/2017/WZ/469 dated 29/03/2017
5. Fire Safety directives letter No : D.o.E cir. No. 262-362 dt. 17.01.2005
6. Date of inspection : 27.01.2022
7. Name of the Inspecting Officers : Aman Kumar Lathar, ADO (JWP)
8. Name and designation of officers
from the building side : Sh. Ravinder Lakra, Principal
9. Year of Construction : 2006
10. Applicant's letter No. : E-mail dt. 21.12.2021

Nathu Ram Sr. Sec. School is comprised of ground and first floor each.

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	DoE circular dated 17.01.2005 Requirement	Provided at site	Remarks MR/NMR
1	Access to building			
	• Road width	06 mts	Provided	MR
	• Gate width	4.5 mts	Provided	MR
	• Width of internal road	N/A	N/A	N/A
2	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases	-----	-----	-----
	• Upper Floors	02	02	MR
	• Basements	N/A	N/A	N/A
	b. Width of staircases	-----	-----	-----
	• Upper Floors	1.50 mts each	1.50 mts each	MR
	• Basements	N/A	N/A	N/A
	c. Protection of exits	-----	-----	-----
	• Fire check door	N/A	N/A	N/A
	• Pressurization	N/A	N/A	N/A
	e. No. of continuous staircases to terrace	01	Provided	MR
	g. Width of Corridor	1.5 mts	1.5 mts	MR
	h. Door Size	1.0 mt	Provided	MR
3	Compartmentation.			
	• Fire check door	N/A	N/A	N/A
	• Sealing of electrical shafts	N/A	N/A	N/A
	• Fire Rating of shaft door	N/A	N/A	N/A
	• Water Curtain	N/A	N/A	N/A
	• Fire Dampers	N/A	N/A	N/A

Dr

N-10

4	Smoke Management System.			
	• Basements	30 a/c per hour	N/A	N/A
	• Upper floors	12 a/c per hour	N/A	N/A
5	Fire Extinguishers			
	• Total numbers	07 nos	Provided	MR
	• Types	ABC, CO ₂ type	Provided	MR
	• IS marking	ISI marked	Provided	MR
6	First-Aid Hose Reels.			
	• Total numbers on each floor	01	Provided	MR
	• Length of hose reel hose	30 mts	Provided	MR
	• Nozzle diameter	05 mm	Provided	MR
7	Automatic fire detection and alarming system			
	• Type of detectors	N/A	N/A	N/A
	• Location of Main Panel	N/A	N/A	N/A
	• Location of Repeater Panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooters' Location	N/A	N/A	N/A
8	MOEFA	N/A	N/A	N/A
9	Public Address System.	N/A	N/A	N/A
10	Automatic Sprinkler System			
	• Basement	N/A	N/A	N/A
	• Upper Floor	N/A	N/A	N/A
	• Sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	• Size of riser/down-comer	N/A	N/A	N/A
	• Number of hydrants per floor	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
12	Yard Hydrants.			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13	Pumping Arrangements			
	• Ground Level	---	----	-----
	➤ Discharge of main Pump	N/A	N/A	N/A
	➤ Head of Main pump	N/A	N/A	N/A
	➤ Number of main pumps	N/A	N/A	N/A
	➤ Jockey Pump out put	N/A	N/A	N/A
	➤ Jockey pump head	N/A	N/A	N/A
	➤ Standby Pump out put	N/A	N/A	N/A
	➤ Standby Pump Head	N/A	N/A	N/A
	➤ Auto Starting/ Manual stopping	N/A	N/A	N/A
	➤ Pump House Access	N/A	N/A	N/A
	• Terrace level	----	-----	-----
	➤ Discharge of pump	220 LPM	Provided	MR
	➤ Head of the pump	40 mts	Provided	MR
	➤ Power Supply	Required	Provided	MR
	➤ Auto Starting of pump	Required	Provided	MR

Dr

14	Captive Water Storage for fire fighting			
	<ul style="list-style-type: none"> Underground tank capacity 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Draw-off connection 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Fire service inlet 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Access to tank 	N/A	N/A	N/A
	<ul style="list-style-type: none"> • Overhead Tank capacity 	N/A	N/A	N/A
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.	Not Applicable		
	<ul style="list-style-type: none"> Pressurization of Lift Shaft 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Pressurization of Lift lobby 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Communication In lift Car 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Fireman's Grounding Switch 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Lift Signage 	N/A	N/A	N/A
17	Standby power supply	N/A	N/A	N/A
18	Refuge Area.			
	<ul style="list-style-type: none"> ➤ Total Area 	N/A	N/A	N/A
	<ul style="list-style-type: none"> ➤ Location 	N/A	N/A	N/A
19	Fire Control Room			
	<ul style="list-style-type: none"> Detector System Panel 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Flow Switch Panel 	N/A	N/A	N/A
	<ul style="list-style-type: none"> PA System Panel 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Batter backup 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Building Floor Plans 	N/A	N/A	N/A
20	Special Fire Protection Systems for Protection of special Risks, if any:	N/A	N/A	N/A

The fire protection systems provided in the building were checked and found functional at the time of inspection.

In view the deemed compliance of the minimum standards on fire prevention and fire safety measures as required under the rules, the NOC issued vide letter No. F6/DFS/MS/School/2017/WZ/469 dated 29/03/2017, renewal under D.o.E cir. No. 262-362 dated 17.01.2005, is recommended.

DFA is put up for approval & signature please.

Aman Kumar Lathar
01/02/22

Signature of the Inspecting Officer
(Aman Kumar Lathar)
Asst. Divisional Officer (JWP)

D.O. (West Division)

[Handwritten signatures and dates]
02/02/2022
37/07/2022
Defo (w2)
AAJ/TWP
R.S.O