

C-49

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI – 110001

No.F6/DFS/MS/School/NDZ/2022/ 527

Dated: 17/05/2022

FIRE SAFETY CERTIFICATE

Certified that the **St. Xavier's School** located at **04 Raj Niwas Marg, Delhi-54** comprised of ground + 3 upper floor (School Block) & ground + one (Multi Purpose hall) was granted Fire Safety Certificate by this department vide Letter no.- F6/DFS/MS/School/2018/NDZ/464 dated 20.03.2018. The premises/ school building was re-inspected by the officer concerned of this department on 06.05.2022 in the presence of Mr. Jose Victoria (P.A. to Principal) and found that the school building have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of Delhi Fire Service Rules 2010 and the premises / building is fit for occupancy, class **B "Educational Building"** except high rise block i.e. Ground + 05 upper floors with effect from 17/05/2022 for a period of three years, in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010, mentioned below.

Issued on 17/05/2022 at New Delhi by.


13/5/22

(Dr. S.K. Tomar)

Dy. Chief Fire Officer

Tel: 011-23412025

82
12/5

Copy to:-

1. The Director of Education, Govt. of NCT of Delhi, Old Secretariat, Delhi.
2. The Principal/HOS, St. Xavier's School at 04 Raj Niwas Marg, Delhi-54

Conditions for the validity of Fire Safety Certificate:-

1. The owner /occupier shall apply for renewal of this fire safety certificate to the Director in form J' [sub Rule (1) of rule 37] along with a copy of this certificate, six months prior to its expiry.
2. All the means of escape shall be kept free of all the type of obstruction all the time.
3. All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
4. All the fire fighting equipments shall be maintained in perfect working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
5. The clarification with regards electrical installation, ventilation, structure stability set back areas, occupancy and constructional deviation in building etc .may be got verified from the authorities concerned.
6. This Fire Safety Certificate cannot be treated in any case for regularizations of unauthorized construction unauthorized use of land if any.
7. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on www.dfs.delhigovt.nic.in.

- 11/26 -

INSPECTION REPORT

1	Name & address of the building	St. Xavier's School located at 04, Raj Niwas Marg, Civil Line, Delhi - 54		
2	Building is comprised of	Ground + 03 upper floor (School Block) & ground + one (Multi purpose hall)		
3	Type of Occupancy	Group-B Educational		
4	Type of Case	Renewal		
5	Details of Previous FSC	F6/DFS/MS/School/2018/NDZ/464 dated 20.03.2018		
6	Fire Safety direction letter No	Nil (Old Case)		
7	Date of Inspection	06.05.2022		
8	Name of the Inspecting Officers	Sumit Kumar ADO (SPM)		
9	Name of the designation of Officer from the building side	Mr. Jose Victoria (P.A. to Principal)		
10	Year of Construction	2000		
11	Applicant's letter No	Outdoor diary no. 264 dated 08.04.2022		Old Case
S.No	Minimum Standards on fire Prevention and fire safety U/R 33	As per Education Circular	Provided at site	Remarks MR/NMR
1	Access to building			
	Road width	6 mtrs.	09 mtrs.	MR
	Gate width	05 mtrs.	05 mtrs.	MR
	Width of internal road	N/A	N/A	N/A
2	Number, Width, Type and Arrangement of Exits			
	A Number of staircases			
	a Upper floor	02 nos. each	02 nos. each block	MR
	b Basement	N/A	N/A	N/A
	B Width of staircases			
	a Upper floor	1.5 mtrs	02 nos in Senior block 1.50 mtr. Each, 02 nos. 1.7 mtr & 1.8 mtr in multi purpose hall	MR
	b Basement	N/A	N/A	N/A
	C Protection of exits			
	a Fire check door	N/A	N/A	N/A
	b Pressurization	N/A	N/A	N/A
	D No. of continuous staircases to terrace	01 nos.	01 nos.	MR
	E Width of corridor	N/A	N/A	N/A
	G Door size	1.5 mtrs.	1.5 mtrs.	MR
3	Compartmentation			
	A Fire check door	N/A	N/A	N/A
	B Sealing of electrical shafts	N/A	N/A	N/A
	C Fire rating of shaft door	N/A	N/A	N/A
	D Water curtain	N/A	N/A	N/A
	E Fire dampers	N/A	N/A	N/A
4	Smoke Management System.			
	A Basement	30a/c per hour	N/A	N/A
	B Upper floor	12a/c per hour	Natural	N/A

2.
10/22

5.	Fire Extinguisher				
	A	Total numbers	28 nos.	28 nos.	MR
	B	Types	CO ₂ & ABC	CO ₂ & ABC	MR
	C	ISI marking	ISI marked	ISI marked	MR
6	First-aid-Hose Reels.				
	A	Total numbers of each floor	01 nos. each block	01 nos. each block	MR
	B	Length of hose reel hose	30 mtrs.	30 mtrs.	MR
	C	Nozzle diameter	5 mm	5 mm	MR
7	Automatic fire detection and alarming system.				
	A	Type of detectors	N/A	N/A	N/A
	B	Location of main panel	N/A	N/A	N/A
	C	Location of repeater panel	N/A	N/A	N/A
	D	Alternate source of power	N/A	N/A	N/A
	E	Hooters	N/A	N/A	N/A
8	MOEFA				
			N.A	N/A	N/A
9	Public address System.				
			N.A	N/A	N/A
10	Automatic Sprinkler System.				
	A	Basement	N/A	N/A	N/A
	B	Upper floor	N/A	N/A	N/A
	C	Sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants				
	A	Size of riser/down-comer	100 mm	100 mm	MR
	B	Number of hydrants per floor	01	01	MR
	C	Hose box	01	01	MR
12	Yard Hydrants.				
	A	Total number of hydrants	N/A	N/A	N/A
	B	Hose box	N/A	N/A	N/A
13	Pumping Arrangements.				
	Ground Level				
	A	Discharge of main pump	N/A	N/A	N/A
	B	Head of main pump	N/A	N/A	N/A
	C	Number of main pumps	N/A	N/A	N/A
	D	Jockey pump out put	N/A	N/A	N/A
	E	Jockey pump head	N/A	N/A	N/A
	F	Standby pump out put	N/A	N/A	N/A
	G	Standby pump head	N/A	N/A	N/A
	H	Auto starting /manual stopping	N/A	N/A	N/A
	I	Pump house access	N/A	N/A	N/A
	Terrace Level				
	A	Discharge of pump	450 LPM	450 LPM	MR
	B	Head of the pump	40 mtrs.	40 mtrs.	MR
	C	Power supply	Required	Provided	MR
	D	Auto starting of pump	Required	Provided	MR

5-Pl...
3/11/21

14	Captive Water Storage for Fire Fighting.				
	A	Underground tank capacity	N/A	N/A	N/A
	B	Draw-off connection	N/A	N/A	N/A
	C	Fire service inlet	N/A	N/A	N/A
	D	Access to tank	N/A	N/A	N/A
	E	Overhead tank capacity	2500 & 5,000 Ltrs	5,000 Ltrs	MR
15	Exit Signage.		Required	Provided	MR
16	Provision of Lifts.				
	A	Pressurization of lift shaft	N/A	N/A	N/A
	B	Pressurization of lift lobby	N/A	N/A	N/A
	C	Communication in lift car	N/A	N/A	N/A
	D	Firemen's grounding switch	Required	Provided	MR
	E	Lift signage	Required	Provided	MR
17	Standby power supply		Required	Provided	MR
18	Refuge Area.				
	A	Total area	N/A	N/A	N/A
	B	Location	N/A	N/A	N/A
19	Fire Control Room				
	A	Detector system panel	N/A	N/A	N/A
	B	Flow switch panel	N/A	N/A	N/A
	C	Pa system panel	N/A	N/A	N/A
	D	Battery backup	N/A	N/A	N/A
	E	Building floor plans	N/A	N/A	N/A
20	Special Fire Protection systems for protection of special Risks, if any:		N.A		N/A

The fire protection systems provided in the school building were tested, checked at random and found functional at the time of inspection.

In view of deemed compliance of the minimum standards on fire prevention and fire safety measures as required under the rules the FSC issued vide letter no. F6/DFS/MS/School/2018/NDZ/464 dated 20.03.2018, renewal under rule 37 of the Delhi Fire Service rules 2010, is recommended.

Sumit Kumar
11/05/22

Signature of the Inspecting Officer
Name Sumit Kumar
Designation ADO (SPM)



DO (ED)
[Signature]
11/5/22

[Signature]
Dy. C.F.O. (NDZ)

[Signature]
11/5/22

A DO (SPM) F.T. letter is put up for signature, please.

Sumit Kumar
12/05/22

Dy. C.F.O. (NDZ)

[Signature]
13/5/22