

2115

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEADQUARTERS: DELHI FIRE SERVICE, CONNAUGHT PLACE**  
**NEW DELHI- 110001**


No.F.6/DFS/MS/EH/2022/SZ/ 191

Dated: 04/07/2022

**FIRE SAFETY CERTIFICATE**

Certified that the M/s Barshala (A unit of Indospirit Bar Pvt. Ltd.), situated at GF, Shop No. 4, 5, 6 & 7 PD area, Uttam Nagar East Metro Station, New Delhi-110058, owned/occupied by A unit of Indospirit Bar Pvt. Ltd. have complied with the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules 2010 and verified by the officer concerned of this department on 20/06/2022 in the presence of Mr. Nitin Kapoor and found that the building is fit for occupancy 'Group D "Assembly Building"(Restaurant) with effect from 04/07/2022 for a period of **three** years in accordance with the Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010, printed below.

Issued on..... 04/07/2022 ..... at New Delhi by

  
(Atul Garg)

**Director**

Delhi Fire Service

o/c

To,

The Manager, M/s Barshala (a unit of Indospirit Bar Pvt. Ltd.)  
GF, Shop No. 4, 5, 6 & 7 PD area, Uttam Nagar East Metro Station, New Delhi.

Copy to:-

The Joint Commissioner of Police, Licensing Unit, First Floor, Police Station,  
Defence Colony, New Delhi.

**Following fire safety directives must be adhered to:-**

- The owner /occupier shall apply for renewal of this fire safety certificate to the Director in form J' [sub rule (1) of rule 37] along with a copy of this certificate, six months prior to its expiry.
- All the means of escape shall be kept free of all the type of obstruction all the time.
- All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
- All the fire fighting equipments shall be maintained in perfect working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
- The clarification with regards electrical installation, ventilation, structure stability set back areas, occupancy and constructional deviation in building etc .may be got verified from the authorities concerned.
- This Fire Safety Certificate can not be treated in any case for regularizations of unauthorized construction unauthorized use of land if any.
- The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on [www.dfs.delhigovt.nic.in](http://www.dfs.delhigovt.nic.in)

N/2

### INSPECTION REPORT

1. Name & address of the building : M/s Barshala (A unit of Indospirit Bar Pvt. Ltd.), GF, Shop No. 4, 5, 6 & 7 PD area, Uttam Nagar East Metro Station, New Delhi.
2. Building comprised of : ground floor only
3. Type of Occupancy : Group D (Assembly)
4. Type of Case : New
5. Details of Previous NOC : N/A
6. Fire Safety directives letter No : N/A
7. Date of inspection : 20/06/2022
8. Name of Inspecting Officers : A.D.O. R.K.Yadav & DO Vedpal Chhikara
9. Name and designation of officers  
From the building side : Sh. Nitin Kapoor
10. Year of Construction : Before 2009
11. Applicant's letter No. : ID No. 2022052511174 dated 25/05/2022

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	Requirements	Provided at site	Remarks MR/NMR
1.	<b>Access to building</b>			
	<ul style="list-style-type: none"> <li>• Road width</li> <li>• Gate width</li> <li>• Width of internal road</li> </ul>	09 m N/A N/A	12 M Provided N/A N/A	M/R N/A N/A
2.	<b>Number, Width, Type &amp; Arrangement of Exits</b>	(Restaurant is running at GF only)		
	a. Number of staircases			
	<ul style="list-style-type: none"> <li>• Upper Floors</li> <li>• Basements</li> </ul>	N/A N/A	N/A N/A	N/A N/A
	b. Width of staircases			
	<ul style="list-style-type: none"> <li>• Upper Floor</li> <li>• Basements</li> </ul>	N/A N/A	N/A N/A	N/A N/A
	c. Protection of exits			
	<ul style="list-style-type: none"> <li>• Fire check door</li> <li>• Pressurization</li> </ul>	N/A N/A	N/A N/A	N/A N/A
	d. No. of continuous staircases to terrace	N/A	N/A	N/A
	e. Width of Corridor	N/A	N/A	N/A
	f. Door Size	2 X 1.50 m	3X 1.50 m	MR
3.	<b>Compartmentation</b>			
	<ul style="list-style-type: none"> <li>• Fire check door</li> <li>• Sealing of electrical shafts</li> <li>• Fire Rating of shaft door</li> <li>• Water Curtain</li> <li>• Fire Dampers</li> </ul>	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A
4.	<b>Smoke Management System</b>			
	<ul style="list-style-type: none"> <li>• Basements</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>• Ground floor</li> </ul>	Required	Natural Ventilation	M/R
5.	<b>Fire Extinguishers</b>			
	<ul style="list-style-type: none"> <li>• Total numbers in restaurant</li> <li>• Types</li> <li>• IS marking</li> </ul>	06 no.'s ABC/CO <sub>2</sub> ISI marked	Provided Provided Provided	M/R M/R M/R

6.	<b>First-Aid Hose Reels</b>			
	<ul style="list-style-type: none"> <li>Total numbers for restaurant</li> </ul>	One	Provided	MR
	<ul style="list-style-type: none"> <li>Length of hose reel hose</li> </ul>	30 mtrs	Provided	MR
	<ul style="list-style-type: none"> <li>Nozzle diameter</li> </ul>	5 mm	Provided	MR
7.	<b>Automatic fire detection and alarming system in restaurant</b>			
	<ul style="list-style-type: none"> <li>Type of detectors Smoke/Heat</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Location of Main Panel</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Location of Repeater Panel</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Alternate source of power</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Hooters' Location</li> </ul>	N/A	N/A	N/A
8.	<b>MOEFA with talk back system</b>	Required	Provided	MR
9.	<b>Public Address System</b>	N/A	N/A	N/A
10.	<b>Automatic Sprinkler System</b>			
	<ul style="list-style-type: none"> <li>Basement</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Ground Floor at restaurant</li> </ul>	Required	Provided	MR
	<ul style="list-style-type: none"> <li>Sprinkler above false ceiling</li> </ul>	N/A	N/A	N/A
11.	<b>Internal Hydrants</b>			
	<ul style="list-style-type: none"> <li>Size of riser/down-comer</li> </ul>	100 mm	Provided	MR
	<ul style="list-style-type: none"> <li>Number of hydrants for restaurant</li> </ul>	One	Provided	MR
	<ul style="list-style-type: none"> <li>Hose Box</li> </ul>	One	Provided	MR
12.	<b>Yard Hydrants</b>			
	<ul style="list-style-type: none"> <li>Total number of hydrants</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Hose Box</li> </ul>	N/A	N/A	N/A
13.	<b>Pumping Arrangements</b>			
	<ul style="list-style-type: none"> <li>Ground Level                             <ul style="list-style-type: none"> <li>Discharge of main Pump</li> <li>Head of Main pump</li> <li>Number of main pumps</li> <li>Jockey Pump out put</li> <li>Jockey pump head</li> </ul> </li> <li>Standby Pump out put</li> <li>Standby Pump Head</li> <li>Water curtain Pump</li> <li>Auto Starting/Manual Stopping</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Pump House Access</li> </ul>			
	<ul style="list-style-type: none"> <li>Terrace level                             <ul style="list-style-type: none"> <li>Discharge of pump</li> <li>Head of the pump</li> <li>Power Supply</li> <li>Auto Starting of pump</li> </ul> </li> </ul>	450 LPM	Provided	MR
		40 mtrs	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
14.	<b>Captive Water Storage for fire fighting</b>			
	<ul style="list-style-type: none"> <li>Underground tank capacity for entire bldg.</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Draw-off connection</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Fire service inlet</li> </ul>	Required	Provided	MR
	<ul style="list-style-type: none"> <li>Access to tank</li> </ul>	N/A	N/A	N/A
	<ul style="list-style-type: none"> <li>Overhead Tank capacity</li> </ul>	20,000 ltrs	Provided	MR
15.	<b>Exit Signage.</b>	Required	Provided	MR

08/9

Provision of Lifts.				
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication In lift Car	N/A	N/A	N/A
	• Fireman's Grounding Switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17.	Standby power supply	Required	Provided	M/R
18.	Refuge Area.			
	➤ Total Area	N/A	N/A	N/A
	➤ Location	N/A	N/A	N/A
19.	Fire Control Room			
	• Detector System Panel	N/A	N/A	N/A
	• Flow Switch Panel	N/A	N/A	N/A
	• PA System Panel	N/A	N/A	N/A
	• Battery backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20.	Special Fire Protection System for Protection of special Risks, if any:	N/A	N/A	N/A

The fire protection systems provided in the building were tested, checked and found functional at the time of inspection. *The eating house is situated in Staircase Shops of ground floor only.*

In view of the above substantial compliance of the minimum standards of fire prevention and fire safety measures as required under the rules, it is recommended to grant Fire Safety Certificate under rule 35 of the Delhi Fire Service Rules 2010 .

*R.K. Yadav*  
 Signature of Inspecting Officer  
 Name:- R.K.Yadav  
 Designation:- Asstt. Divisional Officer

*Vedpal Chhikara*  
 Signature of Inspecting Officer  
 Name:- Vedpal Chhikara  
 Designation:- Divisional Officer

DCFO (South Zone)  
*[Signature]*  
 29/6  
 C.F.O.  
*[Signature]*  
 28/06/2022  
 Director  
*[Signature]*  
 20/06/22

FTPL  
*[Signature]*  
 20/6  
 AIO (JALPORA)