

431



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE
NEW DELHI-110001


No. F.6/DFS/MS/EH/2022/SZ/ 232

Dated 18/08/2022

FIRE SAFETY CERTIFICATE

Certified that **M/s RED CHIILLI** located at **Ground floor, S-15, Green Park, New Delhi 110016** in the building comprised of Basement ground plus 02 upper floors owned/occupied by **A Unit of Maag Entertainment Pvt Ltd** have complied with the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules, 2010 and verified by the officers concerned of this department on 30/07/2022 in the presence of Mr. Harish Kumar (Manager) and that the premises is fit for occupancy class **"Group-D Assembly Building" (Restaurant running at Ground Floor)** with effect from 18/08/2022 for a period of **Three years** in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 18/08/2022 at New Delhi by


(ATUL GARG)
DIRECTOR

DELHI FIRE SERVICE
pk

Copy to: -

1. The Dy. Health Officer, Public Health Department, South Zone, Green Park, Delhi-110016.(Ref. MHA Portal ID 2022071114403 dated 13/07/2022)
2. The Joint Commissioner of Police, Lic/Branch, 1st Floor, P S Defence Colony, New Delhi -110049
3. M/s RED CHIILLI located at Ground floor, S-15, Green Park, New Delhi 110016

Conditions for the validity of Fire Safety Certificate: -

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangement provided therein shall be maintained in good working condition at all time as seen during inspection. Any loss of life property due to non-functional fire safety measures shall be at the responsibility of the management.
3. All the staff members must know the correct method of operation of fire fighting system.
4. The basement shall be used as per the provisions of BBL /NBC Part- IV.
5. The owner/occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on www.dfs.delhigovt.nic.in
6. This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or alteration (Clause 1.4.3 of UBBL-2016), if any.
7. "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in form 'J' [sub rule (I) of rule 37] along with a copy of this Certificate, six month prior to its expiry."

117
INSPECTION REPORT

1	Name & Address of the Building	M/s RED CHILLI (Unit of Maag Entertainment Pvt Ltd) located at Ground floor S-15, Green Park, New Delhi 110016.		
2	Type of Occupancy	Group D Assembly Building. (Eating House)		
3	Building Comprised of	Basement, Ground plus 02 upper floors		
4	Type of Case	New Case		
5	Details of Previous NOC	Nil		
6	Fire Safety Directives Letter No	Nil		
7	Date of Inspection	30/07/2022		
8	Name of the Inspecting Officers	Sh. Rajesh Kumar, ADO (BCP)		
9	Name & Designation of Officers from the building side	Mr. Harish Kumar (Manager)		
10	Year of construction	2002	Restt. Running at GF only	
11	Applicant letter No.	MHA Portal No. 2022071114403 dated 13/07/2022		
S. No.	Minimum standards on Fire Prevention and Fire Safety U/R 33	UBBL/ NBC-2016	Provided at Site	Remarks MR/NMR
1	Access to Building.			
	<ul style="list-style-type: none"> Road width 	6 m	Provided	MR
	<ul style="list-style-type: none"> Gate width 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Width of internal road 	N/A	N/A	N/A
2	Number, width, type & arrangement of exits.			
	a) Number of Staircase	Restaurant at GF only		
	<ul style="list-style-type: none"> Upper floors. 	N/A	NA	N/A
	<ul style="list-style-type: none"> Basement floor. 	N/A	NA	N/A
	b) Width of Staircase			
	<ul style="list-style-type: none"> Upper floors 	N/A	NA	N/A
	<ul style="list-style-type: none"> Basement floor 	N/A	N/A	N/A
	c) Protection of exits			
	<ul style="list-style-type: none"> Fire check door 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Pressurization 	N/A	N/A	N/A
	d) No. of continuous staircase to terrace	N/A	N/A	N/A
	e) Width of corridor	N/A	N/A	N/A
	f) Door size	1.50 mtr each	1.50 mtr each	MR
3	Compartmentation.			
	<ul style="list-style-type: none"> Fire check door. 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Sealing of electrical shafts. 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Fire rating of shaft door. 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Water curtain 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Fire dampers. 	N/A	N/A	N/A
4	Smoke Management system.			
	<ul style="list-style-type: none"> Basement 	NA	N/A	N/A
	<ul style="list-style-type: none"> Upper floors 	NA	N/A	N/A
5	Fire Extinguishers.			
	<ul style="list-style-type: none"> Total numbers 	06 Nos	06 Nos	MR
	<ul style="list-style-type: none"> Types 	ABC/CO ₂	ABC-04 & CO ₂ -02	MR
	<ul style="list-style-type: none"> ISI Marking 	ISI marked	Provided	MR
6	First Aid Hose Reels.			
	<ul style="list-style-type: none"> Total numbers on each floor. 	One	Provided	MR
	<ul style="list-style-type: none"> Length of hose-reel hose. 	30m	Provided	MR

M/S

	• Nozzle Diameter	5mm	Provided	MR
7	Automatic fire detection & alarming system.			
	• Type of detectors	N/A	N/A	N/A
	• Location of Main Panel	N/A	N/A	N/A
	• Location of Repeater Panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooter's location	N/A	N/A	N/A
8	MOEFA	Required	Provided	MR
9	Public Address System	N/A	N/A	N/A
10	Automatic Sprinkler System			
	• Basement	N/A	N/A	N/A
	• Ground/ upper floors.	N/A	N/A	N/A
	= Sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants.			
	• Size of Riser/Down-comer	100 mm	Provided	MR
	• Number of Hydrant per floor	One	Provided	MR
	• Hose box.	One	Provided	MR
12	Yard Hydrants.			
	• Total number of hydrants.	N/A	N/A	N/A
	• Hose box.	N/A	N/A	N/A
13	Pumping arrangements.			
	• Ground Level			
	➤ Discharge of main pump.	N/A	N/A	N/A
	➤ Head of main pump.	N/A	N/A	N/A
	➤ Number of main pumps.	N/A	N/A	N/A
	➤ Jockey Pump output.	N/A	N/A	N/A
	➤ Jockey Pump head.	N/A	N/A	N/A
	➤ Standby Pump output.	N/A	N/A	N/A
	➤ Standby Pump head.	N/A	N/A	N/A
	➤ Auto Starting/Manual Stopping.	N/A	N/A	N/A
	➤ Pump house access.	N/A	N/A	N/A
	• Terrace Level			
	➤ Discharge of pump.	900 LPM	Provided	MR
	➤ Head of pump.	40m	Provided	MR
	➤ Power supply.	Required	Provided	MR
	➤ Auto starting of pump.	Required	Provided	MR
14	Captive water storage for fire fighting.			
	• Underground tank capacity.	N/A	N/A	N/A
	➤ Draw-off connection.	N/A	N/A	N/A
	➤ Fire Service Inlet.	N/A	N/A	N/A
	➤ Access to tank.	N/A	N/A	N/A
	• Overhead tank capacity.	20,000 Ltrs	Provided	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.			
	• Pressurization of lift shaft.	N/A	N/A	N/A
	• Pressurization of lift lobby.	N/A	N/A	N/A
	• Communication in lift car.	N/A	N/A	N/A
	• Fireman's switch.	N/A	N/A	N/A
	= Lift signage.	N/A	N/A	N/A
17	Standby Power Supply	Required	Provided	MR
18	Refuge Area			

N/A

MR	• Total area	N/A	N/A	N/A
	• Location	N/A	N/A	N/A
N/A	19 Fire Control Room.			
N/A	• Detector system panel.	N/A	N/A	N/A
N/A	• Flow switch panel.	N/A	N/A	N/A
N/A	• PA system panel.	N/A	N/A	N/A
N/A	• Battery backup.	N/A	N/A	N/A
N/A	• Building floor plan.	N/A	N/A	N/A
N/A	20 Special Fire Protection System for the Protection of special Risk, if any.	N/A	N/A	N/A

The Fire protection systems provided in the building were test checked at random and found functional at the time of inspection.

Further, the party has complied all the observation / Shortcoming already issued & communicated by this department vide letter of even no 410 dated 14/06/2022.

Keeping in view of the substantially satisfactory compliance of the minimum standards on fire prevention and fire safety measures as required under the rules, it is recommended to issue Fire Safety Certificate under rule 35 (3) of the Dehni Fire Service Rules, 2010

[Signature]
Signature of the Inspecting Officer
Name: Sh. Rajesh Kumar
Designation: ADO (BCP)

Dy. CFO (SZ)

[Signature]
5/8

C.F.O. *[Signature]*
8/8/2022

Director / *[Signature]*
8/8/22 FI PL

[Signature]

As approved, F.T. letter is put up for your signature PI

Director / *[Signature]*
12/8/22

1/14
11/8/2022

[Signature]

Uploaded
18/8/22
[Signature]