

C-41

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEAD QUARTERS: DELHI FIRE SERVICE: NEW DELHI - 110001**


No. F6/DFS/MS/2022 /School/ 1230

Dated: 14/11/2022

**FIRE SAFETY CERTIFICATE**

Certified that the **Govt. Boys Senior Secondary School (I.D No 2 07114)** located at **Nehru Vihar, Delhi-110036** comprised of **single old block ground & 03 upper floors only** owned/ occupied by **Govt. Boys Senior Secondary School** was issued Fire Safety Certificated vide this office letter no. **F6/DFS/MS/School/2019/2023 dated 21.10.2019** the premise was re-inspected by the officer concerned of this department on **04.11.2022** in the presence of **Sh. Sahani (Principal)** and observed that all the fire prevention and fire safety arrangements as provided in the premise found in good working condition. The premise have therefore deemed complied with the requirements under rule 33 of the Delhi Fire Service Rules, 2010 and the building premise is fit for occupancy under **Educational "Group B"** with effect from **14/11/2022** for a period of **three years** in accordance with the rule 36 unless renewed under rule 37 or sooner cancelled under rule 40, subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010,

Issued on **14/11/2022** at New Delhi by

  
(Dharampal Bhardwaj)  
Dy. Chief Fire Officer  
Ph:-011-23414250  
dc go

Copy to: -

1. The Director, Education, Government of N.C.T of Delhi, Old Sectt. Delhi - 110054;
2. The Principal, Govt. Boys Senior Secondary School (I.D No-2107114) located at Nehru Vihar, Delhi-110036.

**Conditions for the validity of Fire Safety Certificate:**

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangements provided therein shall be maintained in good working condition at all time as seen during inspection.
3. Any loss of life or property due to non-functional fire safety measures shall be at the responsibility of the management.
4. All the staff members must know the correct method of operation of firefighting system.
5. The owner / occupier shall submit a declaration **every year in Form "K"** provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on <http://delhi.gov.in/wps/wcm/connect/doit/fire/FIRE/Home/Forms>.
6. This fire safety certificate may not in any way be treated as regularization ( Clause 2 8 of UBBL-2016) of unauthorized construction or Alteration ( Clause 1.4.3 of UBBL-2016), if any.
7. "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in **Form 'J'** [sub rule (1) of rule 37] along with a copy of this Certificate, **six months** prior to its expiry".

6	<b>First-Aid Hose Reels.</b>			
	• Total numbers on each floor	02	02	MR
	• Length of hose reel hose	30m	30m	MR
	• Nozzle diameter	5mm	5mm	MR
7	<b>Automatic fire detection and alarming system.</b>			
	• Type of detectors	NA	NA	NA
	• Location of Main Panel	NA	NA	NA
	• Location of Repeater Panel	NA	NA	NA
	• Alternate source of power	NA	NA	NA
	• Hooters' Location	NA	NA	NA
8	<b>MOEFA</b>			
9	<b>Public Address System.</b>			
10	<b>Automatic Sprinkler System.</b>			
	• Basement	NA	NA	NA
	• Upper Floor	NA	NA	NA
	• Sprinkler above false ceiling	NA	NA	NA
11	<b>Internal Hydrants</b>			
	• Size of riser/down-comer	NA	02 (100mm)	NA
	• Number of hydrants per floor	NA	Provided	NA
	• Hose Box	NA	Provided	NA
12	<b>Yard Hydrants.</b>			
	• Total number of hydrants	NA	NA	NA
	• Hose Box	NA	NA	NA
13	<b>Pumping Arrangements.</b>			
	• Ground Level			
	➤ Discharge of main Pump	NA	NA	NA
	➤ Head of Main pump	NA	NA	NA
	➤ Number of main pumps	NA	NA	NA
	➤ Jockey Pump out put	NA	NA	NA
	➤ Jockey pump head	NA	NA	NA
	➤ Standby Pump out put	NA	NA	NA
	➤ Standby Pump Head	NA	NA	NA
	➤ Auto Starting Manual stopping	NA	NA	NA
	➤ Pump House Access	NA	NA	NA
	• Terrace level			
	➤ Discharge of pump	450lpm	450lpm	MR
	➤ Head of the pump	40m	40m	MR
	➤ Power Supply	Required	Provided	MR
➤ Auto Starting of pump	Required	Provided	MR	
14	<b>Captive Water Storage for fire fighting.</b>			
	• Underground tank capacity	NA	50,000ltr	NA
	➤ Draw-off connection	NA	NA	NA
	➤ Fire service inlet	NA	NA	NA
	➤ Access to tank	NA	NA	NA
	• Overhead Tank capacity	10,000ltrs	10000ltr	MR
15	<b>Exit Signage.</b>			
	Required	Provided	MR	

**INSPECTION REPORT**

1. Name & address of the building	Govt. Boys Sr. Sec. School at Nehru Vidyan, Delhi-110054
2. Type of Occupancy	Educational
3. Composition of building	Single Old Block (Ground & 03 upper floors)
4. Type of Case	Renewal
5. Details of previous NOC	E-6 DIS MS School 2019-2023, dated 21.10.2019
6. Fire Safety directives letter No	Nil
7. Date of inspection	09.11.2022
8. Name of the Inspecting Officers	ADO (RN)
9. Name and designation of officers from the building side	Sh. S.K. Sahani (Principal)
10. Year of Construction	1984
11. Applicant's letter No	GBSSS NV 2022-213, dated 12.10.2022

Minimum Standards on fire prevention and fire safety U/R 33	NBC Requirement	Provided at site	Remarks MR/NMR
<b>1. Access to building</b>			
• Road width	Accessible	Accessible	MR
• Gate width	Accessible	Accessible	MR
• Width of internal road	NA	NA	NA
<b>2. Number, Width, Type &amp; Arrangement of Exits</b>			
<b>a. Number of staircases</b>			
• Upper Floors	01	01	MR
• Basements	01	01	NA
<b>b. Width of staircases</b>			
• Upper Floors	1.5 m	1.5 m x 2 & 1.33 m x 2	MR
• Basements	NA	NA	NA
<b>c. Protection of exits</b>			
• Fire check door	NA	NA	NA
• Pressurization	NA	NA	NA
• No. of continuous staircases to terrace	02	02	MR
e. Width of Corridor	2m	2.65m	MR
f. Door Size	1 m	1.02m double door	MR
<b>3. Compartmentation.</b>			
• Fire check door	NA	NA	NA
• Sealing of electrical shafts	NA	NA	NA
• Fire Rating of shaft door	NA	NA	NA
• Water Curtain	NA	NA	NA
• Fire Dampers	NA	NA	NA
<b>4. Smoke Management System.</b>			
• Basements	12 a/c per hour	NA	NA
• Upper floors	12 a/c per hour	Natural Ventilated	MR
<b>5. Fire Extinguishers</b>			
• Total numbers	32nos	40nos	MR
• Types	ABC Co <sup>2</sup>	10- ABC	MR
• ISI marking	ISI Marked	Provided	MR

6	<b>First-Aid Hose Reels.</b>			
	• Total numbers on each floor	02	02	MIR
	• Length of hose reel hose	30m	30m	MIR
	• Nozzle diameter	5mm	5mm	MIR
7	<b>Automatic fire detection and alarming system.</b>			
	• Type of detectors	NA	NA	NA
	• Location of Main Panel	NA	NA	NA
	• Location of Repeater Panel	NA	NA	NA
	• Alternate source of power	NA	NA	NA
	• Hooters' Location	NA	NA	NA
8	<b>MOEFA</b>	NA	NA	NA
9	<b>Public Address System.</b>	NA	NA	NA
10	<b>Automatic Sprinkler System.</b>			
	• Basement	NA	NA	NA
	• Upper Floor	NA	NA	NA
	• Sprinkler above false ceiling	NA	NA	NA
11	<b>Internal Hydrants</b>			
	• Size of riser down-comer	NA	02 (100mm)	NA
	• Number of hydrants per floor	NA	Provided	NA
	• Hose Box	NA	Provided	NA
12	<b>Yard Hydrants.</b>			
	• Total number of hydrants	NA	NA	NA
	• Hose Box	NA	NA	NA
13	<b>Pumping Arrangements.</b>			
	• Ground Level			
	➤ Discharge of main Pump	NA	NA	NA
	➤ Head of Main pump	NA	NA	NA
	➤ Number of main pumps	NA	NA	NA
	➤ Jockey Pump out put	NA	NA	NA
	➤ Jockey pump head	NA	NA	NA
	➤ Standby Pump out put	NA	NA	NA
	➤ Standby Pump Head	NA	NA	NA
	➤ Auto Starting / Manual stopping	NA	NA	NA
	➤ Pump House Access	NA	NA	NA
	• Terrace level			
	➤ Discharge of pump	450lpm	450lpm	MIR
	➤ Head of the pump	40m	40m	MIR
	➤ Power Supply	Required	Provided	MIR
	➤ Auto Starting of pump	Required	Provided	MIR
14	<b>Captive Water Storage for fire fighting.</b>			
	• Underground tank capacity	NA	50,000ltr.	NA
	➤ Draw-off connection	NA	NA	NA
	➤ Fire service inlet	NA	NA	NA
	➤ Access to tank	NA	NA	NA
	• Overhead Tank capacity	10,000ltrs	10000ltr	MIR
15	<b>Exit Signage.</b>	Required	Provided	MIR

N/22

16	<b>Provision of Lifts.</b>			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication In lift Car	N/A	N/A	N/A
	• Fireman's Grounding Switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17	<b>Standby power supply</b>	N/A	N/A	N/A
18	<b>Refuge Area.</b>			
	➤ Total Area	N/A	N/A	N/A
	➤ Location	N/A	N/A	N/A
19	<b>Fire Control Room</b>			
	• Detector System Panel	N/A	N/A	N/A
	• Flow Switch Panel	N/A	N/A	N/A
	• PA System Panel	N/A	N/A	N/A
	• Batter backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	<b>Special Fire Protection Systems for Protection of special Risks, if any</b>	N/A	N/A	N/A

The fire protection systems provided in the building were tested/ checked randomly and found in working condition at the time of inspection.

Keeping in view the satisfactory compliance of the minimum standards on fire prevention and fire safety required as stipulated in NBC Part-IV, it is recommended to renewal of fire safety certificate issued vide this department letter of even no 2023 dated 21.10.2019.

DO NW → ON M/22  
 Dy CPO (WZ)

*[Handwritten Signature]*  
 9/11/22

*[Signature]*  
 Signature of the Inspecting Officer  
 Name - C.L. Meena  
 Designation - ADO RN

~~ADO RN~~

As approved F.T. letter is put up for your signature please.

Dy CPO (WZ)

*[Handwritten Signature]*  
 11/11/22

*[Signature]*  
 11/11/2022

MST ceep