

# GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELIH HEADQUARTERS: DELIH FIRE SERVICE: NEW DELIH- 110001



~ ....

Dated: 01 /02 /2023

Ph-011

9C

No. F6/DFS/MS/2023/EH/ 43

## FIRE SAFETY CERTIFICATE

Certified that the Cling Kitchen And Bar (A Unit of NGR Hospitalities Pvt. Ltd) located at  $3^{rd}$  Floor, Property No-21&31, Mall Road, Near D.U, Metro Station, Delhi-110054 in a building comprised of basement. ground and 03 upper floors owned/ occupied by Cling Kitchen And Bar (A Unit of NGR Hospitalities Pvt. Ltd) have complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules. 2010 and verified by the officer concerned of Fire Service on 30.01.2023 in the presence of Sh. Raj Makkar and that the building/ premise is fit for occupancy Class Assembly (Restaurant) at third floor only with effect from o1/o2/2023 for a period of 03 (Three) years in accordance with rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on ....01. 02 2023 at New Delhi by

Copy to:-

 Cling Kitchen And Bar (A Unit of NGR Hospitalities Pvt. Ltd) located at 3<sup>rd</sup> Floor. Property No-21&31. Mall Road, Near D.U, Metro Station, Delhi-110054.

## Conditions for the validity of Fire Safety Certificate:


- 1. This Fire Safety Certificate is valid only for restaurant at third floor for assembly occupancy only. In case of any violation, this FSC will be treated as null & void.
- 2. All the means of escape/entry/exit shall be kept free from any obstruction.
- 3. All the fire safety arrangements provided therein shall be maintained in good working condition at all time as seen during inspection.
- 4. Any loss of life or property due to non-functional fire safety measures shall be at the responsibility of the management.
- 5. All the staff members must know the correct method of operation of firefighting system.
- The owner / occupier shall submit a declaration every year in Form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on http://delhi.gov.in./wps/wcm/connect/doit fire/FIRE/Home/Forms.
- This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or Alteration (Clause 1.4.3 of UBBL-2016), if any.
- "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".

CII

	٠	
		-
N	4	5
	1	-
	- 1	

# INSPECTION REPORT

		Instru	TION REPORT		
1.	Name & address of the building	: Cling Kitch	nen And Bar (A Unit of	NGR Hospitalities Pvt.	Ltd.) at Property
				oad, Near D.U, Metro St	
2.	Type of Occupancy		(Assembly)		
3.	Type of Case	New Case	(restemoly)		
4	Composition of building		Convert 8.02		t third from
	composition of building			ors but Restaurant propo	
			ent- vacant, ground- mode	ern bazaar, first floor- saloo	n & 2 <sup>nd</sup> floor-vacan
5.	Details of previous NOC	Nil			
6.	Fire Safety directives letter No	Nil			
7.	Date of inspection	30.01.2023			
8.	Name of the Inspecting Officers	: ADO (RN)	•		
0	Name and designation of officers				
	from the building side	Sh. Raj M	akkar		
10	Year of Construction	2002			
11	Applicant's letter No.	Online I D	No. 2023010300064 D	ated 25.01.2023	
1	Minimum Standards on fire pre		UBBL-2016/NBC		Remarks
	fire safety U/R 33		Part-IV Requiremen		MR/NMR
	Access to building				
	Road width		06	12m	MR
	Gate width		4.5m	4.5m	MR _
	Width of internal road		ΝΛ	NA	ΝΛ
2	Number, Width, Type & Arrange	mont of Frite			
-	Runber, width, Type & Arrange	ement of Exits			
	a. Number of staircases	in the party of the			
	Upper Floors		02	02	MR
	• Basements		ΝΛ	NΛ	NA
	b. Width of staircases		02m & 1.5m	Provided	MR
	Upper Floors		02m & 1.5m		
	Basements		NΛ	NA	NA
	c. Protection of exits				
	Fire check door		Required NA	Provided NA	MR
	Pressurization		02	02	MR
	d. No. of continuous staircases to t	errace			NA
	e Width of Corridor		NA 2.0 - 8 - 1 50m	NA Provided	
	f. Door Size		2.0m & 1.50m	Provided	MR
3	Compartmentation.				
	Fire check door		Required	Provided	MR
	Sealing of electrical shafts		NA	NA	NA
	Fire Rating of shaft door		NA	NΛ	NA
	Water Curtain		NA	ΝΛ	NA
	Fire Dampers		ΝΛ	NA	NA
4	Smoke Management System.				
	Basements		12 a/c per hour	NA	NA
	Upper floors		12 a/c per hour	Provided	MR
5	Fire Extinguishers				
	Total numbers		06nos	08nos	MR
	• Types		ABC Co2	ABC-06 Co2-2	MR
	1SI marking		Yes	Yes	MR
		3	- 6 k	C	



r

MR

MR

MR

MR

MR

NA

MR

Provided

Provided

Provided

Provided

Provided

Provided

Provided

Provided

Provided

	<ul> <li>Hooters' Location</li> </ul>	Durvingd	Provided	MR
s	MOEFA	Required	NA	NA
-		NA	NA	
9	Public Address System.			
10	Automatic Sprinkler System. NA NA			NA
		NA		
	Basement	Required	Provided	MR
	<ul> <li>Upper Floor (Third floor)</li> </ul>	nequire		
	a state have false ceiling	NA	NA	NA
	Sprinkler above faise certing			
11	Internal Hydrants			MR
		100mm	Provided	
	Size of riser/down-comer	01	Provided	MR
	<ul> <li>Number of hydrants per floor</li> </ul>			MR
		01	Provided	NIN
	Hose Box			-
12	Yard Hydrants.			
		NA	NA	NA
	<ul> <li>Total number of hydrants</li> </ul>			
	Hose Box	NA	NA	NA
	• Hose box			
13	Pumping Arrangements.			-
	Ground Level			
	Di Lana Carain Dump	2280 LPM	Provided	MR
		80m	Provided	MR
	<ul> <li>Head of Main pump</li> </ul>	som		
	<ul> <li>Number of main pumps</li> </ul>	02nos	Provided	MR

1801pm

60m

2280 LPM

(Diesel operative)

80m

Required

450 LPM

40m

Required

Required

- Number of main pumps
- Jockey Pump out put
- Jockey pump head
- Standby Pump out put
   Standby Pump Head
- Auto Starting Manual stopping

Auto Starting of pump

- Pump House Access
- Terrace level

6

7

- Discharge of pump
- Head of the pump
- Power Supply
- 14 Captive Water Storage for fire fighting.

#### MR 1,00,000 L T R Provided Underground tank capacity Draw-off connection NA NA NA Fire service inlet NA NA NA Access to tank NA NA NA Overhead Tank capacity 5.000 LTR Provided MR MR Required Provided 15 Exit Signage.



N	17
---	----

-		One Passenger Lift		NΛ
P	rovision of Lifts.	N/A	N/A	
, -	Pressurization of Lift Shaft	N/A	N/A	N/A
	Pressurization of Lift lobby	Required	Provided	MR
	Communication In lift Car	Required	Provided	MR
	Fireman's Grounding Switch		Provided	MR
	Lift Signage	Required		MR
	Standby power supply	Required	Provided	
7	Standby power supply			
18 Refuge Area.	Refuge Area.	N/A	N/A	ΝΛ
T	- Total Area	N/A	N/A	N/A
	<ul> <li>Location</li> </ul>			
19	Fire Control Room	N/A	N/A	NΛ
t	Detector System Panel		N/Λ	NΛ
	Flow Switch Panel	N/A		ΝA
PA System Panel	PA System Panel	N/A	N/A	
	Batter backup	ΝA	ΝA	NΛ
	Building Floor Plans	NA	NΛ	NΛ
		NA	NΛ	NA
20	Special Fire Protection Systems for Protection of special Risks, if any			

Note:-

a. The total covered area of the third floor Restaurant is 500sqm (Approx) including seating area, toilet area, bar area, & store area.

# b. As per the NBC Part IV, the number of occupants comes out to be approx278 person's i.e. (500/1 8=278)

(500/1.8=278) The fire protection systems provided in the building were tested/ checked and found in working order at the time of inspection. The observations/ shortcomings issued and communicated vide this department letter of even no. 37 dated 19.01.2023 have been compiled by the management.

department letter of even no. 37 dated 19.01.2023 have been compliced by internation and keeping in view of the substantial compliance of the minimum standards on fire prevention and fire safety required under the rules it is recommended to grant Fire Safety Certificate under rule 35 of

XI PLS

the Delhi Fire Service Rules 2010.

Signature of the Inspecting Officer Name: - C.L. Meena Designation:- ADO/RN

up ph

0112023 81/1/2013 Dineeta 0420 11