



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI-110001

No.F.6/DFS/MS/2023/CNG/ 132

Dated: 07/03/2023

FIRE SAFETY CERTIFICATE

Certified that the CNG Station located at NH-9 (Old Name NH-24) Vill- Khichripur, Teh-East Delhi, Khichripur, New Delhi-110091 building comprised of **Ground Floor only** owned / occupied by Indraprastha Gas Limited, have complied with the OISD-179 / Rule 33 of Delhi Fire Service, Rules 2010, and verified by the officer concerned of this department on 28/02/2023 in presence of **Sh. Raman Kumar, Manager (F&S)** and that the building / premises is fit for occupancy class Hazardous (Group -J) with effect from 07/03/2023 for a period of three years in accordance with rule 36 unless renewal under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the DFS rules, 2010.

Issued on 07/03/2023 at New Delhi by.


(ATUL GARG)
DIRECTOR
DELHI FIRE SERVICE.

o/c

Copy to :-

1. Sh. Ajay Khatri, DGM (Fire & Safety) IGL Bhawan, Plot No.4, Community Centre, R.K. Puram, Sector-9, New Delhi-110022.
2. Joint Commissioner, Licensing Unit, 1st Floor, P.S. Defence Colony, New Delhi-110024.

Conditions for the validity of Fire Safety Certificate:

1. All the fire safety arrangement provided their in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc. shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on www.dfs.delhigovt.nic.in
7. "The owner / Occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule37] along with a copy of this Certificate, six months prior to its expiry".

INSPECTION REPORT

N/3

1. Name & address of the building: **CNG Station, NH-9 (Old Name NH-24) Vill-Khichripur, Teh-East Delhi, Khichripur, New Delhi-110091.**
2. Type of Occupancy : **Hazardous (Ground Floor only)**
3. Type of Case : **New**
4. Details of previous NOC : **Nil**
5. Fire Safety directives Letter No. : **F6/DFS/MS/CNG/2020/3221 dated 31/12/2020**
6. Date of inspection : **28/02/2023**
7. Name of the Inspecting Officer : **A.K. Jaiswal, D.O. (East)**
8. Name and designation of Officer from the building side : **Mr. Raman Kumar, Manager (F&S)**
9. Year of Construction : **2020**

10. Applicant's letter No. : IGL/F&S/2023/15/02/1 dated 15/02/2023

S No	Minimum standards on fire prevention and fire safety U/R 33	BBL / NBC-IV / OISD / Guidelines Requirements	Provided at site	Remarks MR/NMR
1.	Access of building			
	• Road width	6mtr	On main road	MR
	• Gate width	4.5 mtr	On main road	MR
	• Width of internal road	N/A	N/A	N/A
2.	Number, width, Type & Arrangements of exits			
	a. Number of staircases			
	• Upper floors	N/A	N/A	N/A
	• Basements	N/A	N/A	N/A
	b. Width of staircases			
	• Upper floors	N/A	N/A	N/A
	• Basements	N/A	N/A	N/A
	c. Protection of exits			
	• Fire check door	N/A	N/A	N/A
	• Pressurization	N/A	N/A	N/A
	d. No of continuous staircase to terrace	N/A	N/A	N/A
	e. Width Of Corridor	N/A	N/A	N/A
	f. Door Size	N/A	N/A	N/A
3.	Compartmentation			
	• Fire check door	N/A	N/A	N/A
	• Sealing of electrical shafts	N/A	N/A	N/A
	• Fire Rating of shaft door	N/A	N/A	N/A
	• Water Curtain	N/A	N/A	N/A
	• Fire Dampers			
4.	Smoke managements System			
	• Basements	N/A	N/A	N/A
	• Upper floors	N/A	N/A	N/A
5.	Fire Extinguishers			
	• Total numbers	14	20	M/R
	• Types	ISI marked DCP 10 Kg. & 75 Kg. CO ₂ Water mist cum foam trolley	DCP Mounted trolley-9 (75kg) DCP-10 (10kg) Water mist cum foam trolley-2	M/R
	• IS marking	Required	Provided	M/R
				

N/A				
6.	First - Aid Hose Reels			
	• Total numbers on each floor	N/A	N/A	N/A
	• Length of hose reel hose	N/A	N/A	N/A
	• Nozzle diameter	N/A	N/A	N/A
7.	Automatic fire detection and alarming system			
	• Type of detector	Hand Held explosive Meter / Gas & Flame Detector	Provided	MR
	• Location of Main Panel	N/A	N/A	N/A
	• Location of Repeater Panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooters' Location	Required	Technician room	MR
8.	MOEFA	Required	Provided	MR
9.	Public Address System	N/A	N/A	N/A
10.	CO ₂ flooding system			
	• Ground Floor	Required in compressor Area	Provided	MR
	• Upper Floor	N/A	N/A	N/A
	• Sprinkler above false ceiling	N/A	N/A	N/A
11.	Internal Hydrants			
	• Size of riser/down-comer	N/A	N/A	N/A
	• Number of hydrants per floor	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
12.	Yard Hydrants			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13.	Pumping Arrangements			
	• Ground Level	N/A		
	• Discharge of main pump	N/A	N/A	
	➤ Head of main pump	N/A	N/A	N/A
	➤ Number of main pumps	N/A	N/A	N/A
	➤ Jockey pump out put	N/A	N/A	N/A
	➤ Jockey pump head	N/A	N/A	N/A
	➤ Standby Pump out put	N/A	N/A	N/A
	➤ Standby Pump Head	N/A	N/A	N/A
	➤ Auto Starting/Manual stopping	N/A	N/A	N/A
	➤ Pump House Access	N/A	N/A	N/A
	• Terrace level			
	➤ Discharge of pump	N/A	N/A	N/A
	➤ Head of the pump	N/A	N/A	N/A
	➤ Power supply	N/A	N/A	N/A
	➤ Auto starting of pump	N/A	N/A	N/A
14.	Captive water Storage for fire fighting			
	• Underground tank capacity	N/A	N/A	N/A
	➤ Draw of connection	N/A	N/A	N/A
	➤ Fire service inlet	N/A	N/A	N/A
	➤ Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	N/A	N/A	N/A

(Handwritten signature)


200 /

✓

		N/S		
15	Exit Signage	Required	Provided	MR
16.	Provision of Lifts			
	➤ Pressurization of Lift Shaft	N/A	N/A	N/A
	➤ Pressurization of lift lobby	N/A	N/A	N/A
	➤ Communication in lift Car	N/A	N/A	N/A
	➤ Fireman's Grounding Switch	N/A	N/A	N/A
	➤ Lift Signage	N/A	N/A	N/A
17.	Standby power supply	Required	Provided	MR
18.	Refuge Area	N/A	N/A	
	➤ Total area	N/A	N/A	N/A
	➤ Location	N/A	N/A	N/A
19.	Fire control room			
	➤ Detector system panel	N/A	N/A	N/A
	➤ Flow Switch Panel	N/A	N/A	N/A
	➤ PA System Panel	N/A	N/A	N/A
	➤ Battery backup	N/A	N/A	N/A
	➤ Building Floor Plans	N/A	N/A	N/A
20.	Special Fire Protection Systems for Protection of special Risks, if any;	Fire buckets filled with sand, no smoking boards & emergency no. were found displayed in Hindi & English. No loose electric wiring seen on premises. 6' high boundary wall with barbed wire have been provided. Co2 flooding system connected through detectors provided in each compressor unit.		MR

The fire protection systems provided in the building were tested, checked and found functional at the time of inspection.

Keeping in view of the substantial compliance of the minimum standards on fire prevention and fire safety measures as required under the rules it is recommended to grant Fire Safety Certificate under rule 35 of the Delhi Fire Service rules 2010.


 01/03/2023
 Signature of the Inspecting Officer
 Name : Ashok Kumar Jaiswal
 Designation : D.O. (East Division)

Dy. CFO (NDZ)

KVP
02/03/23

C.F.O.

3/31/2023

Director
3/13/23

Ashok Kumar Jaiswal
D.O. (EAST)

D.O. (ED)

F.T. Letter is added for sign-off.

Director
7/03/23

KVP
06/03/23