



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE  
NEW DELHI- 110 001

No. F6/DFS/MS/School/2023/NDZ/ 917

Dated: 03/04/2023

**FIRE SAFETY CERTIFICATE**

Certified that the EDMC Primary School located at Chandu Park, Delhi-110051, comprised of ground plus two upper floors, owned/occupied by EDMC Primary School was inspected by the officer concerned of fire service on 10/03/2023 in the presence of Mrs. Meena Kumari and observed that all the fire prevention and fire safety arrangements provided in the premises found in good working condition. The premises have complied with Circular No. F.16/Estate/CC/Fire Safety/2011/3298 to 3398 dated-01/03/11 issued by the Director of Education and that the building/premises is fit for occupancy class 'Educational (Group-B)' with effect from 03/04/2023.. for a period of **three** years in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010 & also conditions printed below.

Issued on 03/04/2023..... at New Delhi by

  
(ATUL GARG)  
DIRECTOR  
DELHI FIRE SERVICE

To:-

1. The Principal,  
EDMC Primary School at Chandu Park, Delhi-110051
2. The Director of Education, MCD  
15<sup>th</sup> Floor, E- Block, Dr. S.P. Mukherjee Civic Center, JLN Marg,  
New Delhi-110002

**Conditions for the validity of Fire Safety Certificate**

1. All the means of escape shall be kept free of all type of obstruction all the time
2. All the employees shall be acquainted with the use and maintenance of all fire equipments and method of smooth and speedy safe evacuation of occupants in case of emergency.
3. All the fire fighting equipment shall be maintained in perfect working condition all the time and any lapse rendering non-functional of fire safety measures, management shall be responsible.
4. Any deviation, with regards to construction, ventilation, occupancy, electric installation etc. may be got verified from the concerned authorities.
5. This Fire Safety Certificate may not be treated in any case for regularizations of unauthorized construction /unauthorized use of land if any.
6. The owner / occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rule 2010. The form is available on [www.dfs.delhigovtmc.in](http://www.dfs.delhigovtmc.in)
7. The owner / occupier shall apply for renewal of this Fire Safety Certificate of the Director in Form J [sub rule (1) of rule (37)] along with a copy of this Certificate, Six Months prior to its expiry

### INSPECTION REPORT

1 Name & address of the building	EDMC Primary School Chandu Park, Delhi 110016
2 Building is comprised of	Ground plus two upper floors.
3 Type of Occupancy	Educational
4 Type of Case	New ✓
5 Details of Previous NOC letter	Nil
6 Fire Safety direction letter No.	F.16/Estate/CC Fire Safety/2011/3298 to 3308 dated 01/03/11
7 Date of Inspection	10/03/2023
8 Name of the Inspecting officers	ADO Deepak Kumar
9 Name and designation of Officer from the building side	Ms. Meena Kumari, Principal
10 Year of Construction	2014
11 Applicant's No.	15 dated 25.02/2023.

Sr No	Minimum Standards on fire prevention and fire safety U/R33	Circular Requirement	Provided at Site	Remarks MR NMR
01	Access to building.			
	• Road width	06 m	06 m ✓	MR
	• Gate width	N/A	N/A	N/A
	• Width of internal road	N/A	N/A	N/A
02	Number, Width, Type and Arrangement of Exits:			
	a. Number of Staircases			
	• Upper Floor	01 no.	02 nos ✓	MR
	• Basement	N/A	N/A	N/A
	B. Width of Staircases			
	• Upper Floor	1.5 m	1.5 m & 1.3 m ✓	MR
	• Basement	N/A	N/A	N/A
	c. Protection of exits			
	• Fire check door	N/A	N/A	N/A
	• Pressurization	N/A	N/A	N/A
	d. No. of continuous staircases to terrace	01 no	01 no ✓	MR
	e. Width of Corridor	1.5 m	1.5 m ✓	N/A
	f. Door Size	01m	01m ✓	N/A
03	Compartmentation			
	• Fire check door	N/A	N/A	N/A
	• Sealing of electrical shafts	N/A	N/A	N/A
	• Fire rating of shaft door	N/A	N/A	N/A
	• Water curtain	N/A	N/A	N/A
	• Fire Dampers	N/A	N/A	N/A
04	Smoke Management System			
	• Basement	30 a/c per hour	N/A	N/A
	• Upper floor	12 a/c per hour	N/A	N/A
05	Fire Extinguishers.			
	• Total numbers	06 nos.	08 nos.	N/A
	• types	ABC /CO <sub>2</sub>	ABC /CO	N/A
	• IS marking	ISI marked	ISI marked	N/A

A 50 ✓



06	First-aid-Hose Reels			
	Total numbers on each floor	01 no	01 no	MIR
	• Length of hose reel hose	30m	30m	MIR
	• Nozzle diameter	05 mm	05 mm	MIR
07	Automatic fire detection and alarming system			
	• Type of detectors	N/A	N/A	N/A
	• Location of main panel	N/A	N/A	N/A
	• Location of repeater panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooter's location	N/A	N/A	N/A
08	MOEFA	N/A	N/A	N/A
09	Public address System	N/A	N/A	N/A
10	Automatic Sprinkler System	N/A	N/A	N/A
	• Basement	N/A	N/A	N/A
	• upper floor	N/A	N/A	N/A
	• sprinkler above false ceiling	N/A	N/A	N/A
11	Internal Hydrants			
	• size of riser/down-comer	N/A	N/A	N/A
	• Number of hydrants per floor	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
12	Yard Hydrants			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13	Pumping Arrangements			
	• Ground Level			
	➢ Discharge of main Pump	N/A	N/A	N/A
	➢ Head of Main Pump	N/A	N/A	N/A
	➢ Number of main pumps	N/A	N/A	N/A
	➢ Jockey pump out put	N/A	N/A	N/A
	➢ Jockey pump head	N/A	N/A	N/A
	➢ Standby pump out put	N/A	N/A	N/A
	➢ Standby pump Head	N/A	N/A	N/A
	➢ Auto Starting /Manual stopping	N/A	N/A	N/A
	➢ Pump House Access	N/A	N/A	N/A
	• Terrace Level			
	➢ Discharge of pump	450 Lpm	450 Lpm	MIR
	➢ Head of the Pump	40 M	40 M	MIR
	➢ Power supply	Required	Provided	MIR
	➢ Auto Starting of pump	Required	provided	MIR
14	Captive Water Storage for Fire Fighting			
	• Underground tank capacity	N/A	N/A	N/A
	➢ Draw-off connection	N/A	N/A	N/A
	➢ Fire service inlet	N/A	N/A	N/A
	➢ Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	10,000 Ltr	provided	MIR
15	EXIT Signage	Required	provided	MIR
16	Provision of Lifts			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication in lift car	N/A	N/A	N/A
	• Firemen's grounding switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A

2. 50/

17	Standby power supply			
18	Refuge Area	N/A	N/A	N/A
	• Total area	N/A	N/A	N/A
	• Location	N/A	N/A	N/A
19	Fire Control Room	N/A	N/A	N/A
	• Detector system panel	N/A	N/A	N/A
	• Flow switch panel	N/A	N/A	N/A
	• PA system panel	N/A	N/A	N/A
	• Battery backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection systems for protection of special Risks, if any	N/A	N/A	N/A

The fire protection systems provided in the building were tested checked and found functional at the time of inspection.

Keeping in view the deemed compliance of the minimum standards on fire prevention and fire safety required under the rule It is recommended to grant Fire Safety Certificate under rule 35 of the Delhi Fire Service Rules 2010.

*Deepak*  
 Signature of the Inspecting Officer  
 Name - Deepak Kumar  
 Designation - A D O (Shah)

~~D.O. (D)~~ DFA please

*Aljaiswal*  
 20/03/2023

Dy. CFO (~~NDZ~~)

*Ring*  
 21/03/22

C.F.O.  
*Mugh*  
 21/03/2023

Director / *Aty/SHAH*  
 21/03/2023

*Aty/SHAH* Sirs  
 up for your kind signature pl.  
 ES Letter is put

*Deepak*  
 27/03/2023