



C/6°



**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE
NEW DELHI-110001**

No. F.6/DFS/MS/EH/2023/SZ/ 320

Dated. 30/10/2023

FIRE SAFETY CERTIFICATE

Certified that the Eating House in the Name & Style of **M/s KAAYO** located at **Unit No R-8, UGF, East Wing, Epicuria Nehru place Metro Station, New Delhi 110019** at owner /occupied by **A Unit of Lerro F And B Restaurants Pvt Ltd**, was issued Fire Safety Certificate by this department vide letter no. **F.6/DFS/MS/EH/2022/SZ/80** dated **06/04/2022** in the name of **Nomimona**. The restaurant premise was re-inspected by the officer concerned of this department on **25/10/2023** in the presence of **Sh. Ashutosh Vibhu** and found that the said premise have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the premises is fit for occupancy **Class D "Assembly Building" (Restaurant) and validity upto 31/03/2026** in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 30 / 10 /2023 at New Delhi by

(ATUL GARG)
DIRECTOR
DELHI FIRE SERVICE

Copy to: -

1. The Dy. Health Officer, Public Health Department, Central Zone Lajpat Nagar, New Delhi-110019 (Ref. MHA Portal ID 2023101817478 dated 19/10/2023)

Conditions for the validity of Fire Safety Certificate: -

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangement provided therein shall be maintained in good working condition at all time as seen during inspection. Any loss of life property due to non-functional fire safety measures shall be at the responsibility of the management.
3. All the staff members must know the correct method of operation of fire fighting system.
4. The owner/occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on www.dfs.delhigovt.nic.in
5. This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or alteration (Clause 1.4.3 of UBBL-2016), if any.
6. "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in form 'J' [sub rule (I) of rule 37] along with a copy of this Certificate, six month prior to its expiry."



INSPECTION REPORT

1	Name & Address of the Building	M/s KAAYO (A Unit of Metro Food & B Restaurants Pvt Ltd) at Unit No R-8, UGF, East Wing, Epicuria Nehru place Metro Station, New Delhi 110019		
2	Type of Occupancy	(Eating house at UGF only)		
3	Building Comprised of	Lower Ground Floor & Upper Ground Floor (PD area at Nehru Place Metro Station)		
4	Type of Case	New Case / Name Change		
5	Details of Previous NOC	F.6/DFS/MS/EH/2022/SZ/80 dated 06/04/2022 for the name of Nomimona		
6	Fire Safety Directives Letter No	F.6/DFS/MS/BP/2012/3424 dated 18/09/2012		
7	Date of Inspection	25/10/2023		
8	Name of the Inspecting Officers	Sh. Rajesh Kumar ADO (BCP)		
9	Name & Designation of Officers from the building side	Sh. Ashutosh Vibhu		
10	Year of construction	2013		
11	Applicant letter No.	MHA Portal ID 2023101817478 dated 19/10/2023		
S. No.	Minimum standards on Fire Prevention and Fire Safety U/R 33	NBC / BBL Requirements	Provided at Site	Remarks MR/NMR
1	Access to Building.	F6/DFS/MS/2022/SZ/434 dated 29/09/2022 for TDI Mall		
	<ul style="list-style-type: none"> Road width Gate width Width of internal road 	30mtr 6 mtr 6 mtr	Provided* Provided* Provided*	MR MR MR
2	Number, width, type & arrangement of exits.			
	a) Number of Staircase	Provided & Maintained by TDI Mall /DMRC		
	> Upper floors.	04 Nos	Provided*	MR
	> Basement floor.	07 Nos	Provided*	MR
	b) Width of Staircase	Provided & Maintained by TDI Mall /DMRC		
	> Upper floors	1.50 mtr	Provided*	MR
	> Basement floor	1.50 mtr	Provided*	MR
	c) Protection of exits	Provided & Maintained by TDI Mall /DMRC		
	> Fire check door	N/A	N/A	N/A
	> Pressurization	N/A	N/A	N/A
	d) No. of continuous staircase to terrace	Required	One	MR
	e) Width of corridor	N/A	N/A	N/A
	f) Door size	1.50 mtr each	1.50 mtr & 1.50 mtr	MR
3	Compartmentation.	Provided & Maintained by TDI Mall /DMRC		
	• Fire check door.	N/A	N/A	N/A
	• Sealing of electrical shafts.	N/A	N/A	N/A
	• Fire rating of shaft door.	N/A	N/A	N/A
	• Water curtain	N/A	N/A	N/A
	• Fire dampers.	N/A	N/A	N/A
4	Smoke Management system.	Provided & Maintained by TDI Mall /DMRC		
	• Basement	30 ACPH	N/A	N/A
	• Upper floors	12 ACPH	Exhaust Fans Provided	MR
5	Fire Extinguishers.			
	• Total numbers	04 Nos	06 Nos	MR
	• Types	ABC/CO ₂	ABC-04 & CO ₂ -02	MR
	• ISI Marking	ISI marked	Provided	MR
6	First Aid Hose Reels.	Provided & Maintained by TDI Mall /DMRC		
	• Total numbers on each floor.	One	Provided	MR
	• Length of hose-reel hose.	30m	Provided	MR
	• Nozzle Diameter	5mm	Provided	MR
7	Automatic fire detection & alarming system.	Provided & Maintained by TDI Mall /DMRC		
	• Type of detectors	Required	Provided*	MR

(Handwritten signature)

(Handwritten mark)

	<ul style="list-style-type: none"> Location of Main Panel Location of Repeater Panel Alternate source of power Hooter's location 	Required	Provided*	MR
		Required	Provided*	MR
		Required	Provided*	MR
		Required	Provided*	MR
8	MOEFA	Required	Provided	MR
9	Public Address System	Required	Provided	MR
10	Automatic Sprinkler System	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> Basement 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Ground floor. 	Required	Provided	MR
	<ul style="list-style-type: none"> Sprinkler above false ceiling 	Required	Provided	MR
11	Internal Hydrants.	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> Size of Riser/Down-comer 	150 mm	Provided	MR
	<ul style="list-style-type: none"> Number of Hydrant per floor 	01 No	Provided	MR
	<ul style="list-style-type: none"> Hose box. 	01 No	Provided	MR
12	Yard Hydrants.			
	<ul style="list-style-type: none"> Total number of hydrants. 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Hose box. 	N/A	N/A	N/A
13	Pumping arrangements.			
	<ul style="list-style-type: none"> Ground Level 	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> ➤ Discharge of main pump. 	2850 x 2 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Head of main pump. 	70 m each	Provided	MR
	<ul style="list-style-type: none"> ➤ Number of main pumps. 	02	Provided	MR
	<ul style="list-style-type: none"> ➤ Jockey Pump output. 	180 x 2 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Jockey Pump head. 	70 m	Provided	MR
	<ul style="list-style-type: none"> ➤ Standby Pump output. 	2850 LPM	Provided	MR
	<ul style="list-style-type: none"> ➤ Standby Pump head. 	70 m	Provided	MR
	<ul style="list-style-type: none"> ➤ Auto Starting/Manual Stopping. 	Required	Provided	MR
	<ul style="list-style-type: none"> ➤ Pump house access. 	Required	Provided	MR
	<ul style="list-style-type: none"> Terrace Level 	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> ➤ Discharge of pump. 	N/A	As above	N/A
	<ul style="list-style-type: none"> ➤ Head of pump. 	N/A	As above	N/A
	<ul style="list-style-type: none"> ➤ Power supply. 	N/A	As above	N/A
	<ul style="list-style-type: none"> ➤ Auto starting of pump. 	N/A	As above	N/A
14	Captive water storage for fire fighting.	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> Underground tank capacity. 	100,000 ltr	1,00,000 ltrs	MR
	<ul style="list-style-type: none"> ➤ Draw-off connection. 	Required	Provided	MR
	<ul style="list-style-type: none"> ➤ Fire Service Inlet. 	Required	Provided	MR
	<ul style="list-style-type: none"> ➤ Access to tank. 	Required	Provided	MR
	<ul style="list-style-type: none"> Overhead tank capacity. 	Required	20,000 ltr	MR
15	Exit Signage.	Required	Provided	MR
16	Provision of Lifts.	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> Pressurization of lift shaft. 	Required	Provided	MR
	<ul style="list-style-type: none"> Pressurization of lift lobby. 	Required	Provided	MR
	<ul style="list-style-type: none"> Communication in lift car. 	Required	Provided	MR
	<ul style="list-style-type: none"> Fireman's switch. 	Required	Provided	MR
	<ul style="list-style-type: none"> Lift signage. 	Required	Provided	MR
17	Standby Power Supply	Required	Provided (DG Set)	MR
18	Refuge Area			
	<ul style="list-style-type: none"> Total area 	N/A	N/A	N/A
	<ul style="list-style-type: none"> Location 	N/A	N/A	N/A
19	Fire Control Room.	Provided & Maintained by TDI Mall /DMRC		
	<ul style="list-style-type: none"> Detector system panel. 	N/A	Provided	N/A
	<ul style="list-style-type: none"> Flow switch panel. 	N/A	Provided	N/A
	<ul style="list-style-type: none"> PA system panel. 	N/A	Provided	N/A
	<ul style="list-style-type: none"> Battery backup. 	N/A	Provided	N/A
	<ul style="list-style-type: none"> Building floor plan. 	N/A	Provided	N/A
20	Special Fire Protection System for the	N/A	Provided	N/A

N/18

Protection of special Risk, if any.

The Fire protection systems provided in the premises were test checked at random and found functional at the time of inspection.

Keeping in view of the substantially satisfactory compliance of the minimum standards on fire prevention and fire safety measures as required under the rules, it is recommended to issue Fire Safety Certificate under rule 35 (3) of the Delhi Fire Service Rules, 2010

Accordingly, DFA is put up for approval and signature please.

[Handwritten Signature]
26/10/23

Signature of the Inspecting Officer
Name: Sh. Rajesh Kumar
Designation: ADO (BCP)

DO (SD)

[Handwritten Signature]
27/10/23

[Handwritten Signature]
27/10/2023

[Handwritten Signature]
30/10/23

FT DS

[Handwritten Signature]
30/10/23

As approved, G.I. letter is put up for
your signature 81

[Handwritten Signature]
30/10/2023

[Handwritten Signature]
30/10/23

[Handwritten Signature]

Uploaded
30/10/23