

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE  
NEW DELHI-110 001.

No.F.6/DFS/MS/School/SZ/2024/ 77

Dated: 30/01/2024

**FIRE SAFETY CERTIFICATE**

Certified that the Vidya Memorial Public School, G-1/450, Dal Mill Road, UttamNagar, New Delhi-110059, comprised of ground floor plus three upper floors, owned/occupied by Vidya Memorial Public School was issued Fire Safety Certificate by this department vide letter no. F6/DFS/MS/School/2021/SZ/37 dated 13.01.2021. The School building was re-inspected by the officer concerned of this department on 12.01.2024 in the presence of Mr. Aseem Kumar Tyagi (Chairman) and found that the School building have deemed complied the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules, 2010 and that the building/ premises is fit for occupancy class "Educational" for a period of three years in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under Rule-38 of the Delhi Fire Service Rules, 2010 printed as below.

Issued on.....30/01/2024..... at New Delhi.

(Atul Garg)  
Director  
Delhi Fire Service

Copy to:-

1. The Chirman,  
Vidya Memorial Public School,  
G-1/450, Dal Mill Road, Uttam Nagar,  
New Delhi-110059.
2. Director of Education,  
Govt. of NCT of Delhi, Old Secretariat,  
New Delhi-110054.

**Following fire safety directives must be adhered to:-**

1. All the fire safety arrangements provided therein shall be maintained in good working condition at all times.
2. The means of escape shall be kept unlocked and unobstructed for unhindered evacuation of occupants in case of emergency.
3. Any loss of life or property due to non-functional fire safety measures shall be at the risk and responsibility of the management.
4. The trained staff should be available round the clock.
5. Any deviations w.r.t. construction shall be verified by the concerned building sanctioning agency.
6. The certificate may not be treated in any case for the regularization of the unauthorized construction, if any.
7. The owner/occupier shall submit a declaration every year in the form 'K' provided in the first schedule of Delhi Fire Service Rules 2010, form is available on [www.dfs.delhigovt.nic.in](http://www.dfs.delhigovt.nic.in).
8. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in the Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry.

## INSPECTION REPORT

1. Name & address of the building : Vidya Memorial Public School, G-1/450, Dal Mill Road, Uttam Nagar, New Delhi-110059
2. Building comprised of : Ground plus three upper floors
3. Type of Occupancy : Educational
4. Type of Case : Renewal
5. Details of Previous NOC : F6/DFS/MS/School/2021/SZ/37 dated 13.01.2021
6. Fire Safety directives letter No : N/A
7. Date of inspection : 12.01.2024
8. Name of Inspecting Officer : A.D.O. R.K.Yadav
9. Name and designation of officers
10. From the building side : Mr. Aseem Kumar Tyagi (Chairman)
11. Year of Construction : 2004
12. Applicant's letter No. : Email Id vidyamemorial@gmail.com dated 02.01.2024

S. No.	Minimum Standards on fire prevention and fire safety U/R 33	Requirement	Provided at site	Remarks MR/NMR
1.	<b>Access to building</b>			
	<ul style="list-style-type: none"> <li>• Road width</li> <li>• Gate width</li> <li>• Width of internal road</li> </ul>	Accessible (06 mtrs) 4.5 mtrs N/A	09mtrs 05, 3.8 & 3mtrs N/A	MR MR N/A
2.	<b>Number, Width, Type &amp; Arrangement of Exits</b>			
	a. Number of staircases			
	<ul style="list-style-type: none"> <li>• Upper Floors</li> <li>• Basements</li> </ul>	02 No's N/A	03 No's N/A	MR N/A
	b. Width of staircases			
	<ul style="list-style-type: none"> <li>• Upper Floor</li> <li>• Basements</li> </ul>	1.50 m & .75 m N/A	1.15 to 1.50, 1.27 & 1.20 m N/A	MR old accepted ✓ N/A
	c. Protection of exits			
	<ul style="list-style-type: none"> <li>• Fire check door</li> <li>• Pressurization</li> </ul>	N/A N/A	N/A N/A	N/A N/A
	d. No. of continuous staircases to terrace	Required	Two	MR
	e. Width of Corridor	1.50 m	1.40 to 1.45 m	MR, being old case
	f. Door Size	1.00 m	1.13m & 1.20	MR
3.	<b>Compartmentation</b>			
	<ul style="list-style-type: none"> <li>• Fire check door</li> <li>• Sealing of electrical shafts</li> <li>• Fire Rating of shaft door</li> <li>• Water Curtain</li> <li>• Fire Dampers</li> </ul>	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A	N/A N/A N/A N/A N/A
4.	<b>Smoke Management System</b>			
	<ul style="list-style-type: none"> <li>• Basements</li> <li>• Upper floors</li> </ul>	N/A Required	N/A Natural ventilation	N/A MR
5.	<b>Fire Extinguishers</b>			
	<ul style="list-style-type: none"> <li>• Total numbers</li> <li>• Types</li> <li>• IS marking</li> </ul>	12 no.'s ABC/CO <sub>2</sub> type ISI marked	Provided Provided Provided	MR MR MR
6.	<b>First-Aid Hose Reels</b>			
	<ul style="list-style-type: none"> <li>• Total numbers on each floor</li> <li>• Length of hose reel hose</li> <li>• Nozzle diameter</li> </ul>	01 no. 30 mtrs 5 mm	Provided Provided Provided	MR MR MR

N/18				
7.	<b>Automatic fire detection and alarming system</b>			
	• Type of detectors	N/A	N/A	N/A
	• Location of Main Panel	N/A	N/A	N/A
	• Location of Repeater Panel	N/A	N/A	N/A
	• Alternate source of power	N/A	N/A	N/A
	• Hooters' Location	N/A	N/A	N/A
8.	<b>MOEFA</b>			
9.	<b>Public Address System</b>			
		N/A	Provided	N/A
10.	<b>Automatic Sprinkler System</b>			
	• Basement	N/A	N/A	N/A
	• Ground Floor	N/A	N/A	N/A
	• Sprinkler above false ceiling	N/A	N/A	N/A
11.	<b>Internal Hydrants</b>			
	• Size of riser/down-comer	100 mm	100 mm	MR
	• Number of hydrants per floor	2 no.	2 no.	MR
	• Hose Box	2 no.	2 no.	MR
12.	<b>Yard Hydrants</b>			
	• Total number of hydrants	N/A	N/A	N/A
	• Hose Box	N/A	N/A	N/A
13.	<b>Pumping Arrangements</b>			
	• Ground Level			
	> Discharge of main Pump	N/A	N/A	N/A
	> Head of Main pump	N/A	N/A	N/A
	> Number of main pumps	N/A	N/A	N/A
	> Jockey Pump out put	N/A	N/A	N/A
	> Jockey pump head	N/A	N/A	N/A
	> Standby Pump out put	N/A	N/A	N/A
	> Standby Pump Head	N/A	N/A	N/A
	> Auto Starting/Manual Stopping	N/A	N/A	N/A
	• Terrace level			
	> Pump House Access	N/A	N/A	N/A
	> Discharge of pump	450 LPM	Provided	MR
	> Head of the pump	30 mtrs	Provided	MR
	> Power Supply	Required	Provided	MR
	> Auto Starting of pump	N/A	N/A	N/A
14.	<b>Captive Water Storage for fire fighting</b>			
	• Underground tank capacity	N/A	N/A	N/A
	> Draw-off connection	N/A	N/A	N/A
	> Fire service inlet	N/A	N/A	N/A
	> Access to tank	N/A	N/A	N/A
	• Overhead Tank capacity	10,000 ltrs	Provided	MR
15.	<b>Exit Signage.</b>			
		Required	Provided	MR
16.	<b>Provision of Lifts.</b>			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication In lift Car	N/A	N/A	N/A
	• Fireman's Grounding Switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17.	<b>Standby power supply</b>			
		N/A	N/A	N/A
18.	<b>Refuge Area.</b>			
	> Total Area	N/A	N/A	N/A
	> Location	N/A	N/A	N/A

N/A

N/A

	<ul style="list-style-type: none"> <li>➤ Total Area</li> <li>➤ Location</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A
19.	<b>Fire Control Room</b>			
	<ul style="list-style-type: none"> <li>• Detector System Panel</li> <li>• Flow Switch Panel</li> <li>• PA System Panel</li> <li>• Battery backup</li> <li>• Building Floor Plans</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
20.	<b>Special Fire Protection System for Protection of special Risks, if any:</b>	N/A	N/A	N/A

The fire protection systems provided in the building were tested, checked and found functional at the time of inspection.

In view of the deemed compliance of the minimum standards of fire prevention and fire safety measures as required under the rules the Fire Safety Certificate issued vide letter number F6/DFS/MS/School/2021/SZ/37 dated 13.01.2021 renewal under rule 37 of the Delhi Fire Service Rules 2010 is recommended.

*R. K. Yadav*  
29/11/2024

Signature of Inspecting Officer  
Name:-R.K.Yadav

Designation:-ADO (JKP)

DO (South West)

*AK*  
29/11/24

CFO (S2)  
*Naugh*  
29/11/2024

Director  
*34*  
30/11/24

*Arjun*