

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEADQUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE**  
**NEW DELHI-110001**

No. F.6/DFS/MS/2024/SZ/ 160

Dated: 11/03/2024

**FIRE SAFETY CERTIFICATE**

Certified that the **Srimanta Sankardev Bhawan** located at **A-14/B, Satsang Vihar Marg, Qutub Institutional Area, New Delhi 110067** comprised of Basement, ground plus three upper floors owned/occupied by Assam Association Cultural & Educational Trust, Delhi was issued FSC by this department vide letter No. F.6/DFS/MS/2021/SZ/109 dated 10-02-2021. The premises was re-inspected by officers concerned of this department on 05/03/2024 in the presence of Mr. Abhijeet Singh and found that the said building have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of Delhi Fire Service Rules, 2010 and that the building is fit for occupancy **Group 'C' Institutional Building** with effect from 11/03/2024 for period of **Three years** in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010.

Issued 11/03/2024 at New Delhi by

  
**(ATUL GARG)**  
**DIRECTOR**  
**DELHI FIRE SERVICE**

Copy to: -

1. The Authorized Signatory, Srimanta Sankardev Bhawan at A-14B, Qutub Institutional Area, New Delhi 110067.

**Conditions for the validity of Fire Safety Certificate:**

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangement provided therein shall be maintained in good working condition at all time as seen during inspection. Any loss of life property due to non-functional fire safety measures shall be at the responsibility of the management.
3. All the staff members must know the correct method of operation of fire fighting system.
4. The basement shall be used as per the provisions of UBBL-2016 /NBC Part- IV.
5. The owner/occupier shall submit a declaration every year in form 'K' provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on [www.dfs.delhigovt.nic.in](http://www.dfs.delhigovt.nic.in)
6. This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or Alteration (Clause 1.4.3 of UBBL- 2016), if any.
7. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in form 'J' [sub rule (I) of rule 37] along with a copy of this Certificate, six month prior to its expiry.



N/13

### INSPECTION REPORT

1	Name & Address of the Building	Srimanta Sankaradeva Bhawan, A-14/B Satsang Vihar Marg, Qutab Institutional Area, New Delhi. (Assam Association Cultural & Education Trust, Delhi)		
2	Type of Occupancy	Institutional building, "Group-C"		
3	Building Comprised of	Basement, Ground + 03 upper floors.		
4	Type of Case	Renewal		
5	Details of Previous NOC	F.6/DFS/MS/2021/SZ/109 dated 10-02-2021		
6	Fire Safety Directives Letter No	F6/DFS/MS/BP/99/1574 dated 19.11.1999		
7	Date of Inspection	05/03/2024		
8	Name of the Inspecting Officers	DO (South) & ADO (BCP)		
9	Name & Designation of Officers from the building side	Mr. Abhijeet Singh		
10	Year of construction	1999		
11	Applicant letter No.	Email dated 21-02-2024		
S. No.	Minimum standards on Fire Prevention and Fire Safety U/R 33	Old NOC requirements	Provided at Site	Remarks MR/NMR
1	<b>Access to Building.</b>			
	• Road width	Required	9 mtr	MR
	• Gate width	Required	5 mtr	MR
	• Width of internal road	-NA-	-NA-	-NA-
2	<b>Number, width, type &amp; arrangement of exits.</b>			
	<b>a) Number of Staircase</b>			
	➤ Upper floors.	02 Nos	02 Nos	MR
	➤ Basement floor.	02 Nos	02 Nos	MR
	<b>b) Width of Staircase</b>			
	➤ Upper floors	Required	1.27m & 1.17 m	MR (old case)
	➤ Basement floor	Required	1.27 m & 1.17 m	MR (old case)
	<b>c) Protection of exits</b>			
	➤ Fire check door	Required	Provided	MR
	➤ Pressurization	-NA-	-NA-	-NA-
	<b>d) No. of continuous staircase to terrace</b>	Required	2 Nos	MR
	<b>e) Width of corridor</b>	-NA-	-NA-	-NA-
	<b>f) Door size (Exits in hall)</b>	1.5m, 1.90m & 1.20 (2 No's)	Provided	MR (old case)
3	<b>Compartmentation.</b>			
	• Fire check door.	-NA-	-NA-	-NA-
	• Sealing of electrical shafts.	-NA-	-NA-	-NA-
	• Fire rating of shaft door.	-NA-	-NA-	-NA-
	• Water curtain	-NA-	-NA-	-NA-
	• Fire dampers.	-NA-	-NA-	-NA-
4.	<b>Smoke Management system.</b>			
	• Basement	30 ACPH	Exhaust fan provided	MR
	• Upper floors	-NA-	-NA-	-NA-
5.	<b>Fire Extinguishers.</b>			
	• Total numbers	Required	10 Nos	MR
	• Types	ISI marked	Co2, ABC & DCP	MR
	• ISI Marking	ISI marked	Provided	MR
6.	<b>First Aid Hose Reels.</b>			
	• Total numbers on each floor.	01 Nos	Provided	MR
	• Length of hose-reel hose.	30m	Provided	MR



N/14

	• Nozzle Diameter	5mm	Provided	MR
7	<b>Automatic fire detection &amp; alarming system.</b>			
	• Type of detectors	Required	Smoke type	MR
	• Location of Main Panel	-NA-	Ground floor	-NA-
	• Location of Repeater Panel	-NA-	-NA-	-NA-
	• Alternate source of power	Required	Provided	MR
	• Hooter's location	-NA-	All Areas	-NA-
8.	<b>MOEFA</b>	Required	Provided	MR
9.	<b>Public Address System</b>	Required	Provided	MR
10.	<b>Automatic Sprinkler System</b>			
	• Basement	-NA-	-NA-	-NA-
	• Upper floors.	-NA-	-NA-	-NA-
	• Sprinkler above false ceiling	-NA-	-NA-	-NA-
11.	<b>Internal Hydrants.</b>			
	• Size of Riser/Down-comer	100 mm	Provided	MR
	• Number of Hydrant per floor	01 Nos	Provided	MR
	• Hose box.	01 Nos	Provided	MR
12.	<b>Yard Hydrants.</b>			
	• Total number of hydrants.	-NA-	-NA-	-NA-
	• Hose box.	-NA-	-NA-	-NA-
13.	<b>Pumping arrangements.</b>			
	• <b>Ground Level</b>			
	➤ Discharge of main pump.	-NA-	-NA-	-NA-
	➤ Head of main pump.	-NA-	-NA-	-NA-
	➤ Number of main pumps.	-NA-	-NA-	-NA-
	➤ Jockey Pump output.	-NA-	-NA-	-NA-
	➤ Jockey Pump head.	-NA-	-NA-	-NA-
	➤ Standby Pump output.	-NA-	-NA-	-NA-
	➤ Standby Pump head.	-NA-	-NA-	-NA-
	➤ Auto Starting/Manual Stopping.	-NA-	-NA-	-NA-
	➤ Pump house access.	-NA-	-NA-	-NA-
	• <b>Terrace Level</b>			
	➤ Discharge of pump.	450 LPM	Provided	MR
	➤ Head of pump.	40 m	Provided	MR
	➤ Power supply.	Required	Provided	MR
	➤ Auto starting of pump.	Required	Provided	MR
14.	<b>Captive water storage for fire fighting.</b>			
	• Underground tank capacity.	10,000 Ltr	Provided	MR
	➤ Draw-off connection.	Required	Provided	MR
	➤ Fire Service Inlet.	Required	Provided	MR
	➤ Access to tank.	Required	Provided	MR
	• Overhead tank capacity.	10,000 Ltr	10,000 Ltr	MR
15.	<b>Exit Signage.</b>	Required	Provided	MR
16.	<b>Provision of Lifts.</b>			
	• Pressurization of lift shaft.	-NA-	-NA-	-NA-
	• Pressurization of lift lobby.	-NA-	-NA-	-NA-
	• Communication in lift car.	-NA-	-NA-	-NA-
	• Fireman's switch.	-NA-	-NA-	-NA-
	• Lift signage.	-NA-	-NA-	-NA-
17.	<b>Standby Power Supply</b>	-NA-	Provided (DG Set)	-NA-
18.	<b>Refuge Area</b>			
	• Total area	-NA-	-NA-	-NA-
	• Location	-NA-	-NA-	-NA-

2/15

19.	<b>Fire Control Room.</b>			
	• Detector system panel.	-NA-	-NA-	-NA-
	• Flow switch panel.	-NA-	-NA-	-NA-
	• PA system panel.	-NA-	-NA-	-NA-
	• Battery backup.	-NA-	-NA-	-NA-
	• Building floor plan.	-NA-	-NA-	-NA-
20.	<b>Special Fire Protection System for the Protection of special Risk, if any.</b>	-NA-	-NA-	-NA-

The fire protection system provided in the building were randomly checked and found functional at the time of inspection.

Keeping in view of the deemed compliance of the minimum standard on fire prevention and fire safety measures as required under the rules, the FSC issued vide letter no F.6/DPS/MS/2021/SZ/109 dated 10-02-2021, renewal under rule 35(6) of the Delhi Fire Service rules, 2010 is recommended.

Accordingly, DFA is put up for approval and signature please.

Signature of the Inspection Officer  
Name: Sh. Manoj Kumar Sharma  
Design: DO (South)

Signature of the Inspecting Officer  
Name: Sh. Rajesh Kumar  
Design: ADO (BCP)

CFO (HQ)

*[Handwritten signatures and dates]*  
7/3/2021  
Director  
7/3/21  
7/3/21

As approved, F.T. letter is put up for your signature.

*[Handwritten signatures and dates]*  
Director  
11/3/21  
11/3/21

*[Handwritten signature and date]*  
11/3/21