

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEAD QUARTERS: DELHI FIRE SERVICE: CONNAUGHT PLACE
NEW DELHI-110001**

No.F.6 DFS/MS/School/2024/SZ/ 262

Dated: 01/04/2024

FIRE SAFETY CERTIFICATE

Certified that the **Ambience Public School**, located at **Plot No- A-1, Safdarjung Enclave, New Delhi - 110029** comprised of 2 tier Basement, Ground and Four upper floors (lower basement & caretaker room at terrace floor are sealed) owned/ occupied by Ambience Education Society was granted Fire Safety Certificate by this department vide letter No. F6/DFS/MS/School/2021/SZ/221 Dt. 12/03/2021. The said premises was re-inspected by officer concerned of this department on 19/03/2024 in presence of Sh. Manoj Shah of the school and found that the said school building have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of Delhi Fire Service Rules, 2010 and that the building **(one basement, ground plus four upper floors only)** is fit for occupancy class **"Educational Building Group - B"** with effect from 01/04/2024 for a period of **Three years** in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of the conditions under rule 38 of Delhi Fire Service Rules 2010.

Issued on 01/04/2024 at New Delhi by


**(ATUL GARG)
DIRECTOR
DELHI FIRE SERVICE**

Copy to: -

1. The Principal, Ambience Public School, at Plot No- A-1, Safdarjung Enclave, New Delhi - 110029.
2. The Director of Education, Govt. of NCT of Delhi, Old Secretariat, New Delhi -54

Conditions for the validity of Fire Safety Certificate:-

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangements provided therein shall be maintained in good working condition at all time as seen during inspection. Any loss of life or property due to non-functional fire safety measures shall be at the responsibility of the management.
3. All the staff members must know the correct method of operation of firefighting system.
4. The owner/ occupier shall submit a declaration every year in Form 'K' provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on www.dfs.delhigovt.nic.in
5. This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or Alteration (Clause 1.4.3 of UBBL-2016), if any.
6. "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry."

N/25

INSPECTION REPORT

| 1 | Name & Address of the Building | Ambience Public School, at Plot No A-1, Safdarjung, Enclave, New Delhi 110029 | | |
|-------|---|---|---|----------------|
| 2 | Type of Occupancy | Educational, Group-B (School) | | |
| 3 | Building Comprised of | (Basement-1, Sealed) & B-2 + Ground + Four Upper Floors. | | |
| 4 | Type of Case | Renewal | | |
| 5 | Details of Previous NOC | F6/DFS/MS/School/2021/SZ/221 Dt. 12/03/2021 | | |
| 6 | Fire Safety Directives Letter No | F6/DFS/MS/BP/2011/1093 Dated 03/06/2014 | | |
| 7 | Date of Inspection | 19-03-2024 | | |
| 8 | Name of the Inspecting Officers | DO (South) & ADO (BCP) | | |
| 9 | Name & Designation of Officers from the building side | Sh. Manoj Shah | | |
| 10 | Year of construction | 2014 | | |
| 11 | Applicant letter No. | Outdoor diary no 14083 dated 11/03/2024 | | |
| S. No | Minimum standards on Fire Prevention and Fire Safety U/R 33 | Old NOC requirements | Provided at Site | Remarks MR/NMR |
| 1 | Access to Building. | | | |
| | • Road width | 6 mtr | 6 mtr | MR |
| | • Gate width | 6 mtr | 6 mtr | MR |
| | • Width of internal road | 6 mtr | 6 mtr | MR |
| 2 | Number, width, type & arrangement of exits. | | | |
| | a) Number of Staircase | | | |
| | ➤ Upper floors. | 03 No's | 03 No's | MR |
| | ➤ Basement floor. | 03 No's | 03 No's + 01 Ramp | MR |
| | b) Width of Staircase | | | |
| | ➤ Upper floors | 2.0 mtr each | 2.0 mtr each | MR |
| | ➤ Basement floor | 2.0 mtr & 1.5 mtr | 2 x 2 mtr, 1.50 mtr & ramp 2 way, 6 mtr | MR |
| | c) Protection of exits | | | |
| | ➤ Fire check door | Required | Provided | MR |
| | ➤ Pressurization | Required | Provided | MR |
| | d) No. of continuous staircase to terrace | 03 Required | 03 Provided | MR |
| | e) Width of corridor | 1.5 m | Provided | MR |
| | f) Door size | 1 mtr | 1 mtr | MR |
| 3 | Compartmentation. | | | |
| | • Fire check door. | Required | Provided | MR |
| | • Sealing of electrical shafts. | Required | Provided | MR |
| | • Fire rating of shaft door. | Required | Provided | MR |
| | • Water curtain | -NA- | -NA- | -NA- |
| | • Fire dampers. | Required | Provided | MR |
| 4. | Smoke Management system. | | | |
| | • Basement | 30 ACPH | Provided | MR |
| | • Upper floors | 12 ACPH | Provided | MR |
| 5. | Fire Extinguishers. | | | |
| | • Total numbers | 40 Required | 46 Nos | MR |
| | • Types | ABC / wco2 | ABC / wco2 Type | MR |
| | • ISI Marking | ISI mark | Provided | MR |
| 6. | First Aid Hose Reels. | | | |
| | • Total numbers on each floor. | Three Nos | Provided | MR |
| | • Length of hose-reel hose. | 30 m | Provided | MR |
| | • Nozzle Diameter | 5 mm | Provided | MR |

2/26



| | | | | |
|------------|---|-------------|-------------------|------|
| 7 | Automatic fire detection & alarming system. | | | |
| | <ul style="list-style-type: none"> Type of detectors Location of Main Panel Location of Repeater Panel Alternate source of power Hooter's location | -NA- | NA | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 8. | MOEFA | Required | Provided | MR |
| 9. | Public Address System | Required | Provided | MR |
| 10. | Automatic Sprinkler System | | | |
| | <ul style="list-style-type: none"> Basement Upper floors Sprinkler above false ceiling | Required | Provided | MR |
| | | NA | Provided | NA |
| | | -NA- | -NA- | -NA- |
| 11. | Internal Hydrants. | | | |
| | <ul style="list-style-type: none"> Size of Riser/Down-comer Number of Hydrant per floor Hose box. | Required | 150 mm | MR |
| | | Required | 03 No's | MR |
| | | Required | 03 No's | MR |
| 12. | Yard Hydrants. | | | |
| | <ul style="list-style-type: none"> Total number of hydrants. Hose box. | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 13. | Pumping arrangements. | | | |
| | <ul style="list-style-type: none"> Ground Level <ul style="list-style-type: none"> Discharge of main pump. Head of main pump. Number of main pumps. Jockey Pump output. Jockey Pump head. Standby Pump output. Standby Pump head. Auto Starting / Manual Stopping. Pump house access. Terrace Level <ul style="list-style-type: none"> Discharge of pump. Head of pump. Power supply. Auto starting of pump. | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| | | 900 LPM | 900 LPM x 2 Nos | MR |
| | | 40 mtr | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| 14. | Captive water storage for fire fighting. | | | |
| | <ul style="list-style-type: none"> Underground tank capacity. <ul style="list-style-type: none"> Draw-off connection. Fire Service Inlet. Access to tank. Overhead tank capacity. | -NA- | -NA- | -NA- |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | -NA- | -NA- | -NA- |
| | | 50,000 ltrs | 50,000 ltrs | MR |
| 15. | Exit Signage. | Required | Provided | MR |
| 16. | Provision of Lifts. | | | |
| | <ul style="list-style-type: none"> Pressurization of lift shaft. Pressurization of lift lobby. Communication in lift car. Fireman's switch. Lift signage. | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| | | Required | Provided | MR |
| 17. | Standby Power Supply | Required | Provided (DG Set) | MR |
| 18. | Refuge Area | | | |
| | <ul style="list-style-type: none"> Total area Location | -NA- | -NA- | -NA- |
| | | -NA- | -NA- | -NA- |
| 19. | Fire Control Room. | | | |

Handwritten marks and signatures at the bottom of the page.

M27

| | | | |
|---|----------|----------|------|
| <ul style="list-style-type: none"> • Detector system panel. • Flow switch panel. • PA system panel. • Battery backup. • Building floor plan. | -NA- | -NA- | -NA- |
| | Required | Provided | MR |
| | Required | Provided | MR |
| | Required | Provided | MR |
| | Required | Provided | MR |
| 20. Special Fire Protection System for the Protection of special Risk, if any. | -NA- | -NA- | -NA- |

The fire protection system provided in the building were randomly checked and found functional at the time of inspection.

Further, the party has complied all the observation / Shortcoming already issued & communicated by this department vide letter of even no 74 dated 22/02/2024.

Keeping in view of the deemed compliance of the minimum standard on fire prevention and fire safety measures as required under the rules, the FSC issued vide letter no F6/DPS/MS/School/2021/SZ/221 Dt. 12/03/2021, renewal under rule 37 of the Delhi Fire Service rules, 2010 is recommended.

Accordingly, DFA is put up for approval and signature please.

Manoj Kumar Sharma
Signature of the Inspecting Officer
Name: Sh. Manoj Kumar Sharma
Design: DO (South)

Sh. Rajesh Kumar
Signature of the Inspecting Officer
Name: Sh. Rajesh Kumar
Design: ADO (BCP)

CFO (HQ)

Manoj
22/02/2024

Director
20/07/20

Manoj
20/07/20

Manoj
20/07/20

As approved, F.T letter is put up for your signature pl.

Manoj
28/3/2024