



**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI-110001**

No. F.6/DFS/MS/Audi/2024/SZ/266

Dated: 29/04/2024

**FIRE SAFETY CERTIFICATE**

Certified that the **Sirifort Auditorium Complex** (Audi-1, 2, 3 & 4) at August Kranti Marg, New Delhi-110049, comprised of Basement, Ground & 1<sup>st</sup> Floor only, owned/occupied by Directorate of Film Festivals has already been issued Fire Safety Certificate by this office vide letter No. F6/DFS/MS/2021/SZ/Audi/129 dated 18/02/2021. The premises was re-inspected by the officers concerned of this department on 22/04/2024 in the presence of Sh. Om Prakash (AE-P) and Sh. Mahipal (AE-E) and observed that the said premises have deemed complied with the fire prevention and fire safety requirements in accordance with rule 33 of the Delhi Fire Service Rules, 2010 and that the building/premises is fit for occupancy class "**Assembly Group-D**" (Auditorium) for a period of **three years** from the date of issuance in accordance with rule 36 unless renewed under rule 37 or sooner cancelled under Rule 40 and subject to compliance of conditions under 38 of the Delhi Fire Service Rules, 2010.

Issued on 29/04/2024 at New Delhi by

  
(ATUL GARG)  
DIRECTOR  
DELHI FIRE SERVICE  
at NB

Copy to: -

1. The Deputy Director, National Film Development Corporation Limited (A Government of India Enterprises), 4<sup>th</sup> Floor, Sookhana Bhawan, Phase-1, C.G.O. Complex, Lodhi Road, New Delhi-110003
2. The Joint Commissioner of Police (Lic), 1<sup>st</sup> Floor, Police Station Defence Colony, New Delhi-110049

**Conditions for the validity of Fire Safety Certificate:**

1. All the means of escape/entry/exit shall be kept free from any obstruction.
2. All the fire safety arrangement provided therein shall be maintained in good working conditions at all time as seen during inspection. Any loss of life property due to non-functional fire safety measures shall be at the responsibility of the management.
3. The trained fire-fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc. shall be got verified by the concerned building sanctioning agency.
5. This fire safety certificate cannot be treated in any case for regularization of unauthorized construction
6. The owner/occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on [www.dfs.delhigovt.nic.in](http://www.dfs.delhigovt.nic.in)
7. "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".

## INSPECTION REPORT

1.	Name & address of the building	Sirifort Auditorium Complex (Audi-1, 2, 3 & 4) at August Kranti Marg, New Delhi-110049		
2.	Type of Occupancy	Assembly		
3.	Composition of building	Basement (Storage & Services), Ground + 01 upper floor (Audi-1 having 1865 seats at ground & first floor balcony, Audi-2 having 72 seats at ground floor only), Audi-1, 3 & 4 are in same interconnected block and Audi-2 is in separate block. Both blocks are having basement but not interconnected.		
4.	Type of Case	Renewal		
5.	Details of previous NOC	F6/DFS/MS/2021/SZ/Audi/129 dtd 18/02/2021		
6.	Fire Safety directives Letter No	Nil		
7.	Date of inspection	22/04/2024		
8.	Name of the Inspecting Officer	Manoj Kumar Sharma (DO/SD) and Santosh Kumar (ADO/SJ)		
9.	Name and Designation of Officers from the building side	Sh. Om Prakash (AE-P) Sh. Mahipal (AE-E)		
10.	Year of Construction	1982		
11.	Applicant's letter No.	Outdoor dairy No. 363 dated 08/04/2024		
S. No.	Minimum standards on fire prevention and fire safety U/R 33	Requirements/ Existing Fire Protection System	Provided at site	Remarks MR/NMR
1.	Access of building			
	• Road width	9m	15m	MR
	• Gate width	5m	5m	MR
	• Width of internal road	N/A	N/A	N/A
2.	Number, width, Type & Arrangements of exits			
	a. Number of staircases			
	• Upper floors	08 nos.	Provided	MR
	• Basements	06 nos.	Provided	MR
	b. Width of staircases			
	• Upper floors	1.5m	1.5m (each)	MR (old case)
	• Basements	1.5m	1.5m (each)	MR (old case)
	c. Protection of exits			
	• Fire check door	Required	Provided	MR
	• Pressurization	N/A	N/A	N/A
	d. No of continuous staircase to terrace	02nos	02nos	MR
	e. Width Of Corridor	N/A	N/A	N/A
	f. Door Size	Required	Audi-1: 7 at GF & 8 at Balcony, Audi-2: 4 at GF, Audi-3: 2 at GF & 2 at FF (Balcony), Audi-4: 2 at GF level (Each exit is 1.35m wide)	MR (Old Case)
3.	Compartmentation			
	• Fire check door	Required	Provided	MR
	• Sealing of electrical shafts	Required	Provided	MR
	• Fire Rating of shaft door	N/A	N/A	N/A
	• Water Curtain	N/A	N/A	N/A
	• Fire Dampers	N/A	N/A	N/A
4.	Smoke managements System			
	• Basements	30 ACPH	Exhaust fan provided	MR
	• Upper floors	12 ACPH	Exhaust fan provided	MR
5.	Fire Extinguishers			
	• Total numbers		200 nos.	MR
	• Types		ABC, W.CO <sub>2</sub> & CO <sub>2</sub>	MR
	• ISI marking	ISI marked	Provided	MR
6.	First-Aid Hose Reels			
	• Total numbers on each floor		2nos at Basement, 9nos at GF & 4nos at 1 <sup>st</sup> Floor	MR
	• Length of hose reel hose	Hose-reel	30m	MR
	• Nozzle diameter		5mm	MR

88

7.	Automatic fire detection and alarming system			MR
	<ul style="list-style-type: none"> <li>Type of detector</li> <li>Location of Main Panel</li> <li>Location of Repeater Panel</li> <li>Alternate source of power</li> <li>Hooters' Location</li> </ul>	Smoke, Heat & Beam	Provided & functional	MR
		Gd. floor	Ground floor	MR
		N/A	N/A	N/A
		Required	Provided	MR
		All Areas	Provided	MR
8.	MOEFA/MCPs	Required	Provided	MR
9.	Public Address System	Required	Provided	MR
10.	Automatic Sprinkler System			
	<ul style="list-style-type: none"> <li>Basements</li> <li>Upper Floor</li> <li>Sprinkler above false ceiling</li> </ul>	Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
11.	Internal Hydrants			
	<ul style="list-style-type: none"> <li>Size of riser/down- comer</li> <li>Number of hydrants per floor</li> <li>Hose Box</li> </ul>	150mm	150mm	MR
		Required	02nos at Basement, 09nos at GF & 04nos at 1 <sup>st</sup> Floor	MR
		Required	02nos at Basement, 09nos at GF & 04nos at 1 <sup>st</sup> Floor	MR
12.	Yard Hydrants			
	<ul style="list-style-type: none"> <li>Total number of hydrants</li> <li>Hose Box</li> </ul>	10 nos.	10 nos.	MR
		10 nos.	10 nos.	MR
13.	Pumping Arrangements			
	<ul style="list-style-type: none"> <li>Ground Level                             <ul style="list-style-type: none"> <li>Discharge of main pump</li> <li>Head of main pump</li> <li>Number of main pumps</li> <li>Jockey pump out put</li> <li>Jockey pump head</li> <li>Standby Pump out put</li> <li>Standby Pump Head</li> <li>Auto Staring/Manual stopping</li> <li>Pump House Access</li> </ul> </li> <li>Terrace level                             <ul style="list-style-type: none"> <li>Discharge of pump</li> <li>Head of the pump</li> <li>Power supply</li> <li>Auto starting of pump</li> </ul> </li> </ul>			
		2280 LPM	2280 LPM	MR
		55m	55m	MR
		02 nos.	02 nos.	MR
		225 LPM	225 LPM	MR
		55m	55m	MR
		2280 LPM	2280 LPM (Electrical)	MR
		55m	55m	MR
		Required	Provided	MR
		Required	Provided	MR
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
	NA	NA	NA	
14.	Captive water Storage for fire fighting			
	<ul style="list-style-type: none"> <li>Underground tank capacity                             <ul style="list-style-type: none"> <li>Draw of connection</li> <li>Fire service inlet</li> <li>Access to tank</li> </ul> </li> <li>Overhead Tank capacity</li> </ul>	100,000 Ltrs	100,000 Ltrs	MR
		Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
		20,000 Ltrs	20,000 Ltrs	MR
15.	Exit Signage	Required	Provided	MR
16.	Provision of Lifts			
	<ul style="list-style-type: none"> <li>Pressurization of Lift Shaft</li> <li>Pressurization of lift lobby</li> <li>Communication in lift Car</li> <li>Fireman's Grounding Switch</li> <li>Lift Signage</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A
		Required	Provided	MR
		Required	Provided	MR
		Required	Provided	MR
17.	Standby power supply	Required	Provided	MR
18.	Refuge Area			
	<ul style="list-style-type: none"> <li>Total area</li> <li>Location</li> </ul>	N/A	N/A	N/A
		N/A	N/A	N/A

SP

Fire control room		Required	Provided	
19.	> Detector system panel	Required	Provided	MR
	> Flow Switch Panel	N/A	N/A	N/A
	> PA System Panel	Required	Provided	MR
	> Battery backup	Required	Provided	MR
	> Building Floor Plans	N/A	N/A	N/A
20.	Special Fire Protection Systems for Protection of special Risks, if any;	CO <sub>2</sub> flooding system provided for electric sub-station & transformer room.		MR

The fire protection systems provided in the premises were checked, tested at random and found functional at the time of inspection. The shortcomings earlier communicated vide this department letter No. F.6/DFS/MS/2024/SZ/52 dated 15/02/2024 found complied.

Keeping in view of the deemed compliance of the minimum standards on fire prevention and fire safety measures as required under the rules, the fire safety certificate issued vide letter No. F6/DFS/MS/2021/SZ/Audi/129 dated 18/02/2021, renewal under rule 37 of the Delhi Fire Service Rules, 2010 is recommended.

Accordingly, DFA is put up for approval and signature please.

*Manoj*  
 Signature of the Inspecting Officer  
 Name: Manoj Kumar Sharma  
 Designation: DO (SD)

*Santosh*  
 Signature of the Inspecting Officer  
 Name: Santosh Kumar  
 Designation: ADO (SJ)

CFO (HO)  
*[Signature]*  
 24/11/2024

Director  
*[Signature]*  
 24/11/24

*[Signature]*  
 ADO/SJ

Sir,  
 F.T letter is prout for your sing. pl

*Santosh*  
 29/09/24

Director  
*[Signature]*  
 29/11/24

*Manoj*