

C-77

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEADQUARTERS: DELHI FIRE SERVICE, NEW DELHI-110001**

No. F6/DFS/MS/2024/Hospital/WZ/ 644

Dated: 22/10/2024

**FIRE SAFETY CERTIFICATE**

Certified that the **Bhagwati Hospital** located at **CS/OCF-6, Sector-13, Rohini, Delhi-110085**, comprised of **Basement + Ground + Three upper floors** owned / occupied by (A unit of **Sarvodaya Health Foundation, Delhi**) has already been issued FSC by this department vide letter No. **F.6/DFS/MS/2021/WZ/495** dated **11.10.2021**. The premises was re-inspected by the officer concerned of this department on **25.07.2024** in the presence of **Dr. Naresh Pamnani (Medical Superintendent)** and observed that all the prevention and fire safety arrangements provided in the premises found in good working condition. The premises have therefore deemed complied with the fire prevention and fire safety requirements in accordance with Rule 33 of the Delhi Fire Service Rules, 2010 and that the premises fit for occupancy class (**Hospital**) with effect from 22/10/2024 for a period of **three years** in accordance with Rule 36 unless renewed under Rule 37 or sooner cancelled under Rule 40 and subjected to compliance of the conditions under Rule 38 of the Delhi Fire Service Rules, 2010.

Issued on 22/10/2024 at New Delhi by

  
(A. Garg)  
**DIRECTOR**  
Ph: 011-23414000

Copy to :-

1. Dr. Naresh Pamnani (Medical Superintendent), Bhagwati Hospital located at CS/OCF-6, Sector-13, Rohini, and Delhi-110085.

**Conditions for the validity of fire safety certificate:**

1. All the fire safety arrangement provided there-in shall be maintained in good working conditions at all times.
2. Loss of life or property due to non functional fire safety measure shall be at the responsibility of the management.
3. The trained fire fighting staff should be available round the clock.
4. Any deviation with regard to the construction etc shall be verified by the concerned building sanctioning agency.
5. This certificate cannot be treated in any case for regularizations of unauthorized construction.
6. The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director of Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".
7. The owner / occupier shall submit a declaration every year in form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on
8. All the means of escape shall be kept free of any obstruction all the time to evacuate the occupant, in a safe manner, in the event of emergency.

[http://www.delhi.gov.in/wps/wcm/connect/doit\\_fire/FIRE/Home/Fire+Safety+Acts+and+Ru](http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Fire+Safety+Acts+and+Rules/)  
[les/ http://www.delhi.gov.in/wps/wcm/connect/doit\\_fire/FIRE/Home/Forms](http://www.delhi.gov.in/wps/wcm/connect/doit_fire/FIRE/Home/Forms)



**INSPECTION REPORT**

1. Name & address of the building : Bhagwati Hospital CS/OCF-6, Sec-13, Rohini, Delhi-110085.
2. Type of Occupancy : Institutional (Hospital)
3. Type of Case : Renewal (Basement + Ground + 3 upper floors)
4. Details of Previous NIOC : F.6/DFS/MS/2021/WZ/495 dated 11.10.2021.
5. Fire Safety directives letter No : F.6/DFS/MS/BP/Hospital/99/1377 dated 11.10.2021.
6. Date of inspection : 25.07.2024.
7. Name of Inspecting Officer : A.K.Sharma ADO(Rohini)
8. Name and designation of officers  
From the building side : Dr. Naresh Pannani (Medical Superintendent)
9. Year of Construction : 2003
10. Applicant's letter No. : OD No.4079 dated 11.07.2024.

| S. No.   | Minimum Standards on fire prevention and fire safety U/R 33 | Rule 35(6)      | Provided at site     | Remarks MR/NMR |
|--|---|-----------------|----------------------|----------------|
| <b>1. Access to building</b>                             |   |                 |                      |                |
|  | • Road width  | Accessible      | Accessible           | MR             |
|  | • Gate width  | Accessible      | 5.0m                 | MR             |
|  | • Width of internal road                                    | NA              | NA                   | NA             |
| <b>2. Number, Width, Type &amp; Arrangement of Exits</b> |   |                 |                      |                |
| g. Number of staircases                                  |   |                 |                      |                |
|  | • Upper Floors  | 02nos.          | 02nos.               | MR             |
|  | • Basements   | 1, 1 (ramp)     | 1, 1 (ramp)          | MR             |
| h. Width of staircases                                   |   |                 |                      |                |
|  | • Upper Floor   | 2.0m            | 2.0m & 1.10m         | MR(Old case)   |
|  | • Basements   | 2.0m            | 1.80m & ramp 2.0m    | MR(Old case)   |
| i. Protection of exits                                   |   |                 |                      |                |
| Fire check door  |   |                 |                      |                |
|  | • Pressurization  | Required        | Provided             | MR             |
|  |   | -NA-            | -NA-                 | -NA-           |
| d. No. of continuous staircases to terrace               |   |                 |                      |                |
|  |   | 02nos.          | 02nos.               | MR             |
| c. Width of Corridor                                     |   |                 |                      |                |
|  |   | 2.0m            | 1.30 m to 2.0 m      | MR(Old case)   |
| f. Door Size   |   |                 |                      |                |
|  |   | 1.0m            | 1.0m                 | MR (Old case)  |
| <b>3. Compartmentation</b>                               |   |                 |                      |                |
|  | • Fire check door   | Required        | Provided in basement | MR             |
|  | • Sealing of electrical shafts                              | Required        | Provided             | MR             |
|  | • Fire Rating of shaft door                                 | -NA-            | -NA-                 | -NA-           |
|  | • Water Curtain   | -NA-            | -NA-                 | -NA-           |
|  | • Fire Dampers  | -NA-            | -NA-                 | -NA-           |
| <b>4. Smoke Management System</b>                        |   |                 |                      |                |
|  | • Basements   | 30 a/c per hour | Exhaust fan provided | MR             |
|  | • Upper floors  | -NA-            | -NA-                 | -NA-           |
| <b>5. Fire Extinguishers</b>                             |   |                 |                      |                |
|  | • Total numbers   | 20nos.          | 52nos.               | MR             |
|  | • Types   | ABC/CO2         | ABC/CO2              | MR             |
|  | • IS marking  | ISI marked      | Yes                  | MR             |
| <b>6. First-Aid Hose Reels</b>                           |   |                 |                      |                |
|  | • Total numbers on each floor                               | 01nos.          | Provided             | MR             |
|  | • Length of hose reel hose                                  | 30mm            | Provided             | MR             |
|  | • Nozzle diameter   | 5m              | Provided             | MR             |
| <b>7. Automatic fire detection and alarming system</b>   |   |                 |                      |                |
|  | • Type of detectors   | Smoke           | Provided             | MR             |
|  | • Location of Main Panel                                    | Gr. floor       | Provided             | MR             |
|  | • Location of Repeater Panel                                | -NA-            | -NA-                 | -NA-           |
|  | • Alternate source of power                                 | Required        | Provided             | MR             |
|  | • Hoopsters' Location                                       | Required        | Provided             | MR             |

*Signature*

|    |  |              |              |      |
|----|--|--------------|--------------|------|
| 8. | <b>MOEFA</b>                                   | Required     | Provided     | MR   |
| 9. | <b>Public Address System</b>                   | Required     | Provided     | MR   |
| 10 | <b>Automatic Sprinkler System</b>              |              |              |      |
|    | • Basement                                     | Required     | Provided     | MR   |
|    | • Ground & Upper Floors                        | -NA-         | -NA-         | -NA- |
|    | • Sprinkler above false ceiling                | -NA-         | -NA-         | -NA- |
| 11 | <b>Internal Hydrants</b>                       |              |              |      |
|    | • Size of riser/down-comer                     | -NA-         | -NA-         | -NA- |
|    | • Number of hydrants per floor                 | -NA-         | -NA-         | -NA- |
|    | • Hose Box                                     | -NA-         | -NA-         | -NA- |
| 12 | <b>Yard Hydrants</b>                           |              |              |      |
|    | • Total number of hydrants                     | -NA-         | -NA-         | -NA- |
|    | • Hose Box                                     | -NA-         | -NA-         | -NA- |
| 13 | <b>Pumping Arrangements</b>                    |              |              |      |
|    | • Ground Level                                 | -NA-         | -NA-         | -NA- |
|    | ➤ Discharge of main Pump                       | -NA-         | -NA-         | -NA- |
|    | ➤ Head of Main pump                            | -NA-         | -NA-         | -NA- |
|    | ➤ Number of main pumps                         | -NA-         | -NA-         | -NA- |
|    | ➤ Jockey Pump out put                          | -NA-         | -NA-         | -NA- |
|    | ➤ Jockey pump head                             | -NA-         | -NA-         | -NA- |
|    | ➤ Standby Pump out put                         | -NA-         | -NA-         | -NA- |
|    | ➤ Standby Pump Head                            | -NA-         | -NA-         | -NA- |
|    | ➤ Auto Starting/Manual Stopping                | -NA-         | -NA-         | -NA- |
|    | ➤ Pump House Access                            | -NA-         | -NA-         | -NA- |
|    | • Terrace level                                |              |              |      |
|    | ➤ Discharge of pump                            | 450 & 180lpm | 450 & 180lpm | MR   |
|    | ➤ Head of the pump                             | 40m          | 40m          | MR   |
|    | ➤ Power Supply                                 | Required     | Provided     | MR   |
|    | ➤ Auto Starting of pump                        | Required     | Provided     | MR   |
| 14 | <b>Captive Water Storage for fire fighting</b> |              |              |      |
|    | • Underground tank capacity                    | 25,000ltr    | 25,000ltr    | MR   |
|    | ➤ Draw-off connection                          | -NA-         | -NA-         | -NA- |
|    | ➤ Fire service inlet                           | -NA-         | -NA-         | -NA- |
|    | ➤ Access to tank                               | -NA-         | -NA-         | -NA- |
|    | • Overhead Tank capacity                       | 12,500ltr    | 15,500ltr    | MR   |
| 15 | <b>Exit Signage.</b>                           | Required     | Provided     | MR   |
| 16 | <b>Provision of Lifts.</b>                     |              |              |      |
|    | • Pressurization of Lift Shaft                 | -NA-         | -NA-         | -NA- |
|    | • Pressurization of Lift lobby                 | -NA-         | -NA-         | -NA- |
|    | • Communication In lift Car                    | Required     | Provided     | MR   |
|    | • Fireman's Grounding Switch                   | Required     | Provided     | MR   |
|    | • Lift Signage                                 | Required     | Provided     | MR   |
| 17 | <b>Standby power supply</b>                    | Required     | 2 X 750 kva  | MR   |
| 18 | <b>Refuge Area.</b>                            |              |              |      |
|    | ➤ Total Area                                   | -NA-         | -NA-         | -NA- |
|    | ➤ Location                                     | -NA-         | -NA-         | -NA- |
| 19 | <b>Fire Control Room</b>                       |              |              |      |
|    | • Detector System Panel                        | Required     | Provided     | MR   |
|    | • Flow Switch Panel                            | -NA-         | -NA-         | -NA- |
|    | • PA System Panel                              | Required     | Provided     | MR   |
|    | • Battery backup                               | Required     | Provided     | MR   |
|    | • Building Floor Plans                         | -NA-         | -NA-         | -NA- |

any



MR

Special Fire Protection System for Protection of special Risks, if any:

-NA-

-NA-

-NA-

The fire protection systems provided in the building were test checked & tested randomly and found on terrace shall be used for storage of record only as applicant submitted undertaking that it will not be used for human occupancy.

In view of the deemed compliance of the minimum standards of the fire prevention and fire safety measures as required under the rules the NOC issued vide letter no. F.6/DFS/MS/2021/WZ/495 dated 11.10.2021 is recommended for renewal under rule 37 of the Delhi Fire Service rules 2010

*[Signature]*  
29/7/24

Signature of the Inspecting Officer  
Name Ajay Kumar Sharma  
Designation ADO (Rohini)

DO (NW)

*[Signature]*  
31/07/2024

Dy CFO (W3)

*[Signature]*  
01/8/2024

CFO

Please speak for FSC condition NO 9. (terrace)<sup>UR</sup>

*[Signature]*  
2/8/2024

Dy CFO (W2)

Spoken with CFO on 2/8/24 and it was discussed to issue shortcoming for point no-9. Submitted for approval please.

Do (NW) - short coming is not put up in file  
*[Signature]*  
06/08/2024

*[Signature]*  
5/8/24

Dy CFO (W2)

Where is shortcoming?

*[Signature]*  
7/8/2024

DO (NW)

*[Signature]*  
09/08/2024

DCFO/136  
Dated: 21/8/2024

DCFO/136  
Dated: 7/8/2024