

20/10/24
 P. Singh on website
 4/10/24

Delhi Jal Board
 Office of Additional CEO
 Delhi Jal Board, Varunalaya Phase-II, Jhandewalan
 New Delhi-110005

No.DJB/Addl.CEO/2024-5098/

Dated : 01-10-2024

INSTRUCTIONAL ORDER

This order outlines the procedures to be followed immediately for temporary road restoration to ensure smooth coordination with other land-owning agencies such as MCD, PWD, DDA, and others for strict compliance :

1	Pre-Restoration Coordination	Ensure all necessary permissions and clearances are obtained from relevant authorities before commencing any road restoration work. Coordinate with other land-owning agencies to schedule the restoration work, ensuring minimal disruption to their planned activities.
2	Materials & Environment impact.	The trench cut for laying of pipes shall be filled up with good earth/appropriate material in 20 cm layers and each layer to be well compacted with appropriate means/roller to have desired compacted density. Use maximum environmentally friendly materials and methods for restoration to reduce the environmental impact. Road owning agency will reconstruct the road with metallic carpet/CC as per road norms.
3	Proper Compaction	Ensure that the backfill is properly compacted to prevent future settling, which can complicate permanent restoration efforts. The field staff will ensure proper compaction by visiting the site regularly. The field staff to certify that the filling and compaction has been done as per applicable CPWD specifications & there will not be any settlement in future. Non execution of work as per prescribed specification will attract strict action against the executing agency including black listing.

Chief Engineer (IT)
 Delhi Jal Board, GNCTD

Dy. No. 561 dt 04/10/2024

CE (IT)

P. Singh
 Dy. Dir. 01/10/24
 Delhi Jal Board, GNCTD
 Room No. 501, Varunalaya
 Phase-II, Karol Bagh, New Delhi-110005

1269 07/10/24

5	Coordination with land owning agencies	Communicate and coordinate with LOG to align on the temporary restoration standards and future plans for permanent restoration.
6	Safety Measures	Implement safety measures such as proper barricading and signage to protect the temporary restoration area and ensure public safety.
7	Minimal Disruption	Plan the temporary restoration to minimize disruption to traffic and pedestrians, ensuring that the area remains accessible until permanent restoration is completed.
8	Regular Inspections	Conduct regular inspections of the road restoration to identify and address any issues promptly, ensuring that the area remains safe and functional until permanent restoration.

All CEs/SEs/EEs shall ensure that the above directives are strictly complied to ensure efficient and effective road restoration. Non-compliance will be subject to disciplinary action.

This issues with the approval of the Competent Authority:

CE Noida-II-Water Drainage

Cheshta

(Cheshta Yadav, IAS)
Additional CEO

Copy to :-

1. CEO, DJB- for kind information
2. Member (A)-for kind information
3. All CEs(Civil)/SEs(Civil)/EEs(Civil)

Cheshta

Additional CEO