

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE: NEW DELHI- 110001**

No. F.6/DFS/MS/Hospital/2021/NDZ/ 2004

Dated: 29/09/2021

To,

Dr. Kulvinder Singh Kochar,  
Medical Superintendant,  
Shanti Mukand Hospital,  
2, Institutional Area, Vikas Marg Extn.,  
Karkardooma, Delhi-110092


**Subject:- Renewal of Fire Safety Certificate.**

Sir,

With reference to letter no. SMH/Admn/2021 dated 17/08/2021 on the subject cited above, it is informed that officer concerned of this department inspected the building on, it was noted that the shortcomings issued vide letter No. F.6/DFS/MS/Hospital/2020/2960 dated 04/12/2020 and No. F.6/DFS/MS/Hospital/2021/NDZ/1496 dated 30/07/2021 have not been complied as yet (The copy of the same is enclosed for reference).

In view of the above Fire Safety Certificate cannot be considered at this stage. Therefore, you are once again requested to rectify the said shortcoming under intimation to this office for further consideration in the matter.

Yours Faithfully,



(Dr. S. K. Tomar)  
Dy. Chief Fire Officer

1109

**GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI**  
**HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE**  
**NEW DELHI- 110 001**

No. F6/DFS/MS/<sup>Hospital</sup>School/2020/NDZI

2960

Dated: 07/11/2020

To

Medical Superintendent,  
M/s Shanti Mukand Hospital,  
Plot no. 2, Institutional Area Vikas Marg Extn.,  
Delhi-110092.

**Sub:- Regarding Issuance of Fire Safety Certificate in r/o M/s Shanti Mukand Hospital, Plot no. 2, Institutional Area Vikas Marg Extn., Delhi-110092.**

Sir,

This is in reference to your letter No. SMH/Adm/2020/8562 dated 23/10/2020 on the subject cited above. In this connection, it is to inform you that the team of officer of this department have carried out the inspection of the above mentioned hospital from fire safety point of view in presence of Dr. Mohan Dubey(DMS). During the course of inspection, the following points / shortcomings were noticed in the building comprised of basement, ground plus four upper floors.

1. Temporary structure constructed in front set back to be removed.
2. Exit signage not provided.
3. PA system not audible in basement & having poor audio quality needs to be improve.
4. Detector & MCP not provided in Lift Machine Room.
5. Fibre sheet wherever used to be removed.
6. Hose reel hose not covering whole area needs to be extended at each floor.
7. Sprinkler not provided at 1<sup>st</sup> floor.
8. Detector & sprinkler not provided in store.
9. Down comer/ wet riser not provided in basement.
10. Smock Management Ventilation not provided in basement.

In view of above, the building can not be considered for issue of Fire Safety Certificate at this stage. Therefore you are suggested to rectify the above mentioned shortcomings under the intimation to this department for further course of action.

Yours faithfully

(Atul Garg)  
Director