

GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI  
HEADQUARTERS: DELHI FIRE SERVICE: CANNAUGHT PLACE  
NEW DELHI- 110 001

No.F6/DFS/MS/Hospital/2022/SZ/ 1943  
To,

Dated: 01/08/2022

Dr. Manish Kumar  
Tarak Hospital India Private Limited,  
C-7,Jai Bharat Enclave,DwarkaMore,  
Opposite metro pillar no.789, New Delhi-110059.

**Sub:** - Regarding issue of "Fire Safety Certificate" from fire safety point of view in r/o M/s Tarak Hospital India Private Limited,C-7,Jai Bharat Enclave,DwarkaMore, Opposite metro Pillar No.789, New Delhi-110059.

Sir,

Please refer to your letter No.Nil dated 06 /07/2022on the subject cited above. In this connection this is to inform you that officer concerned of this department inspected the hospital building to verify the fire safety arrangements in accordance with the fire safety guidelines issued vide letter No.F6/DFS/MS/ BP/2021/2121 dated 12/10/2021. At the time of inspection Sh. Arun Kumar was present and it was observed that the hospital building is comprised of basement, ground plus four upper floors and have following shortcomings: -

1. There are only one staircase of 2 m width is provided in basement one more staircase is required of 1.5 meter. Both staircase should be widen to 2 m clear width for upper floors as per guidelines.
2. Width of corridor is 2.10 m provided in place of 2.40 m.
3. Door width of patient rooms is 1 m provided in place of 1.25 m.
4. Fire check door not provided.
5. Smoke Management System not provided in basement.
6. First aid hose reel provided but not functional/Hose reel not provided at 4<sup>th</sup> & 2<sup>nd</sup> floor.
7. Automatic sprinkler system & detector system is not fully covered.
8. Internal hydrant provided but not functional/Hydrant not provided at 4<sup>th</sup> & 2<sup>nd</sup> floor.
9. Main Fire pump capacity of 2280 LPM, Standby pump 2280 LPM & Jockey pump 180 LPM output 60 m head not provided.
10. Under ground water storage tank capacity of 2, 00,000 liters not provided.
11. Exit signage's are provided but not sufficient.
12. Buildings are not connected at 3<sup>rd</sup> floor.
13. The staircase is constructed around the lift shaft which is not allowed as per clause 7.11(c) of UBBL-2016.

In view of above, the fire safety certificate cannot be considered at this stage. You are requested to rectify the above shortcoming under the intimation to this department for further course of action. You are also hereby advised not to use the building till you provide required fire safety arrangements as per law.

Yours faithfully,

(Arun Garg)

**Director**

Delhi Fire Service

Copy to:-

The Directorate of Health Services,  
M.O./C Nursing Home Cell,  
S-1, School Block, Shakarpur Delhi-110092.